

ADDENDUM 001 Request for Bid Bunker Mechanics Building RFB 9-170317SB

Bidders should acknowledge receipt of Addendum 001 (ONE) by signing and including it with the original bid. The due date for receipt of bids **has not** changed by this Addendum; the due date is **March 17, 2017 2:00 PM Central Time**. Accordingly, the following clarifications, and or additional information, are believed to be of general interest to all potential bidders. All other terms and conditions remain unchanged and in full force.

Name and Title of Signer (Print or type)	Name and Title of Department Authority Shannon Branson General Services Specialist
Contractor/Offeror Signature (Signature of person authorized to sign)	Department of Transportation <i>Shannon Branson</i> (Authorizing Signature)
Date Signed:	Date Signed: 3/9/17

Delete the following:

Current Site Note E:

Contractor to install 4" schedule 40 pvc sanitary sewer line to the existing sanitary line exiting from existing maintenance building for an operable service, abandon old sanitary line and septic tank.

Replace with the following:

NEW Site Note E:

Contractor to install 4" schedule 40 pvc sanitary sewer line to the existing sanitary line exiting from existing maintenance building for an operable service.

CORRECTION on SHEET 2:

Contractor to eliminate sanitary line from Route A to 5 (five) feet south of concrete slab in front of new Mechanics Building.



CORRECTION:

Replace-Time of Completion

If this bid is accepted, it is hereby agreed that work will begin no later than the date specified in the "Notice to Proceed" and will diligently be prosecuted in order to complete the work by **June 8, 2017**. Completion of work will be based on FINAL ACCEPTANCE of the building; "SUBSTANTIAL COMPLETION" will not be accepted as basis for completion.

With the following:

Time of Completion

If this bid is accepted, it is hereby agreed that work will begin no later than the date specified in the "Notice to Proceed" and will diligently be prosecuted in order to complete the work by **August 18th, 2017**. Completion of work will be based on FINAL ACCEPTANCE of the building; "SUBSTANTIAL COMPLETION" will not be accepted as basis for completion.

Addition

Contractor to install either concrete or fiberglass pit (size as required) with lid. Bottom to be lined with rock. Contractor to install one shut off valve going to existing 2" hydrant and one shut off valve going to new 2" service to new building inside the pit.

QUESTIONS

Question 1: What material is the existing 2" water line?:

Answer: Water line is 2" PVC schedule 40.