

Missouri Department of Transportation
Roberta Broeker, Interim Director

573.751.2551
Fax: 573.751.6555
1.888.ASK MODOT (275.6636)

ADDENDUM 001 Request for Bid Vienna Maintenance Building RFB 9-151119KH

Bidders should acknowledge receipt of Addendum 001 (ONE) by signing and including it with the original bid. The due date for receipt of bids **has not** changed by this Addendum; the due date is **November 19, 2015 2:00 PM Central Time**. Accordingly, the following clarifications, and or additional information, are believed to be of general interest to all potential bidders. All other terms and conditions remain unchanged and in full force.

Name and Title of Signer (Print or type)	Name and Title of Department Authority Kristi Hixson General Services Senior Specialist
Contractor/Offeror Signature (Signature of person authorized to sign)	Department of Transportation <i>Kristi Hixson</i> (Authorizing Signature)
Date Signed:	Date Signed: 11/10/2015

Plan Sheet:

- Sheet 2 Revise the sixth Grading Note to read: Provide 5" minimum 1" minus rock on West of approach pad and south side of new building after construction up to 15'-0". Provide adequate amount of top soil, starter fertilizer, Triple 'T' seed and straw up to 15'-0" on North and East sides of the new building. Contour to drain away from building.
- Sheet 13 Details E & J-13. The Contractor will need to block out as required at 10" concrete stem wall for the garage door track at jambs. Typical.
- Sheet 14 HVAC Schedule, 'G' in Remarks change the lateral duct kit model number to PDXDAA.



Sheet 20 The Sub-Panel (SP) will be mounted below the Service Panel LPB. The conductors in conduit are all to be copper from the power pole to the Main Distribution Panel. MoDOT to have meter on pole before construction begins and the Contractor's work is to begin from meter.

Sheet 2 and Sheet C-301 Sheet 2, Site Note E estimates 38.6 cubic yards of rock to be encountered. Sheet C-301, General Notes 3 estimates 10 cubic yards of rock to be excavated. **Add** an estimated 6.4 cubic yards of rock to be excavated. These added together equals a total of 55 cubic yards of rock estimated to be excavated.

Specifications:

Section 15500 Heating & Ventilating & Air Conditioning. There is no return ductwork (plenum return) so the insulation isn't required. All supply ducts to get the 1" thick fiberglass blanket on the exterior of ductwork and no acoustical duct liner.

Section 12512 Horizontal Louver Blinds, Edit to read: Provide horizontal metal slat louver blinds at each exterior window in rooms 103, 107, 108, 109 & 110 only.

Annual Wage Order:

Updated Annual Wage Order – Maries County (separate attachment)

Questions:

Question: Where wall type B-11 butts into columns 3D and 3A, does the wall framing & furring and metal panels go around column or just butt into the column?

Answer: Butts into the column.

Question: Where wall type B-11 butts into the overhead beam, does the framing & furring and met panels go around and over the face of the beam or just butt up to the bottom of the beam?

Answer: Butts into the beam.

Question: Has a ceiling tile model number been selected? If so what is it?

Answer: Model number has not been selected. It will be approved in the submittal process. The ceiling tile must meet the ASTM E1264 requirement.