



Pete K. Rahn, Director



2007 Missouri Quality Award Winner

January 9, 2008

**Addendum No. 002
9-080117**

To: Plans and Specifications Holders List for:

Missouri Department of Transportation –
DISTRICT-5 Pre-Engineered Metal Building & Site Work – Cole Camp, MO

IN THE SPECIFICATIONS

Section 02220, EXCAVATING, BACKFILLING AND COMPACTING. Change paragraph 3.4 EXCAVATING to read:

- E. Excavation of rock:
1. Where rocks, boulders, granite, or similar material is encountered, and where such material cannot be removed or excavated by conventional earth moving or ripping equipment, take required steps to proceed with the general grading operations of the Work, and remove or excavate such material by means which will not endanger buildings or structures whether on or off the site.
 2. Do not use explosives without written permission from the Architect.

Section 08351, OVERHEAD COILING DOORS. Add to Part 2 PRODUCTS, 2.1 OVERHEAD COILING DOORS A. to read: 12. Track. Galvanized.

Section 08710, DOOR HARDWEAR, Change paragraph 3.5 Hardware A.5 to read:

5.	Hardware group 5:	Door #13			
	1-1/2	Hinges pr.	F179 4 1/2 x 4 1/2	US26D	Stanley
	1	Storeroom Lockset	93K-7-D-15D-S3-626	US26D	Yale = Best

Section 09971, FIBERGLASS WALL PANELS. Delete in PART 2 PRODUCTS, 2.1 WALL PANELS, paragraph A.

Delete Specification Section 13120 PRE-ENGINEERED FABRIC STRUCTURE.

Include in Specifications the following:

SECTION 11452

RESIDENTIAL APPLIANCES

PART 1 GENERAL

1.1 SECTION INCLUDES

- A. Refrigerator
- B. Upright Freezer

1.2 SUBMITTALS FOR INFORMATION

- A. Section 01300 - Submittals: Procedures for submittals.
- B. Manufacturer's Certificate: Certify that Products meet or exceed specified requirements.

1.3 DELIVERY, STORAGE, AND PROTECTION

- A. Section 01600 - Material and Equipment: Transport, handle, store and protect products.
- B. Accept appliances on site in manufacturer's packaging. Inspect for damage.

PART 2 PRODUCTS

2.1 TOP-MOUNT REFRIGERATOR

- A. Equal to Hotpoint 14 Cu. Ft. Top-Mount Refrigerator, Model CTX14CAX as manufactured by General Electric Company. (2 required)
 - 1. White on white.
 - 2. 14.4 cubic foot capacity.
 - 3. 3.86 cubic foot freezer.
 - 4. Automatic icemaker.

2.2 UPRIGHT FREEZER

- A. Equal to Hotpoint 20.3 Cu. Ft. upright freezer, Model FUF20DPRWH as manufactured by General Electric Company. (1 required)
 - 1. White on white.
 - 2. 20.3 cubic foot capacity.
 - 3. Frost Free

PART 3 EXECUTION

3.1 INSTALLATION

- A. Install in accordance with manufacturer's instructions.
- B. Install appliances plumb and square.
- C. Place and secure on prepared surfaces.
- D. Secure appliances with anchor devices to suit substrate materials.

3.2 CLEANING

- A. Clean appliances interiors and exterior surfaces.

END OF SECTION

IN THE DRAWINGS

Sheet 2, Site Plan. Site benchmark to be established and provided by MoDOT at time of pre-construction meeting.

Sheet 2, Site Plan. Contractor to provide 4" of topsoil over all lawn areas disturbed during construction.

Sheet 2, Site Plan. Note G indicates to see Sheet 20. Change to see Sheet 17.

Sheet 17, Spreader Rack and Fuel Pads. Detail D-17 indicates 4" Type 5 aggregate by MoDOT. Change to 4" Type 5 aggregate by Contractor.

ALL exterior walls to have a batt insulation value of R-25.

Remove the existing page 10 from the Blue Bid Book and replace with this new page 10.

**SECTION 00301
BID FORM**

To: The Missouri Highway and Transportation Commission
105 West Capitol Avenue
Jefferson City, Missouri 65101

1. The undersigned, having examined the proposed Contract Documents titled: **Proposal for Constructing the New Maintenance Building & Site Work, Benton County, Cole Camp, MO** and having visited the site and examined the conditions affecting the Work, hereby proposes and agrees to furnish all labor, materials, equipment and everything which may be necessary or incidental thereto, as proposed by said Contract Documents, all to the satisfaction of the Chief Engineer of the Missouri Department of Transportation and the Missouri Highway and Transportation Commission, for the stipulated sum of:

_____ DOLLARS (\$_____).

2. The undersigned, submits the following unit price:

Mass Rock excavation if encountered. \$_____ per cubic yard.

Trench Rock excavation if encountered. \$_____ per cubic yard.

Compactable fill as/if required under the New Maintenance and Future Fabric Salt Building. \$_____ per cubic yard.

3. The undersigned, acknowledges having examined and being familiar with the contract documents including the drawings, the Instructions to Bidders, General Conditions, Supplementary Conditions and the body of technical specifications.
4. The undersigned acknowledges receipt of Addenda number _____ through _____ inclusive.
5. Enclosed with this bid is bid security in the amount of not less than 5% of the bidder's proposed Contract Sum, the amount being _____ DOLLARS _____).

IF AN INDIVIDUAL

Name of individual

Residence address

Telephone Number

Social Security Number

Firm Name, If Any

Address for communications

Signature