



Pete K. Rahn, Director

**ADDENDUM #1
9-070328B**

March 15, 2007

To: Plans and Specifications Holders of List For:

**Missouri Department of Transportation - District #4, Concordia, Missouri, Roof Replacements,
Lafayette County.**

The following changes should be noted:

Note: This roof replacement project now includes both the East and West Bound Concordia Rest Areas. (Rt. 23, .1 Mi. N of I-70).

IN THE DRAWINGS

- Sheet 1 Change: Detail A-1 title to read – Two (2) Roofs, REST AREA ROOF PLANS
- Change: Detail B-1 title to read – Four (4) Roofs, CONCESSION/MAP CENTER ROOF PLANS
- Change: Detail C-1 title to read – Ten (10) Roofs, PICNIC TABLE ROOF PLANS
- Change: Detail B-1, Add – Contractor to provide 26 gauge prefinished steel gutters and
 downspouts. Gutters to be on all four sides. Two downspouts located on backside of each
 building per MoDOT field representative. Sizing of gutters and downspouts as required. Color
 picked by MoDOT. New gutters and downspouts on Concession roofs only.
- Sheet 2 Change: Note to read – MoDOT to remove the existing condensing unit before Contractor
 demolition and relocate after construction. MoDOT to make connections at the existing
 condensing unit for an operational system. MoDOT to provide sealants at all penetrations of the
 rooftop HVAC units only.
- Change: Note to read – MoDOT to bolt-mount condensing unit to MoDOT provided hot-dipped
 galvanized steel mounting frame. Angles to be 2" x 2" x 1/8". Stainless steel lag bolt (4) to new
 roof. MoDOT to apply sealant over bolts. Frame to be level. Field verify size.

Sincerely,

Sherry King
General Services - Facilities Management
573/522-5591
Sharon.King@modot.mo.gov

**All other terms and conditions of IFB 9-070328B remain unchanged
END OF SECTION**