

Missouri  
Department  
of Transportation



Kevin Keith, Director

105 West Capitol Avenue  
P.O. Box 270  
Jefferson City, MO 65102  
(573) 751-2551  
Fax (573) 751-6555  
[www.modot.org](http://www.modot.org)

November 10, 2010

**Addendum No. 001  
IFB 9-101123**

To: Plans and Specifications Holders List for:

**MISSOURI DEPARTMENT OF TRANSPORTATION: DISTRICT – 9, TRUCK WASH, STEELVILLE,  
MISSOURI**

THE BID OPENING DATE AND TIME: NOVEMBER 23, 2010 AT 3:00 P.M. LOCAL TIME.

In the Drawings replace all references to painting and replace with sealer product.

In the Bid and Specifications remove Section 09900 Painting, and refer to the Sealer specification in Section 4300, Unit Masonry System, 2.5.

Remove and replace Construction Facilities and Temporary Control Requirements, Section 01500 (3-pages) with the attached corrected section.

END SECTION

## CONSTRUCTION FACILITIES AND TEMPORARY CONTROL REQUIREMENTS

### PART 1 GENERAL

#### 1.1 SECTION INCLUDES

- A. Temporary Utilities: Electricity, telephone service, facsimile service and sanitary facilities.
- B. Temporary Controls: enclosures and fencing, protection of the Work and water control.
- C. Construction Facilities: progress cleaning and temporary buildings.

#### 1.2 TEMPORARY ELECTRICITY

- A. Cost: By Contractor; pay for temporary power service furnished by MoDOT.

#### ~~1.3 TELEPHONE SERVICE~~

- ~~A. Provide, maintain, and pay for telephone service to field office and Architect/Engineer/Designer's field office at time of project mobilization.~~

#### ~~1.4 FACSIMILE SERVICE~~

- ~~A. Provide, maintain and pay for facsimile service and a dedicated telephone line to field office and Architect/Engineer/Designer's field office at time of project mobilization.~~

#### 1.5 TEMPORARY WATER SERVICE

- A. Connect to existing water source as directed for construction operations at time of project mobilization.
- B. Contractor will reimburse Owner for water used in construction as agreed upon at time of project mobilization.

#### ~~1.6 TEMPORARY SANITARY FACILITIES~~

- ~~A. Provide and maintain required facilities and enclosures. Provide at time of project mobilization.~~

#### 1.7 FENCING

- A. Construction: Use plastic mesh safety fencing or better.
- B. Provide 48" high fence around construction site; equip with vehicular and pedestrian gates with locks.

#### 1.8 WATER CONTROL

- A. Grade site to drain. Maintain excavations free of water. Provide, operate and maintain pumping equipment.
- B. Protect site from puddling or running water. Provide water barriers as required to protect site from soil erosion.

#### 1.9 EXTERIOR ENCLOSURES

- A. Provide temporary weather tight closure of exterior openings to accommodate acceptable working conditions and protection for Products, to allow for temporary heating and maintenance of required ambient temperatures identified in individual specification sections, and to prevent entry of unauthorized persons. Provide access doors with self-closing hardware and locks.

1.10 PROTECTION OF INSTALLED WORK

- A. Protect installed Work and provide special protection where specified in individual specification sections.
- B. Provide temporary and removable protection for installed Products. Control activity in immediate work area to prevent damage.
- C. Provide protective coverings at walls, projections, jambs, sills and soffits of openings.
- D. Protect finished floors, stairs, and other surfaces from traffic, dirt, wear, damage or movement of heavy objects, by protecting with durable sheet materials.
- E. Prohibit traffic or storage upon waterproofed or roofed surfaces. If traffic or activity is necessary, obtain recommendations for protection from waterproofing or roofing material manufacturer.
- F. Prohibit traffic from landscaped areas.

1.11 SECURITY

- A. Provide security and facilities to protect Work and existing facilities and Owner's operations from unauthorized entry, vandalism or theft.
- B. Coordinate with Owner's security program.

1.12 ACCESS ROADS

- A. Provide and maintain access to fire hydrants, free of obstructions.
- B. Provide means of removing mud from vehicle wheels before entering streets.
- C. Designated existing on-site roads may be used for construction traffic.

1.13 PROGRESS CLEANING AND WASTE REMOVAL

- A. Maintain areas free of waste materials, debris and rubbish. Maintain site in a clean and orderly condition.
- B. Remove debris and rubbish from pipe chases, plenums, attics, crawl spaces and other closed or remote spaces, prior to enclosing the space.
- C. Broom and vacuum clean interior areas prior to start of surface finishing and continue cleaning to eliminate dust.
- D. Collect and remove waste materials, debris and rubbish from site periodically and dispose off-site.
- E. Open free-fall chutes are not permitted. Terminate closed chutes into appropriate containers with lids.

~~1.14 FIELD OFFICES AND SHEDS~~

- ~~A. Office: Weather tight, with lighting, electrical outlets, heating and ventilating equipment and equipped with drawing rack and drawing display table.~~
- ~~B. Provide space for Project meetings, with table and chairs to accommodate 6 persons.~~

1.15 REMOVAL OF UTILITIES, FACILITIES, AND CONTROLS

- A. Remove temporary utilities, equipment, facilities and materials prior to Final Application for Payment inspection.
- B. Clean and repair damage caused by installation or use of temporary work.
- C. Restore existing facilities used during construction to original condition. Restore permanent facilities used during construction to specified condition.

**PART 2 PRODUCTS**

Not Used.

**PART 3 EXECUTION**

Not Used.

**END OF SECTION**