



June 17, 2011

Addendum No. 001
IFB 9-110701C

MISSOURI DEPARTMENT OF TRANSPORTATION
CONSTRUCT SEWER AT MOUNTAIN GROVE, MISSOURI

BID OPENING DATE AND TIME: JULY 1, 2011 AT 3:00 P.M. LOCAL TIME.

1. The Prevailing Wage Rate No.17 as referenced in the bid documents should be changed to Prevailing Wage Rate No.18.
2. The contractor will haul off and properly dispose of all excess excavated and construction materials from site.
3. The following are clarifications for sizes of the vacuum air release and force main junction / clean out manhole structures.
 - Vacuum Air Release Manhole - 24"diameter by 5' as note on Vacuum Air Release Manhole Detail on Dwg. D-03
 - Force main Junction / Cleanout Manhole - 36" diameter by 42"
4. The force main Junction / Cleanout Manholes structures shall be of precast concrete (ASTM C478) construction and with heavy duty frame and cover capable of HS-20 truck loading.
5. The 1-1/2" Dia force main thru the asphalt parking shall receive 8" of concrete over the earth fill to match the finished surface of the existing asphalt surface.

END SECTION