



July 15, 2009

**Addendum No. 002  
9-090721**

To: Plans and Specifications Holders List for:

**District-2, Overhead Door Replacements, Two North Central Locations**

The bid opening date and time remains unchanged.

Corrections include:

- The Macon Weld Shop opener (1-each) shall be reused.
- The 4-openers at Milan shall be reused.
- A total of two openers are to be supplied and installed at the Macon Special Crews – Bridge Building.
- Openers power shall use existing 230V single phase.
- Safety sensing edges are required on all new doors.

Time for completion of this project shall be within 60 working days after receipt of Notice to Proceed.

Omit all references to coiling doors, as no coiling doors are required.

- END SECTION -