

IFB 9-110617
ADDENDUM NO. 2
June 9, 2011

PROJECT TITLE: District 8 Office Boiler Replacement

OWNER: Missouri Highways and Transportation Commission

ENGINEER: ESC, Inc. Consulting Engineers
Attn: Mike McKinnis, PE
Email: mmckinnis@escfirm.com
Phone: 417-831-5500

THE FOLLOWING ADDENDUM ITEMS PERTAIN TO PROJECT:

Comments and Corrections:

1. General bid information: Bids are due in Jefferson City MoDOT Office 3:00 pm CDT 6-17-11. Prevailing wage for Greene county is in effect. There is a 5% Bid Bond requirement. The project is sales tax exempt, the selected contractor will be provided an exemption certificate. The warranty period of 1 year is to start at final acceptance.
2. The completion date is October 1, 2011. Liquidated damages apply after that date.
3. Drawing M1 Demo Note 5: The contractor shall remove the housekeeping pad for the condensate return tank/pumps.
4. Drawing M1 Note 1: The expanded housekeeping pad shall be doweled into the existing floor using #4 X 0-6" dowels on 2' CC. The pad reinforcing shall be 6 X 6 X 1.4 X 1.4 mesh lapped 6" on all sides or #3 bars on 2' CC EW. The concrete shall be redi-mixed 3000 psi concrete with tooled edges.
5. Drawing M1 Number 11: This note applies to the venting for the boilers not the Hot Water Supply and Return piping.
6. Drawing M4 schedule BLR 101, BLR 201, and FWT 101: The boilers and condensate return system shall be 208V 3 ph.
7. Drawing M6 Division 23 52 39: The boiler burner control shall be low fire-high fire-low fire arrangement – not a full modulating control. The boiler controller shall be a Honeywell controller with display and expanded annunciator.