

TABLE OF CONTENTS

| DIVISION | | PAGE |
|--|--|-------------|
| DIVISION 1 – GENERAL REQUIREMENTS (BROAD SCOPE) | 3 | |
| 01019 | CONTRACT REQUIREMENTS | 3 |
| 01039 | COORDINATION AND MEETING REQUIREMENT | 5 |
| 01300 | SUBMITTAL REQUIREMENTS | 8 |
| 01400 | QUALITY CONTROL REQUIREMENTS | 11 |
| 01500 | CONSTRUCTION FACILITIES AND TEMPORARY CONTROL REQUIREMENTS | 13 |
| 01600 | MATERIAL AND EQUIPMENT REQUIREMENT | 15 |
| 01650 | STARTING OF SYSTEMS REQUIREMENT | 17 |
| 01700 | CONTRACT CLOSEOUT REQUIREMENT | 18 |
| DIVISION 2 - SITEWORK | 19 | |
| 02100 | SITE PREPARATION | 20 |
| DIVISION 3 - CONCRETE | 21 | |
| 03100 | CONCRETE FORMWORK | 21 |
| 03200 | CONCRETE REINFORCEMENT | 24 |
| 03300 | CAST-IN-PLACE CONCRETE | 26 |
| 03370 | CONCRETE CURING | 30 |
| DIVISION 5 - METALS | 31 | |
| 05500 | METAL FABRICATIONS | 31 |
| DIVISION 6 - WOOD AND PLASTIC | 33 | |
| 07210 | BUILDING INSULATION | 33 |
| 07600 | FLASHING AND SHEET METAL | 35 |
| 07229 | SPRAYED INSULATION | 40 |
| DIVISION 8 - DOORS AND WINDOWS | 42 | |
| 08111 | STANDARD STEEL DOORS | 42 |
| 08112 | STANDARD STEEL FRAMES | 44 |
| 08351 | OVERHEAD COILING DOORS | 46 |
| 08710 | DOOR HARDWARE | 48 |
| 08720 | ELECTRIC DOOR OPERATORS | 51 |
| 08800 | GLAZING | 53 |
| DIVISION 9 - FINISHES | 55 | |
| 09900 | PAINTING | 55 |
| DIVISION 10 - SPECIALTIES | 58 | |
| 15400 | PLUMBING SYSTEMS | 58 |
| 15500 | HEATING, VENTILATING AND AIR CONDITIONING | 60 |
| 15990 | TESTING AND BALANCING | 65 |
| DIVISION 16 - ELECTRICAL | 70 | |
| 16100 | ELECTRICAL WORK | 70 |
| 16101 | GENERAL | 70 |
| 16102 | FIELD CONDITIONS AND MEASUREMENTS | 70 |
| 16103 | CLEANUP | 70 |
| 16104 | GUARANTEE | 70 |
| 16105 | CODES | 70 |
| 16106 | SUBMITTALS | 70 |
| 16107 | QUALITY ASSURANCE | 71 |
| 16108 | CONDUIT | 71 |
| 16109 | WIRE AND CABLE | 71 |
| 16110 | JUNCTION AND OUTLET BOXES | 72 |
| 16111 | LIGHTING FIXTURES | 72 |
| 16112 | WIRING DEVICES | 72 |
| 16113 | PANELBOARDS | 73 |
| 16114 | TRANSFORMERS | 73 |
| 16115 | DISCONNECT SWITCHES | 73 |
| 16116 | GROUNDING | 73 |
| 16117 | OTHER MATERIALS | 73 |

| | | |
|-------|----------------------------|----|
| 16118 | EXECUTION | 73 |
| 16119 | PREPARATION | 73 |
| 16120 | TRENCHING AND BACKFILLING | 74 |
| 16122 | INSTALLATION OF CONDUCTORS | 74 |
| 16123 | INSTALLATION OF PANELS | 74 |
| 16124 | TESTING AND INSPECTION | 74 |
| 16125 | PROJECT COMPLETION | 75 |

01019

CONTRACT REQUIREMENTS

PART 1 GENERAL

1.1 SCHEDULE OF VALUES

- A. Submit a printed schedule on Contractor's standard form. Electronic media printout will be considered.
- B. Submit Schedule of Values in duplicate within 20 days after date of Owner-Contractor Agreement.
- C. Revise schedule to list approved Change Orders, with each Application For Payment.

1.2 APPLICATIONS FOR PAYMENT

- A. Submit four copies of each application on Contractor's electronic media driven form.
- B. Content and Format: Utilize Schedule of Values for listing items in Application for Payment.
- C. Payment Period: 30 days.
- D. Include an updated construction progress schedule.
- E. Certified payroll records.

1.3 CHANGE PROCEDURES

- A. The Architect/Engineer/Designer may issue a Notice of Change that includes a detailed description of a proposed change with supplementary or revised Drawings and specifications, a change in Contract Time for executing the change with a stipulation of any overtime work required.
- B. The Contractor may propose changes by submitting a request for change to the Architect/Engineer/Designer describing the proposed change and its full effect on the Work. Include a statement describing the reason for the change, the effect on the Contract Sum/Price and Contract Time, and a statement describing the effect on Work by the MoDOT District or other Contractors.
- C. Stipulated Sum/Price Change Order: Based on Notice of Change and Contractor's fixed price quotation or Contractor's request for a Change Order as approved by Architect/Engineer/Designer.
- D. Construction Change Directive: Architect/Engineer/Designer may issue a directive instructing the Contractor to proceed with a change in the Work, for subsequent inclusion in a Change Order. Document will describe changes in the Work, and designate method of determining any change in Contract Sum/Price or Contract Time. Promptly execute the change.
- E. Time and Material Change Order: Submit itemized account and supporting data after completion of change, within time limits indicated in the Conditions of the Contract. Architect/Engineer/Designer will determine the change allowable in Contract Sum/Price and Contract Time as provided in the Contract Documents.
- F. Maintain detailed records of work done on Time and Material basis. Provide full information required for evaluation of proposed changes, and to substantiate costs for changes in the Work.

- G. Execution of Change Orders: Architect/Engineer/Designer will issue Change Orders for signatures of parties as provided in the Conditions of the Contract.

1.4 DEFECT ASSESSMENT

- A. Replace the Work, or portions of the Work, not conforming to specify requirements.
- B. If, in the opinion of the Architect/Engineer/Designer, it is not practical to remove and replace the Work, the Architect/Engineer/Designer will direct an appropriate remedy or adjust payment.

1.5 ALTERNATIVES

- A. Accepted Alternatives will be identified in Owner-Contractor Agreement.

END OF SECTION

COORDINATION AND MEETING REQUIREMENT

PART 1 GENERAL

1.1 COORDINATION AND PROJECT CONDITIONS

- A. Coordinate scheduling, submittals, and Work of the various sections of the Project Manual to ensure efficient and orderly sequence of installation of interdependent construction elements.
- B. Verify utility requirements and characteristics of operating equipment are compatible with building utilities. Coordinate work of various sections having interdependent responsibilities for installing, connecting to and placing in service, such equipment.
- C. Coordinate space requirements, supports, and installation of mechanical and electrical Work, which are indicated diagrammatically on Drawings. Follow routing shown for pipes, ducts, and conduit, as closely as practicable; place runs parallel with lines of building. Utilize spaces efficiently to maximize accessibility for other installations, for maintenance, and for repairs.
- D. In finished areas, except as otherwise indicated, conceal pipes, ducts and wiring within the construction. Coordinate locations of fixtures and outlets with finish elements.
- E. Coordinate completion and clean up of Work of separate sections in preparation for Completion.
- F. After Owner occupancy of premises, coordinate access to site for correction of defective Work and Work not in accordance with Contract Documents, to minimize disruption of Owner's activities.

1.2 FIELD ENGINEERING

- A. Employ a Land Surveyor registered in the State of Missouri and acceptable to Architect/Engineer/Designer.
- B. Owner will locate and protect survey control and reference points.
- C. Control datum for survey is that established by Owner provided survey.
- D. Verify setbacks and easements; confirm drawing dimensions and elevations.
- E. Provide field engineering services. Establish elevations, lines and levels, utilizing recognized engineering survey practices.

1.3 PRECONSTRUCTION MEETING

- A. Architect/Engineer/Designer will schedule a meeting after Notice of Award.
- B. Attendance Required: District engineer or representative, Architect/Engineer/Designer and Contractor.
- C. Record minutes and distribute copies within 5 days after meeting to participants, with two copies to District Engineer, Architect/Engineer/Designer, participants and those affected by decisions made.

1.4 SITE MOBILIZATION MEETING

- A. Architect/Engineer/Designer will schedule a meeting at the Project site prior to Contractor occupancy.
- B. Architect/Engineer/Designer will record minutes and distributes copies within 5 days after meeting to participants, with two copies to Architect/Engineer/Designer, participants and those affected by decisions made.

1.5 PROGRESS MEETINGS

- A. Schedule and administer meetings throughout progress of the Work at when arranged by Architect/Engineer/Designer.
- B. Architect/Engineer/Designer will make arrangements for meetings, prepare agenda with copies for participants, and preside at meetings.
- C. Attendance Required: Job superintendent, major Subcontractors and suppliers, District engineer representative, Architect/Engineer/Designer, as appropriate to agenda topics for each meeting.
- D. Agenda:
 - 1. Review of Work progress.
 - 2. Field observations, problems, and decisions.
 - 3. Identification of problems, which impede planned progress.
 - 4. Maintenance of progress schedule.
 - 5. Corrective measures to regain projected schedules.
 - 6. Coordination of projected progress.
 - 7. Effect of proposed changes on progress schedule and coordination.
- E. Record minutes and distributes copies within 5 days after meeting to participants and those affected by decisions made.

1.6 PREINSTALLATION MEETING

- A. When required in individual specification sections, convene a pre-installation meeting at the site prior to commencing work of the section.
- B. Notify Architect/Engineer/Designer seven days in advance of meeting date.
- C. Prepare agenda and preside at meeting:
 - 1. Review conditions of installation, preparation and installation procedures.
 - 2. Review coordination with related work.
- D. Record minutes and distributes copies within 5 days after meeting to participants and those affected by decisions made.

PART 2 PRODUCTS

Not used

PART 3 EXECUTION

3.1 CUTTING AND PATCHING

- A. Employ skilled and experienced installer to perform cutting and patching.
- B. Submit written request in advance of cutting or altering elements, which affect:
 - 1. Structural integrity of element.
 - 2. Integrity of weather-exposed or moisture-resistant elements.
 - 3. Work of Owner or separate contractor.
- C. Execute cutting, fitting, and patching to complete Work, and to:
 - 1. Uncover Work to install or correct ill-timed Work.
 - 2. Remove and replace defective and non-conforming Work.
 - 3. Provide openings in elements of Work for penetrations of mechanical and electrical Work.

- D. Cut masonry and concrete materials using masonry saw or core drill.
- E. Fit Work tight to pipes, sleeves, ducts, conduit and other penetrations through surfaces.
- F. Maintain integrity of wall, ceiling, or floor construction; completely seal voids.
- G. Refinish surfaces to match adjacent finishes. For continuous surfaces, refinish to nearest intersection; for an assembly, refinish entire unit.
- H. Identify hazardous substances or conditions exposed during the Work to the Architect/Engineer/Designer for decision or remedy.

3.2 ALTERATION PROJECT PROCEDURES

- A. Materials: As specified in Product sections; match existing Products and work for patching and extending work.
- B. Close openings in exterior surfaces to protect existing work from weather and extremes of temperature and humidity.
- C. When finished surfaces are cut so that a smooth transition with new Work is not possible, terminate existing surface along a straight line at a natural line of division and submit recommendation to Architect/Engineer/Designer for review.
- D. Patch or replace portions of existing surfaces that are damaged, lifted, discolored or showing other imperfections.
- E. Finish surfaces as specified in individual Product sections.

END OF SECTION

01300

SUBMITTAL REQUIREMENTS

PART 1 GENERAL

1.1 REFERENCES

- A. AGC Associated General Contractors of America publication "The Use of CPM in Construction - A Manual for General Contractors and the Construction Industry".

1.2 SUBMITTAL PROCEDURES

- A. Submit five (5) hard copies of each submittal with Architect/Engineer/Designer accepted form.
- B. Identify Project, Contractor, Subcontractor or supplier; pertinent drawing and detail number and specification section number, as appropriate.
- C. Apply Contractor's stamp, signed or initialed certifying that review, approval, verification of Products required, field dimensions, adjacent construction Work and coordination of information is in accordance with the requirements of the Work and Contract Documents.
- D. Schedule submittals to expedite the Project, and deliver to Architect/Engineer/Designer at business address. Coordinate submission of related items.
- E. For each submittal for review, allow 15 days excluding delivery time to and from the contractor.
- F. Identify variations from Contract Documents and Product or system limitations, which may be detrimental to successful performance of the completed Work.
- G. Submittals not requested will not be recognized or processed.

1.3 CONSTRUCTION PROGRESS SCHEDULES

- A. Submit initial schedule in duplicate within 15 days after date established in Notice to Proceed.
- B. Revise and resubmit as required.
- C. Submit revised schedules with each Application for Payment, identifying changes since previous version.
- D. Submit a horizontal bar chart with separate line for each major portion of Work or operation, identifying first workday of each week.

1.4 PROPOSED PRODUCTS LIST

- A. Within 15 days after date of Notice to Proceed, submit list of major products proposed for use, with name of manufacturer, trade name and model number of each product.
- B. For products specified only by reference standards, give manufacturer, trade name, model or catalog designation and reference standards.

1.5 PRODUCT DATA

- A. Product Data for Review:
 - 1. Submitted to Architect/Engineer/Designer for review for the limited purpose of checking for conformance with information given and the design concept expressed in the contract documents.
 - 2. After review, provide copies and distribute in accordance with SUBMITTAL PROCEDURES article above and for record documents purposes described in Section 01700 - CONTRACT CLOSEOUT.
- B. Product Data for Information:
 - 1. Submitted for the Architect/Engineer/Designer's knowledge as contract administrator or for the Owner.

- C. Product Data for Project Closeout:
 - 1. Submitted for the Owner's benefit during and after project completion.
- D. Submit the number of copies, which the Contractor requires, plus two copies that will be retained by the Architect/Engineer/Designer.
- E. Mark each copy to identify applicable products, models, options and other data. Supplement manufacturers' standard data to provide information specific to this Project.
- F. After review distribute in accordance with the Submittal Procedures article above and provide copies for record documents described in Section 01700 - CONTRACT CLOSEOUT.

1.6 SHOP DRAWINGS

- A. Shop Drawings for Review:
 - 1. Submit five (5) hard copies to Architect/Engineer/Designer for review for the limited purpose of checking for conformance with information given and the design concept expressed in the contract documents.
 - 2. After review, produce copies and distribute in accordance with SUBMITTAL PROCEDURES article above and for record documents purposes described in Section 01700 - CONTRACT CLOSEOUT.
- B. Shop Drawings for Information:
 - 1. Submitted for the Architect/Engineer/Designer's knowledge as contract administrator or for the Owner.
- C. Shop Drawings For Project Closeout:
 - 1. Submitted for the Owner's benefit during and after project completion.
- D. Indicate special utility and electrical characteristics, utility connection requirements and location of utility outlets for service for functional equipment and appliances.
- E. Submit in the form of one reproducible transparency and one opaque reproduction.

1.7 SAMPLES

- A. Samples for Review:
 - 1. Submitted to Architect/Engineer/Designer for review for the limited purpose of checking for conformance with information given and the design concept expressed in the contract documents.
 - 2. After review, produce duplicates and distribute in accordance with SUBMITTAL PROCEDURES article above and for record documents purposes described in Section 01700 - CONTRACT CLOSEOUT.
- B. Samples for Information:
 - 1. Submitted for the Architect/Engineer/Designer's knowledge as contract administrator or for the Owner.
- C. Samples for Selection:
 - 1. Submitted to Architect/Engineer/Designer for aesthetic, color, or finish selection.
 - 2. Submit samples of finishes for Architect/Engineer/Designer selection.
 - 3. After review, produce duplicates and distribute in accordance with SUBMITTAL PROCEDURES article above and for record documents purposes described in Section 01700 - CONTRACT CLOSEOUT.

1.8 DESIGN DATA

- A. Submit for the Architect/Engineer/Designer's knowledge as contract administrator or for the Owner.
- B. Submit for information for the limited purpose of assessing conformance with information given and the design concept expressed in the contract documents.

1.9 TEST REPORTS

- A. Submit for the Architect/Engineer/Designer's knowledge as contract administrator or for the Owner.
- B. Submit test reports for information for the limited purpose of assessing conformance with information given and the design concept expressed in the contract documents.

1.10 CERTIFICATES

- A. When specified in individual specification sections, submit certification by the manufacturer, installation/application subcontractor, or the Contractor to Architect/Engineer/Designer, in quantities specified for Product Data.
- B. Indicate material or Product conforms to or exceeds specified requirements. Submit supporting reference data, affidavits and certifications as appropriate.
- C. Certificates may be recent or previous test results on material or Product but must be acceptable to Architect/Engineer/Designer.

1.11 MANUFACTURER'S INSTRUCTIONS

- A. When specified in individual specification sections, submit printed instructions for delivery, storage, assembly, installation, and start-up, adjusting and finishing, to Architect/Engineer/Designer for delivery to owner in quantities specified for Product Data.
- B. Indicate special procedures, perimeter conditions requiring special attention and special environmental criteria required for application or installation.
- C. Refer to Section 01400 - Quality Control, Manufacturers' Field Services article.

1.12 MANUFACTURER'S FIELD REPORTS

- A. Submit reports for the Architect/Engineer/Designer's benefit as contract administrator or for the Owner.
- B. Submit for information for the limited purpose of assessing conformance with information given and the design concept expressed in the contract documents.

1.13 ERECTION DRAWINGS

- A. Submit drawings for the Architect/Engineer/Designer's benefit as contract administrator or for the Owner.
- B. Submit for information for the limited purpose of assessing conformance with information given and the design concept expressed in the contract documents.
- C. Data indicating inappropriate or unacceptable Work may be subject to action by the Architect/Engineer/Designer or Owner.

END OF SECTION

QUALITY CONTROL REQUIREMENTS

PART 1 GENERAL

1.1 QUALITY ASSURANCE - CONTROL OF INSTALLATION

- A. Monitor quality control over suppliers, manufacturers, Products, services, site conditions and workmanship, to produce Work of specified quality.
- B. Comply with manufacturers' instructions, including each step in sequence.
- C. Should manufacturers' instructions conflict with Contract Documents, request clarification from Architect/Engineer/Designer before proceeding.
- D. Comply with specified standards as minimum quality for the Work except where more stringent tolerances, codes or specified requirements indicate higher standards or more precise workmanship.
- E. Perform Work by persons qualified to produce required and specified quality.
- F. Verify that field measurements are as indicated on shop drawings or as instructed by the manufacturer.
- G. Secure Products in place with positive anchorage devices designed and sized to withstand stresses, vibration, physical distortion, or disfigurement.

1.2 TOLERANCES

- A. Monitor fabrication and installation tolerance control of Products to produce acceptable Work. Do not permit tolerances to accumulate.
- B. Comply with manufacturers' tolerances. Should manufacturers' tolerances conflict with Contract Documents, request clarification from Architect/Engineer/Designer before proceeding.
- C. Adjust Products to appropriate dimensions; position before securing Products in place.

1.3 REFERENCES AND STANDARDS

- A. For Products or workmanship specified by association, trade or other consensus standards, comply with requirements of the standard, except when more rigid requirements are specified or are required by applicable codes.
- B. Conform to reference standard by date of issue current on date for receiving bids or date specified in the individual specification sections, except where a specific date is established by code.
- C. Neither the contractual relationships, duties or responsibilities of the parties in Contract nor those of the Architect/Engineer/Designer shall be altered from the Contract Documents by mention or inference otherwise in any reference document.

1.4 TESTING SERVICES

- A. Contractor to provide all testing services as called out in these specifications.
- B. Testing and source quality control may occur on or off the project site. Perform off-site testing as required by the Architect/Engineer/Designer or the Owner.
- C. Testing does not relieve Contractor to perform Work to contract requirements.
- D. Re-testing required because of non-conformance to specified requirements shall be performed by the same MoDOT personnel on instructions by the Architect/Engineer/Designer.

1.5 INSPECTION SERVICES

- A. Owner will employ MoDOT Personnel to perform inspection.
- B. Inspecting may occur on or off the project site. Perform off-site inspecting as required by the Architect/Engineer/Designer or the Owner.
- C. Inspecting does not relieve Contractor to perform Work to contract requirements.

1.6 MANUFACTURERS' FIELD SERVICES

- A. When specified in individual specification sections, require material or Product suppliers or manufacturers to provide qualified staff personnel to observe site conditions, conditions of surfaces and installation, quality of workmanship, start-up of equipment, test, adjust and the balancing of equipment as applicable and to initiate instructions when necessary.
- B. Report observations and site decisions or instructions given to applicators or installers that are supplemental or contrary to manufacturers' written instructions.
- C. Refer to Section 01300 - SUBMITTALS, MANUFACTURERS' FIELD REPORTS article.

PART 2 EXECUTION

2.1 EXAMINATION

- A. Verify that existing site conditions and substrate surfaces are acceptable for subsequent Work. Beginning new Work means acceptance of existing conditions.
- B. Verify that existing substrate is capable of structural support or attachment of new Work being applied or attached.

2.2 PREPARATION

- A. Clean substrate surfaces prior to applying next material or substance.
- B. Seal cracks or openings of substrate prior to applying next material or substance.
- C. Apply manufacturer required or recommended substrate primer, sealer or conditioner prior to applying any new material or substance in contact or bond.

END OF SECTION

01500

CONSTRUCTION FACILITIES AND TEMPORARY CONTROL REQUIREMENTS

PART 1 GENERAL

1.1 TEMPORARY ELECTRICITY

- A. Cost: By Contractor; pay for temporary power service furnished by MoDOT.

1.2 TELEPHONE SERVICE

- A. Provide, maintain, and pay for telephone service to field office and Architect/Engineer/Designer's field office at time of project mobilization.

1.3 FACSIMILE SERVICE

- A. Provide, maintain and pay for facsimile service and a dedicated telephone line to field office and Architect/Engineer/Designer's field office at time of project mobilization.

1.4 TEMPORARY WATER SERVICE

- A. Connect to existing water source as directed for construction operations at time of project mobilization.
- B. Contractor will reimburse Owner for water used in construction as agreed upon at time of project mobilization.

1.5 TEMPORARY SANITARY FACILITIES

- A. Provide and maintain required facilities and enclosures. Provide at time of project mobilization.

1.6 FENCING

- A. Construction: Use plastic mesh safety fencing or better.
- B. Provide 48" high fence around construction site; equip with vehicular and pedestrian gates with locks.

1.7 WATER CONTROL

- A. Grade site to drain. Maintain excavations free of water. Provide, operate and maintain pumping equipment.
- B. Protect site from puddling or running water. Provide water barriers as required to protect site from soil erosion.

1.8 EXTERIOR ENCLOSURES

- A. Provide temporary weather tight closure of exterior openings to accommodate acceptable working conditions and protection for Products, to allow for temporary heating and maintenance of required ambient temperatures identified in individual specification sections, and to prevent entry of unauthorized persons. Provide access doors with self-closing hardware and locks.

1.9 PROTECTION OF INSTALLED WORK

- A. Protect installed Work and provide special protection where specified in individual specification sections.
- B. Provide temporary and removable protection for installed Products. Control activity in immediate work area to prevent damage.

- C. Provide protective coverings at walls, projections, jambs, sills and soffits of openings.
- D. Protect finished floors, stairs, and other surfaces from traffic, dirt, wear, damage or movement of heavy objects, by protecting with durable sheet materials.
- E. Prohibit traffic or storage upon waterproofed or roofed surfaces. If traffic or activity is necessary, obtain recommendations for protection from waterproofing or roofing material manufacturer.
- F. Prohibit traffic from landscaped areas.

1.10 SECURITY

- A. Provide security and facilities to protect Work and existing facilities and Owner's operations from unauthorized entry, vandalism or theft.
- B. Coordinate with Owner's security program.

1.11 ACCESS ROADS

- A. Provide and maintain access to fire hydrants, free of obstructions.
- B. Provide means of removing mud from vehicle wheels before entering streets.
- C. Designated existing on-site roads may be used for construction traffic.

1.12 PROGRESS CLEANING AND WASTE REMOVAL

- A. Maintain areas free of waste materials, debris and rubbish. Maintain site in a clean and orderly condition.
- B. Remove debris and rubbish from pipe chases, plenums, attics, crawl spaces and other closed or remote spaces, prior to enclosing the space.
- C. Broom and vacuum clean interior areas prior to start of surface finishing and continue cleaning to eliminate dust.
- D. Collect and remove waste materials, debris and rubbish from site periodically and dispose off-site.
- E. Open free-fall chutes are not permitted. Terminate closed chutes into appropriate containers with lids.

1.13 FIELD OFFICES AND SHEDS

- A. Office: Weather tight, with lighting, electrical outlets, heating and ventilating equipment and equipped with drawing rack and drawing display table.
- B. Provide space for Project meetings, with table and chairs to accommodate 6 persons.

1.14 REMOVAL OF UTILITIES, FACILITIES, AND CONTROLS

- A. Remove temporary utilities, equipment, facilities and materials prior to Final Application for Payment inspection.
- B. Clean and repair damage caused by installation or use of temporary work.
- C. Restore existing facilities used during construction to original condition. Restore permanent facilities used during construction to specified condition.

END OF SECTION

MATERIAL AND EQUIPMENT REQUIREMENT

PART 1 GENERAL

1.1 PRODUCTS

- A. Do not use materials and equipment removed from existing premises, except as specifically permitted by the Contract Documents.
- B. Provide interchangeable components of the same manufacture for components being replaced.

1.2 TRANSPORTATION AND HANDLING

- A. Transport and handle Products in accordance with manufacturer's instructions.
- B. Promptly inspect shipments to ensure that Products comply with requirements, quantities are correct and products are undamaged.
- C. Provide equipment and personnel to handle Products by methods to prevent soiling, disfigurement or damage.

1.3 STORAGE AND PROTECTION

- A. Store and protect Products in accordance with manufacturers' instructions.
- B. Store with seals and labels intact and legible.
- C. Store sensitive Products in weather tight, climate controlled, enclosures in an environment favorable to Product.
- D. For exterior storage of fabricated Products, place on sloped supports above ground.
- E. Provide bonded off-site storage and protection when site does not permit on-site storage or protection.
- F. Cover Products subject to deterioration with impervious sheet covering. Provide ventilation to prevent condensation and degradation of Products.
- G. Store loose granular materials on solid flat surfaces in a well-drained area. Prevent mixing with foreign matter.
- H. Provide equipment and personnel to store Products by methods to prevent soiling, disfigurement or damage.
- I. Arrange storage of Products to permit access for inspection. Periodically inspect to verify Products are undamaged and are maintained in acceptable condition.

1.4 PRODUCT OPTIONS

- A. Products Specified by Reference Standards or by Description Only: Any Product meeting those standards or description is acceptable.
- B. Products Specified by Naming One or More Manufacturers: Products of manufacturers named and meeting specifications, no options or substitutions allowed.
- C. Products Specified by Naming One or More Manufacturers with a Provision for Substitutions: Submit a request for substitution for any manufacturer not named in accordance with the following article.

1.5 SUBSTITUTIONS

- A. Architect/Engineer/Designer will consider requests for Substitutions only within 15 days after date established in Notice to Proceed.
- B. Substitutions may be considered when a Product becomes unavailable through no fault of the Contractor.
- C. Document each request with complete data substantiating compliance of proposed Substitution with Contract Documents.
- D. A request constitutes a representation that the Contractor:
 - 1. Has investigated proposed Product and determined that it meets or exceeds the quality level of the specified Product.
 - 2. Will provide the same warranty for the Substitution as for the specified Product.
 - 3. Will coordinate installation and make changes to other Work that may be required for the Work to be complete with no additional cost to Owner.
 - 4. Waives claims for additional costs or time extension that may subsequently become apparent.
 - 5. Will reimburse Owner for review or redesign services associated with re-approval by authorities.
- E. Substitutions will not be considered when they are indicated or implied on shop drawing or product data submittals, without separate written request or when acceptance will require revision to the Contract Documents.
- F. Substitution Submittal Procedure:
 - 1. Submit three copies of request for Substitution for consideration. Limit each request to one proposed Substitution.
 - 2. Submit shop drawings, product data and certified test results attesting to the proposed Product equivalence. Burden of proof is on proposer.
 - 3. The Architect/Engineer/Designer will notify Contractor in writing of decision to accept or reject request.

END OF SECTION

STARTING OF SYSTEMS REQUIREMENT

PART 1 GENERAL

1.1 STARTING SYSTEMS

- A. Coordinate schedule for start-up of various equipment and systems.
- B. Notify Architect/Engineer/Designer seven days prior to start-up of each item.
- C. Verify that each piece of equipment or system has been checked for proper lubrication, drive rotation, belt tension, and control sequence and for conditions that may cause damage.
- D. Verify tests, meter readings, and specified electrical characteristics agree with those required by the equipment or system manufacturer.
- E. Verify that wiring and support components for equipment are complete and tested.
- F. Execute start-up under supervision of applicable manufacturer's representative or Contractors' personnel in accordance with manufacturers' instructions.
- G. When specified in individual specification Sections, require manufacturer to provide authorized representative to be present at site to inspect, check and approve equipment or system installation prior to start-up and to supervise placing equipment or system in operation.
- H. Submit a written report in accordance with Section 01300 that equipment or system has been properly installed and is functioning correctly.

1.2 DEMONSTRATION AND INSTRUCTIONS

- A. Demonstrate operation and maintenance of Products to Owner's personnel two weeks prior to date of Final Completion.
- B. For equipment or systems requiring seasonal operation, perform demonstration for other season within six months.
- C. Utilize operation and maintenance manuals as basis for instruction. Review contents of manual with Owners' personnel in detail to explain all aspects of operation and maintenance.
- D. Demonstrate start-up, operation, control, adjustment, trouble-shooting, servicing, maintenance and shutdown of each item of equipment at agreed time, at equipment location.
- E. Prepare and insert additional data in operations and maintenance manuals when the need for additional data becomes apparent during instruction.
- F. The amount of time required for instruction on each item of equipment and system that's specified in individual sections.

END OF SECTION

CONTRACT CLOSEOUT REQUIREMENT

PART 1 GENERAL

1.1 CLOSEOUT PROCEDURES

- A. Submit written certification that Contract Documents have been reviewed, Work has been inspected, and that Work is complete in accordance with Contract Documents and ready for Architect/Engineer/Designer's review.
- B. Provide submittals to Owner that is required by governing or other authorities.
- C. Submit final Application for Payment identifying total adjusted Contract Sum, previous payments and sum remaining due.
- D. Owner will occupy portions of the building as specified in Section 01010.
- E. Projects shall not be accepted by MoDOT until the vendor has completed all punch list items. The vendor will then have 30 days to submit all required paperwork necessary to close the project. Failure to submit the required paperwork within 30 days could result in the debarment or suspension of the contractor from future projects.

1.2 FINAL CLEANING

- A. Execute final cleaning prior to final project assessment. Clean interior and exterior glass, surfaces exposed to view; remove temporary labels, stains and foreign substances, polish transparent and glossy surfaces, vacuum carpeted and soft surfaces.
- B. Clean equipment and fixtures to a sanitary condition with cleaning materials appropriate to the surface and material being cleaned.
- C. Clean or replace filters of operating equipment used during construction and/or adjustment.
- D. Clean debris from roofs, gutters, downspouts and drainage systems.
- E. Clean site; sweep paved areas, rake clean landscaped surfaces.
- F. Remove waste and surplus materials, rubbish and construction facilities from the site.

1.3 ADJUSTING

- A. Adjust operating Products and equipment to ensure smooth and unhindered operation.

1.4 PROJECT RECORD DOCUMENTS

- A. Store record documents separate from documents used for construction.
- B. Record information concurrent with construction progress.
- C. Specifications: Legibly mark and record at each Product section description of actual Products installed, including the following:
 - 1. Manufacturer's name and product model and number.
 - 2. Product substitutions or alternates utilized.
 - 3. Changes made by Addenda and modifications.
- D. Record Drawings and Shop Drawings: Legibly mark each item to record actual construction including:
 - 1. Measured depths of foundations in relation to finish main floor datum.

2. Measured horizontal and vertical locations of underground utilities and appurtenances, referenced to permanent surface improvements.
 3. Measured locations of internal utilities and appurtenances concealed in construction, referenced to visible and accessible features of the Work.
 4. Field changes of dimension and detail.
 5. Details not on original Contract drawings.
- E. Submit documents to Architect/Engineer/Designer's with claim for final Application for Payment.
- 1.5 OPERATION AND MAINTENANCE DATA
- A. Submit data bound in 8-1/2 x 11 inch (A4) text pages, three D side ring binders with durable plastic covers.
 - B. Prepare binder cover with printed title "OPERATION AND MAINTENANCE INSTRUCTIONS", title of project and subject matter of binder when multiple binders are required.
 - C. Internally subdivide the binder contents with permanent page dividers, logically organized; with tab titling clearly printed under reinforced laminated plastic tabs.
 - D. Submit 1 draft copy of completed volumes 15 days prior to final inspection. This copy will be reviewed and returned with Architect/Engineer/Designer comments. Revise content of all document sets as required prior to final submission.
 - E. Submit two sets of revised final volumes, within 10 days after final inspection.
- 1.6 SPARE PARTS AND MAINTENANCE PRODUCTS
- A. Provide spare parts, maintenance, and extra Products in quantities specified individual specification sections.
 - B. Deliver to Project site; obtain receipt prior to final payment.
 - C. Examine system components at a frequency consistent with reliable operation. Clean, adjust and lubricate as required.
 - D. Include systematic examination, adjustment, and lubrication of components. Repair or replace parts whenever required. Use parts produced by the manufacturer of the original component.
 - E. Maintenance service shall not be assigned or transferred to any agent or Subcontractor without prior written consent of the Owner.
- 1.7 WARRANTIES
- A. Execute and assemble transferable warranty documents from Subcontractors, suppliers and manufacturers.
 - B. Submit prior to final Application for Payment.
 - C. For items of Work delayed beyond date of Final Completion, provide updated submittal within 10 days after acceptance, listing date of acceptance as start of the warranty period.

END OF SECTION

02100

SITE PREPARATION

PART 1 SCOPE

Contractor to provide like materials in all areas disturbed during construction.

END OF SECTION

03100

CONCRETE FORMWORK

PART 1 GENERAL

1.1 REFERENCES

- A. ACI 301 - Structural Concrete for Buildings.
- B. ACI 318 - Building Code Requirements for Reinforced Concrete.
- C. ACI 347 - Recommended Practice For Concrete Formwork.
- D. PS 1 - Construction and Industrial Plywood.

1.2 DESIGN REQUIREMENTS

- A. Design, engineer and construct formwork, shoring and bracing to conform to design and code requirements; concrete to conform to required shape, line and dimension.

1.3 SUBMITTALS

- A. Submit under provisions of Section 01300.
- B. Product Data: Provide data on void form materials and installation requirements.

1.4 QUALITY ASSURANCE

- A. Perform Work in accordance with ACI 347.

1.5 REGULATORY REQUIREMENTS

- A. Conform to applicable code for design, fabrication, erection and removal of formwork.

1.6 FIELD SAMPLES

- A. Provide under provisions of Section 01400. Coordinate with requirements stated in Section 03100 and 03300.

1.7 DELIVERY, STORAGE AND HANDLING

- A. Deliver, store, protect and handle products to site under provisions of Section 01600.
- B. Deliver void forms and installation instructions in manufacturer's packaging.
- C. Store off ground in ventilated and protected manner to prevent deterioration from moisture.

1.8 COORDINATION

- A. Coordinate this Section with other Sections of work that require attachment of components to formwork.
- B. If formwork is placed after reinforcement resulting in insufficient concrete cover over reinforcement before proceeding, request instructions from Architect/Engineer.

PART 2 PRODUCTS

2.1 WOOD FORM MATERIALS

- A. Plywood: Douglas Fir species; grade B/B plyform class 1 or 2; sound undamaged sheets with clean, true edges.

- B. Lumber: Douglas Fir species; standard grade; with grade stamp clearly visible.

2.2 PREFABRICATED FORMS

- A. Preformed Steel Forms: Minimum 16 gage matched, tight fitting, stiffened to support weight of concrete without deflection detrimental to tolerances and appearance of finished surfaces.
- B. Pan Type: Steel of size and profile required.
- C. Tubular Column Type: Round, spirally wound laminated fiber material, surface treated with release agent, non-reusable, of sizes required.
- D. Void Forms: Moisture resistant treated paper faces, biodegradable, structurally sufficient to support weight of wet concrete mix until initial set; 2 inches thick.

2.3 FORMWORK ACCESSORIES

- A. Form Ties: Snap-off type, galvanized metal, fixed length, cone type, with waterproofing washer, free of defects that could leave holes larger than 1 inch in concrete surface.
- B. Form Release Agent: Colorless mineral oil which will not stain concrete, or absorb moisture, or impair natural bonding or color characteristics of coating intended for use on concrete.
- C. Dovetail Anchor Slot: Galvanized steel, 22 gauge thick, foam filled, release tape sealed slots, anchors for securing to concrete formwork.
- D. Flashing Reglets: Galvanized steel, 22 gage thick, longest possible lengths, with alignment splines for joints, foam filled, release tape sealed slots, anchors for securing to concrete formwork.
- E. Nails, Spikes, Lag Bolts, Through Bolts, Anchorages: Sized as required, of sufficient strength and character to maintain formwork in place while placing concrete.
- F. Waterstops: Rubber, minimum 1,750 p.s.i tensile strength, minimum 50 degrees F to plus 175 degrees F working temperature range, wide, maximum possible lengths, ribbed profile, preformed corner sections, heat welded jointing.

PART 3 EXECUTION

3.1 EXAMINATION

- A. Verify lines, levels and centers before proceeding with formwork. Ensure that dimensions agree with drawings.

3.2 EARTH FORMS

- A. Earth forms are not permitted except for spread and column footings, which are to be square and free of debris.

3.3 ERECTION - FORMWORK

- A. Erect formwork, shoring and bracing to achieve design requirements, in accordance with ACI 301.
- B. Provide bracing to ensure stability of formwork. Shore or strengthen formwork subject to over stressing by construction loads.
- C. Arrange and assemble formwork to permit dismantling and stripping. Do not damage concrete during stripping. Permit removal of remaining principal shores.
- D. Align joints and make watertight. Keep form joints to a minimum.
- E. Obtain approval before framing openings in structural members that are not indicated on Drawings.
- F. Install void forms in accordance with manufacturer's recommendations. Protect forms from moisture or crushing.

3.4 APPLICATION - FORM RELEASE AGENT

- A. Apply form release agent on formwork in accordance with manufacturer's recommendations.
- B. Apply prior to placement of reinforcing steel, anchoring devices and embedded items.
- C. Do not apply form release agent where concrete surfaces will receive special finishes or applied coverings that are affected by agent. Soak inside surfaces of untreated forms with clean water. Keep surfaces coated prior to placement of concrete.

3.5 INSERTS, EMBEDDED PARTS, AND OPENINGS

- A. Provide formed openings where required for items to be embedded in passing through concrete work.
- B. Locate and set in place items which will be cast directly into concrete.
- C. Coordinate with work of other sections in forming and placing openings, slots, reglets, recesses, sleeves, bolts, anchors, other inserts and components of other Work.
- D. Install accessories in accordance with manufacturer's instructions, straight, level and plumb. Ensure items are not disturbed during concrete placement.
- E. Install water-stops continuous without displacing reinforcement. Heat seal joints watertight.
- F. Provide temporary ports or openings in formwork where required to facilitate cleaning and inspection. Locate openings at bottom of forms to allow flushing water to drain.
- G. Close temporary openings with tight fitting panels, flush with inside face of forms and neatly fitted so joints will not be apparent in exposed concrete surfaces.

3.6 FORM CLEANING

- A. Clean forms as erection proceeds, to remove foreign matter within forms.
- B. Clean formed cavities of debris prior to placing concrete.
- C. Flush with water or use compressed air to remove remaining foreign matter. Ensure that water and debris drain to exterior through clean-out ports.
- D. During cold weather, remove ice and snow from within forms. Do not use de-icing salts. Do not use water to clean out forms, unless formwork and concrete construction proceed within heated enclosure. Use compressed air or other means to remove foreign matter.

3.7 FORMWORK TOLERANCES

- A. Construct formwork to maintain tolerances required by ACI 301.

3.8 FIELD QUALITY CONTROL

- A. Inspect erected formwork, shoring, and bracing to ensure that work is in accordance with formwork design and that supports, fastenings, wedges, ties and items are secure.
- B. Do not reuse wood formwork more than 2 times for concrete surfaces to be exposed to view. Do not patch formwork.

3.9 FORM REMOVAL

- A. Do not remove forms or bracing until concrete has gained sufficient strength to carry its own weight and imposed loads.
- B. Loosen forms carefully. Do not wedge pry bars, hammers or tools against finish concrete surfaces scheduled for exposure to view.
- C. Store removed forms in manner that surfaces to be in contact with fresh concrete will not be damaged. Discard damaged forms.

END OF SECTION

03200

CONCRETE REINFORCEMENT

PART 1 GENERAL

1.1 REFERENCES

- A. ACI 301 - Structural Concrete for Buildings.
- B. ACI 318 - Building Code Requirements For Reinforced Concrete.
- C. ACI SP-66 - American Concrete Institute - Detailing Manual.
- D. ACI 315-99 – Details and Detailing of Concrete Reinforcement.
- E. ANSI/ASTM A82 - Cold Drawn Steel Wire for Concrete Reinforcement.
- F. ANSI/ASTM A184 - Fabricated Deformed Steel Bar Mats for Concrete Reinforcement.
- G. ANSI/ASTM A185 - Welded Steel Wire Fabric for Concrete Reinforcement.
- H. ANSI/AWS D1.4 - Structural Welding Code for Reinforcing Steel.
- I. ASTM A615 - Deformed and Plain Billet Steel Bars for Concrete Reinforcement.
- J. AWS D12.1 - Welding Reinforcement Steel, Metal Inserts and Connections in Reinforced Concrete Construction.
- K. CRSI - Concrete Reinforcing Steel Institute - Manual of Standard Practice.
- L. CRSI - Placing Reinforcing Bars.

1.2 QUALITY ASSURANCE

- A. Perform Work in accordance with CRSI - Manual of Standard Practice & ACI 318.

1.3 COORDINATION

- A. Coordinate work under provisions of Section 01039.
- B. Coordinate with placement of formwork, formed openings and other Work.

PART 2 PRODUCTS

2.1 REINFORCEMENT

- A. Reinforcing Steel: ASTM A615, yield grade; deformed billet steel bars, unfinished.
- B. Reinforcing Steel Plain Bar and Rod Mats: ASTM A704, ASTM A615, Grade 60; steel bars or rods, unfinished.
- C. Stirrup Steel: ANSI/ASTM A82, unfinished.
- D. Welded Steel Wire Fabric: ASTM A815; in flat sheets.

2.2 ACCESSORY MATERIALS

- A. Tie Wire: Minimum gage annealed type.

- B. Chairs, Bolsters, Bar Supports, Spacers: Sized and shaped for strength and support of reinforcement during concrete placement conditions including load bearing pad on bottom to prevent vapor barrier puncture.
- C. Special Chairs, Bolsters, Bar Supports, Spacers Adjacent to Weather Exposed Concrete Surfaces: Plastic coated steel; size and shape as required.

2.3 FABRICATION

- A. Fabricate concrete reinforcing in accordance with CRSI Manual of Practice ACI SP-66.

PART 3 EXECUTION

3.1 PLACEMENT

- A. Place, support and secure reinforcement against displacement. Do not deviate from required position.
- B. Do not displace or damage vapor barrier.
- C. Accommodate placement of formed openings.
- D. Conform to applicable code for concrete cover over reinforcement.

END OF SECTION

03300

CAST-IN-PLACE CONCRETE

PART 1 GENERAL

1.1 REFERENCES

- A. ACI 301 - Structural Concrete for Buildings.
- B. ACI 302 - Guide for Concrete Floor and Slab Construction.
- C. ACI 304 - Recommended Practice for Measuring, Mixing, Transporting and Placing Concrete.
- D. ACI 305R - Hot Weather Concreting.
- E. ACI 306R - Cold Weather Concreting.
- F. ACI 318 - Building Code Requirements for Reinforced Concrete.
- G. ANSI/ASTM D994 - Preformed Expansion Joint Filler for Concrete (Bituminous Type).
- H. ANSI/ASTM D1190 - Concrete Joint Sealer, Hot-Poured Elastic Type.
- I. ANSI/ASTM D1751 - Preformed Expansion Joint Fillers for Concrete Paving and Structural Construction (Non-extruding and Resilient Bituminous Types).
- J. ANSI/ASTM D1752 - Preformed Sponge Rubber and Cork Expansion Joint Fillers for Concrete Paving and Structural Construction.
- K. ASTM C33 - Concrete Aggregates.
- L. ASTM C94 - Ready-Mixed Concrete.
- M. ASTM C150 - Portland cement.
- N. ASTM C260 - Air Entraining Admixtures for Concrete.

1.2 SUBMITTALS

- A. Submit under provisions of Section 01300.
- B. Product Data: Provide data on joint devices, attachment accessories and admixtures.

1.3 QUALITY ASSURANCE

- A. Perform Work in accordance with ACI 301.

1.4 COORDINATION

- A. Coordinate work under provisions of Section 01039.
- B. Coordinate the placement of joint devices with erection of concrete formwork and placement of form accessories.

PART 2 PRODUCTS

2.1 CONCRETE MATERIALS

- A. Cement: ASTM C150, Type I - Normal, Type II - Moderate, Type V - Sulfate Resistant.
- B. Fine and Coarse Aggregates: ASTM C33.
- C. Water: Clean and not detrimental to concrete.

2.2 ADMIXTURES

- A. Air Entrainment: ASTM C260.

2.3 ACCESSORIES

- A. Bonding Agent: Polymer resin emulsion.
- B. Vapor Barrier: thick clear polyethylene film.
- C. Non-Shrink Grout: Premixed compound consisting of non-metallic aggregate, cement, water reducing and plasticizing agents; capable of developing minimum compressive strength of 2,400 psi in 48 hours and 7,000 psi in 28 days.

2.4 JOINT DEVICES AND FILLER MATERIALS

- A. Joint Filler Type A: ASTM D1751; ASTM D994; Asphalt impregnated fiberboard or felt, 1/2" thick; tongue and groove profile.
- B. Joint Filler Type B: ASTM D1752; Closed cell polyvinyl chloride foam, resiliency recovery of 95 percent if not compressed more than 50 percent of original thickness.
- C. Joint Filler Type C; ASTM D1752; Pre-molded sponge rubber fully compressible with recovery rate of minimum 95 percent.
- D. Expansion Joint Devices: ASTM B221 alloy, extruded aluminum; resilient filler strip with a Shore A hardness of 35 to permit plus or minus 25 percent joint movement with full recovery; extruded aluminum cover plate, of longest manufactured length at each location, flush Mounted, color as selected.
- E. Sealant: ASTM D1190; polymer based asphalt or coal tar and rubber compound.

2.5 FIBEROUS REINFORCEMENT

- A. Fibrous concrete reinforcement shall be one hundred percent (100%) virgin polypropylene fibrillated fibers specifically manufactured for use as concrete reinforcement, containing no reprocessed olefin materials. The fibers shall have the following physical characteristics:
 - 1. Specific gravity – 0.91.
 - 2. Tensile strength – 70,000 to 110,000 psi.
 - 3. Fiber length – per manufacturer’s recommendation for specific use.
- B. Add fibrous concrete reinforcement to concrete materials at the time the concrete is batched in the amounts recommended by the manufacturer (1.5 lb/cubic yard for sidewalks) or as indicated on the accepted plans.
- C. Concrete shall be mixed in strict accord with the fibrous concrete reinforcement manufacturer’s instructions and recommendations to assure uniform and complete dispersion.

2.6 CONCRETE MIX

- A. All concrete shall be Type 1 cement with a compressive strength of 4,000 p.s.i. at 28 days.
- B. Mix concrete in accordance with ACI 304. Deliver concrete in accordance with ASTM C94.
- C. Use accelerating admixtures in cold weather only not to exceed 1%. Use of admixtures will not relax cold weather placement requirements.
- D. Use calcium chloride only when approved by Architect/Engineer.

- E. Use set retarding admixtures during hot weather only when approved by Architect/Engineer.
- F. Add air entraining agent to normal weight concrete mix for work exposed to exterior.

PART 3 EXECUTION

3.1 EXAMINATION

- A. Verify requirements for concrete cover over reinforcement.
- B. Verify that anchors, seats, plates, reinforcement and other items to be cast into concrete are accurately placed, positioned securely and will not cause hardship in placing concrete.

3.2 PREPARATION

- A. Prepare previously placed concrete by cleaning with steel brush and applying bonding agent in accordance with manufacturer's instructions.
- B. In locations where new concrete is dowelled to existing work, drill holes in existing concrete, insert steel dowels and pack solid with non-shrink grout.

3.3 PLACING CONCRETE

- A. Place concrete in accordance with ACI 304 & ACI 301.
- B. Notify Architect/Engineer minimum 24 hours prior to commencement of operations.
- C. Ensure reinforcement, inserts, embedded parts, formed expansion and contraction joints are not disturbed during concrete placement.
- D. Separate slabs on grade from vertical surfaces with 1/2" thick joint filler.
- E. Place joint filler in floor slab pattern placement sequence. Set top to required elevations. Secure to resist movement by wet concrete.
- F. Extend joint filler from bottom of slab to within 1/2 inch of finished slab surface. Conform to Section 07900 for finish joint sealer requirements.
- G. Install joint devices in accordance with manufacturer's instructions.
- H. Install construction joint devices in coordination with floor slab pattern placement sequence. Set top to required elevations. Secure to resist movement by wet concrete.
- I. Install joint device anchors. Maintain correct position to allow joint cover to be flush with floor and wall finish.
- J. Install joint covers in longest practical length, when adjacent construction activity is complete.
- K. Apply sealants in joint devices in accordance with Section 07900.
- L. Place concrete continuously between predetermined expansion, control and construction joints.
- M. Do not interrupt successive placement; do not permit cold joints to occur.
- N. Place floor slabs in pattern indicated on drawings.
- O. Saw cut joints within 24 hours after placing. Use 3/16" thick blade, cut into 1/4 depth of slab thickness. If in-slab-heating is used cut joints 1/2 inch deep.
- P. Screed floors and slabs on grade level, maintaining surface flatness of maximum.

3.4 SEPARATE FLOOR TOPPINGS

- A. Prior to placing floor topping, roughen substrate concrete surface and remove deleterious material. Broom and vacuum clean.
- B. Place required dividers, edge strips, reinforcing, and other items to be cast in.
- C. Apply bonding agent to substrate in accordance with manufacturer's instructions.

3.5 CONCRETE FINISHING

- A. Provide formed concrete surfaces to be left exposed with smooth rubbed finish.
- B. Finish concrete floor surfaces to requirements of Section 03346.

3.6 CURING AND PROTECTION

- A. Immediately after placement, protect concrete from premature drying, excessively hot or cold temperatures, and mechanical injury.
- B. Maintain concrete with minimal moisture loss at relatively constant temperature for period necessary for hydration of cement and hardening of concrete.
- C. Cure concrete floor surfaces to requirements of Section 03370.
- D. Cure floor surfaces in accordance with ACI 308.

3.7 FIELD QUALITY CONTROL

- A. Field inspection and testing will be performed in accordance with ACI 301 and under provisions of Section 01400.
- B. Provide free access to Work and cooperate with appointed firm.
- C. Submit proposed mix design to architect for review prior to commencement of Work.
- D. Contractor shall supply testing of cement and aggregates to ensure conformance with specified requirements.
- E. Contractor shall provide three concrete test cylinders per day for every 75 or less cu yards of concrete placed.
- F. One additional test cylinder will be taken during cold weather concreting, cured on job site under same conditions as concrete it represents.
- G. Contractor shall provide one slump test to be taken for each set of test cylinders taken.

3.8 PATCHING

- A. Allow Architect/Engineer to inspect concrete surfaces immediately upon removal of forms.
- B. Excessive honeycomb or embedded debris in concrete is not acceptable. Notify Architect/Engineer upon discovery.
- C. Patch imperfections as directed.

3.9 DEFECTIVE CONCRETE

- A. Defective Concrete: Concrete not conforming to required lines, details, dimensions, tolerances or specified requirements.
- B. Repair or replacement of defective concrete will be determined by the Architect/Engineer.
- C. Do not patch, fill, touch-up, repair, or replace exposed concrete except upon express direction of Architect/Engineer for each individual area.

END OF SECTION

03370

CONCRETE CURING

PART 1 GENERAL

1.1 REFERENCES

- A. ACI 301 - Structural Concrete for Buildings.
- B. ACI 302 - Recommended Practice for Concrete Floor and Slab Construction.
- C. ACI 308 - Standard Practice for Curing Concrete.
- D. ASTM C309 - Liquid Membrane-Forming Compounds for Curing Concrete.
- E. ASTM D2103 - Polyethylene Film and Sheeting.

1.2 QUALITY ASSURANCE

- A. Perform Work in accordance with ACI 301 and ACI 302.

1.3 DELIVERY, STORAGE, AND HANDLING

- A. Deliver, store, protect, and handle products under provisions of Section 01600.
- B. Deliver curing materials in manufacturer's packaging including application instructions.

PART 2 PRODUCTS

2.1 MATERIALS

- A. Curing/sealing compound equal to Ashford Formula as distributed by:
Curecrete Chemical Company, Inc.
1201 W. Spring Creek Place
Springville, UT 84663
(801)489-5663

PART 3 EXECUTION

3.1 EXAMINATION

- A. Verify that substrate surfaces are ready to be cured.

3.2 EXECUTION - HORIZONTAL SURFACES

- A. Cure floor surfaces in accordance with ACI 308.

3.3 EXECUTION - VERTICAL SURFACES

- A. Cure surfaces in accordance with ACI 308.

3.4 PROTECTION OF FINISHED WORK

- A. Protect finished Work under provisions of Section 01500.
- B. Do not permit traffic over unprotected floor surface.

END OF SECTION

05500

METAL FABRICATIONS

PART 1 GENERAL

1.1 REFERENCES

- A. ASTM A36 - Structural Steel.
- B. ASTM A53 - Hot-Dipped, Zinc-coated Welded and Seamless Steel Pipe.
- C. ASTM A123 - Zinc (Hot-Dip Galvanized) Coatings on Iron and Steel Products.
- D. ASTM A283 - Carbon Steel Plates, Shapes and Bars.
- E. ASTM A307 - Carbon Steel Bolts and Studs, 60,000 p.s.i Tensile Strength.
- F. ASTM A500 - Cold-Formed Welded and Seamless Carbon Steel Structural Tubing in Round and Shapes.
- G. ASTM A501 - Hot-Formed Welded and Seamless Carbon Steel Structural Tubing.
- H. AWS A2.0 - Standard Welding Symbols.
- I. AWS D1.1 - Structural Welding Code.
- J. SSPC (Steel Structures Painting Council) - Steel Structures Painting Manual.

PART 2 PRODUCTS

2.1 MATERIALS - STEEL

- A. Steel Sections: ASTM A36.
- B. Steel Tubing: ASTM A500, Grade B.
- C. Plates: ASTM A283.
- D. Pipe: ASTM A53, Grade B, Schedule 40.
- E. Bolts, Nuts, and Washers: ASTM A325 galvanized to ASTM A153 for galvanized components.
- F. Welding Materials: AWS D1.1; type required for materials being welded.
- G. Ladders: ANSI A14.3.
- H. Shop and Touch-Up Primer: SSPC 15, Type 1, red oxide.

2.2 FABRICATION

- A. Fit and shop assemble items in largest practical sections, for delivery to site.
- B. Fabricate items with joints tightly fitted and secured.
- C. Grind exposed joints flush and smooth with adjacent finish surface. Make exposed joints butt tight, flush and hairline. Ease exposed edges to small uniform radius.
- D. Exposed Mechanical Fastenings: Flush countersunk screws or bolts; unobtrusively located; consistent with design of component, except where specifically noted otherwise.
- E. Supply components required for anchorage of fabrications. Fabricate anchors and related components of same material and finish as fabrication, except where specifically noted otherwise.

2.3 FABRICATION TOLERANCES

- A. Squareness: 1/8-inch maximum difference in diagonal measurements.
- B. Maximum Offset Between Faces: 1/16 inch.
- C. Maximum Misalignment of Adjacent Members: 1/16 inch.
- D. Maximum Bow: 1/8 inch in 48 inches.
- E. Maximum Deviation From Plane: 1/16 inch in 48 inches.

2.4 FINISHES - STEEL

- A. Clean surfaces of rust, scale, grease, and foreign matter prior to finishing.

- B. Do not prime surfaces in direct contact with concrete or where field welding is required.
- C. Prime paint items with one coat.
- D. Structural Steel Members: Galvanize after fabrication to ASTM A123. Provide minimum 1.25 oz/sq ft galvanized coating.
- E. Non-structural Items: Galvanized after fabrication to ASTM A123. Provide minimum 1.25 oz/sq ft galvanized coating.
- F. Chrome Plating: ASTM B177, weight, nickel-chromium alloy, satin finish.

PART 3 EXECUTION

3.1 EXAMINATION

- A. Verify that field conditions are acceptable and are ready to receive work.

3.2 PREPARATION

- A. Clean and strip primed steel items to bare metal where site welding is required.
- B. Supply steel items required to be cast into concrete or embedded in masonry with setting templates to appropriate sections.

3.3 INSTALLATION

- A. Install items plumb and level, accurately fitted, free from distortion or defects.
- B. Provide for erection loads, and for sufficient temporary bracing to maintain true alignment until completion of erection and installation of permanent attachments.
- C. Field weld components indicated on Drawings.
- D. Perform field welding in accordance with AWS D1.1.
- E. Obtain approval prior to site cutting or making adjustments not scheduled.
- F. After erection, prime welds, abrasions, and surfaces not shop primed or galvanized, except surfaces to be in contact with concrete.

3.4 ERECTION TOLERANCES

- A. Maximum Variation From Plumb: 1/4 inch per story, non-cumulative.
- B. Maximum Offset From True Alignment: 1/4 inch.
- C. Maximum Out-of-Position: 1/4 inch.

END OF SECTION

07210

BUILDING INSULATION

PART 1 GENERAL

1.1 SUMMARY

- A. Provide building insulation where shown on the Drawings, as specified herein and as needed for a complete and proper installation.
- B. Related work:
 - 1. Documents affecting work of this Section include but are not necessarily limited to, General Conditions, Supplementary Conditions and Sections in Division 1 of these Specifications.

1.2 SUBMITTALS FOR REVIEW

- A. Section 01300 - Submittals: Procedures for submittals.
- B. Product Data: Provide for all insulating products.

1.3 QUALITY ASSURANCE

- A. Use adequate numbers of skilled workmen who are thoroughly trained and experienced in the necessary crafts and who are completely familiar with the specified requirements and the methods needed for proper performance of the work of this Section.
- B. Upon completion of this portion of the Work, complete and post a certificate of insulation compliance in accordance with pertinent requirements of governmental agencies having jurisdiction.

1.4 DELIVERY, STORAGE AND HANDLING

- A. Comply with pertinent provisions of Section 01600.

PART 2 PRODUCTS

2.1 MATERIALS

- A. Provide the following building insulation where shown on the Drawings or otherwise needed to achieve the degree of insulation required under pertinent regulations of governmental agencies having jurisdiction.
 - 1. Exterior Wall Insulation - R-25 fiberglass batt insulation installed between the girts. Provide full height 6 mil. vapor barrier fabric between the girts and interior liner panels.

2.2 OTHER MATERIALS

- A. Provide 6 mil. vapor barrier where specified on drawings.
- B. Provide other materials, not specifically described but required for a complete and proper installation, as selected by the Contractor subject to the approval of the Architect.
- C. Provide as follows (1) 22" x 48" insulation baffle between each 24" rafter spacing or (1) 16" x 48" insulation baffle between each 16" rafter spacing or (2) 22" x 48" insulation baffles between each 4'-0" rafter spacing or (5) 22" x 48" insulation baffles between each 10'-0" rafter spacing down the length of building both sides.

PART 3 EXECUTION

3.1 SURFACE CONDITIONS

- A. Examine the areas and conditions under which work of this Section will be performed. Correct conditions detrimental to timely and proper completion of the Work. Do not proceed until unsatisfactory conditions are corrected.
- B. Remove, or protect against, projections in construction framing that may damage or prevent proper insulation.

3.2 INSTALLATION

- A. Install the work of this Section in strict accordance with the original design, requirements of governmental agencies having jurisdiction, and the manufacturer's recommended installation procedures as approved by the Architect, anchoring all components firmly into position.

END OF SECTION

FLASHING AND SHEET METAL

PART 1 GENERAL

1.1 DISCRIPTION OF WORK

- A. Fascia Systems.
- B. Metal Roof Flashing and Trim.

1.2 REFERENCES

- A. ASTM A 526 – Standard Specification for Steel Sheet, Zinc-Coated (Galvanized) by the Hot-Dip Process, Commercial Quality.
- B. ASTM A 527 – Specification for Steel Sheet, Zinc-Coated (Galvanized) by the Hot-Dip Process, Lock-Forming Quality.
- C. ASTM B 209 – Standard Specification for Aluminum and Aluminum-Alloy Sheet and Plate.
- D. National Roofing Contractors Association (NRCA) – “Roofing and Waterproofing Manual” third edition.
- E. Sheet Metal and Air Conditioning Contractor’s National Association (SMACNA) – Architectural Sheet Metal Manual.

1.3 SUBMITTALS

- A. Submit under provisions of Section 01300.
- B. Manufacturer’s data sheets on each product to be used, including:
 - 1. Preparation instructions and recommendations.
 - 2. Storage and handling requirements and recommendations.
 - 3. Installation method.
- C. Shop Drawings:
 - 1. Indicate material profile, dimensions, jointing pattern, jointing details, fastening methods, flashing, termination, and installation details.
 - 2. Show the layout of wall sections, attachment, joint details, trim flashing, accessories and air infiltration seals.
 - 3. Show thickness of treated wood nailers and substrate.
- D. Design Data:
 - 1. Submit manufacturer’s certification that product supplied meets Factory Mutual Research Corporation’s (FMRC) requirements for Roof Perimeter Flashing for use in Zone 1 and Zone 2 Windstorm Resistance Areas as defined in FME & R Loss Prevention Data Sheet 1-7 and 1-49 design recommendations, and meets the wind resistance requirements specified.
 - 2. Certify that perimeter metal edge systems furnished meet the specified design pressures as tested using ANSI/SPRI ES-1-98 test method RE-2 or RE-3 test methodology.
 - 3. Certify that membrane attachment by perimeter edge systems exceeds 100 lb/ft of force as tested by ANSI/SPRI ES-1-98 test method RE-1.
- E. Verification Samples: For each finish product specified, two samples, minimum size 6 inches square, representing actual product, color, and pattern.

1.4 QUALITY ASSURANCE

- A. Installer qualifications: Companies specializing in sheet metal work with 5 years documented experience.

1.5 DELIVERY, STORAGE, AND HANDLING

- A. Store products in manufacturer's unopened packaging until ready for installation.
- B. Store and dispose of solvent-based materials, and materials used with solvent-based materials, in accordance with requirements of local authorities having jurisdiction.
- C. Materials shall be delivered with identification labels, warnings and storage recommendations.
- D. Materials shall be stored in a clean, dry location prior to installation to prevent any damage to the contents. Store materials off the ground and protect from damage and deterioration as required by the material manufacturer.
- E. Handle materials to prevent damage to their surfaces, edges and ends of metal items. Damaged material shall be rejected and immediately removed from the site.

1.6 PROJECT CONDITIONS

- A. Maintain environmental conditions (temperature, humidity, and ventilation) within limits recommended by manufacturer for optimum results. Do not install products under environmental conditions outside manufacturer's absolute limits.

1.7 WARRANTY

- A. Warranty Certification: Installing contractor shall certify that sheet metal work has been installed per National Sheet Metal System's printed details and specifications.
- B. Manufacturer warrants sheet metal fabrications are warranted to be free of defects in material and workmanship for a period of five (5) years from date of shipment.
- C. Provide manufacturer's Twenty (20) year finish warranty for standard coil-coated 40-year polyester finish colors against peeling, chalking, fading, checking and crazing, commencing upon date of final completion.
- D. No other warranties either expressed or implied are acceptable unless so stated in writing.

PART 2 PRODUCTS

2.1 MANUFACTURERS

- A. Central States or equal; Toll Free 1-800-356-2733.
Local supplier- Mac Steel Inc., 17982 Elder Road, Diamond MO 64840. macstell@jscomm.net
Phone: 1-677-209-0886.
- B. Equal to 26 ga. Panel-Loc Plus 40 year polyester paint with minimum of 0.80 top coat thickness.
- C. Other manufacturer's as approved by the Architect.

2.2 FASCIA AND ROOF EDGE SYSTEMS

- A. Provide fascia/flashing system which meets the criteria recommended by Factory Mutual Research Corporation's (FRMC) requirements for Roof Perimeter Flashing for use in Zone 1 and Zone 2 Windstorm Resistance Areas as defined in FME & R Loss Prevention Data Sheet 1-7 and 1-49.
- B. 2-Piece Fascia:
 - 1. As shown on details.
- C. Accessories:
 - 1. Closure Cleat.
 - 2. Custom Fabrications as shown on details.
- D. Fascia Covers and Accessories to be Fabricated from:
 - 1. .050 inch aluminum ASTM B 209 3105-H14 alloy.
- E. Waterdam Components:
 - 1. 0.040 inch aluminum ASTM B 209 3105-H14 alloy.

- F. Standard Length of Product: Produce components in longest possible lengths for system specified.
- G. Aluminum Finish:
 - 1. 40-year polyester paint with minimum of 0.80 top coat thickness from manufacturer's standard coil-coated colors.
 - a. Color – Picked by District Facilities Manager.

2.3 METAL ROOF FLASHING & TRIM

- A. Profile: As indicated on Roof Manufacturer's standard details.
 - 1. Pitch Break.
 - 2. Valley Flashing.
 - 3. Peak Flashing.
 - 4. Ridge/Hip Flashing.
 - 5. Eave Flashing.
 - 6. Outside Corner Flashing.
 - 7. Inside Corner Flashing.
 - 8. Material and Finish: 26 ga. Steel galvanized/paint grip.
- B. Steel Finish:
 - 1. Prefinished steel with 40-year polyester paint from manufacturer's standard colors.

2.4 MATERIALS

- A. Prefinished Zinc-Coated Steel: Hot-dip galvanized steel, commercial quality A1 S1 G90 extra smooth, primed on both sides and finished on 1 side with 40-year polyester paint with minimum of 0.80 top coat thickness.
 - 1. Strippable coating: Shop-applied liquid to front side of pre-finished metal to protect finish during fabrication, shipment, and field handling.
- B. Prefinished Aluminum Sheet: ASTM B 209, alloy 3003, coil-coated, 40-year polyester paint based on minimum of 0.80 top coat thickness.

2.5 FABRICATION

- A. General Metal Fabrication: Shop-fabricate work to the greatest extent possible. Comply with details indicated on Drawings, and with applicable requirements of SMACNA. Fabricate for waterproof and weather-resistant performance; with expansion provisions for running work. Form work to fit substrates. Comply with material manufacturer instructions and recommendations for forming material. Form exposed sheet metal work without excessive oil-canning, buckling, and tool marks, true to line and levels indicated, with exposed edges folded back to form hems.
- B. Seams: Fabricate non-moving seams in sheet metal with flat-lock seams. Form seams and solder tin edges to be seamed.
- C. Expansion and Contraction:
 - 1. Provide for thermal expansion and contraction, and building movement in completed work, without over-stressing the material, breaking connections, or producing wrinkles and distortion in finished surfaces. Make watertight and weather-resistant.
 - 2. Where subject to thermal expansion and contraction, attach members with clips to permit movement without damage, or provide slotted or oversize holes with washers only, as acceptable to Architect.
 - 3. Make lock seam work flat and true to line, and sweat full of solder, except where installed to permit expansion and contraction.
 - a. Lap flat lock seams and soldered lap seams according to pitch, but in no case less than 3 inches. Make seams in direction of flow.
- D. Sealant Joints: Where movable, non-expansion type joints are indicated, or required for proper performance of work, form metal to provide for proper installation of sealant per SMACNA standards.

- E. Metal Separation: Separate metal from non-compatible metal or corrosive substrates by coating concealed surfaces at locations of contact with bituminous coatings or other permanent separation as recommended by manufacturer.
- F. Soldering:
 1. Clean material and tin prior to soldering. Solder with heavy coppers of blunt design, properly tinned before use.
 2. Solder slowly with well-heated coppers. Heat seams thoroughly and completely fill with solder.
 3. Make exposed joints on finish surfaces full flowing and smooth.
 4. Wash acid flux with soda solution after soldering, and remove soldering flux on exposed and painted surfaces.
- G. Accessories:
 1. Factory assemblies shall be furnished to maintain watertight integrity.
 2. Provide matching accessories or other special fabrications from the manufacturer; color to match specified profile unless noted otherwise.
- H. Fascia/flushing sections furnished with strippable protective vinyl masking shall have film removed immediately before installation to prevent damage to the coating if left exposed to the ultra-violet rays of sunlight.

PART 3 EXECUTION

3.1 EXAMINATION

- A. Do not begin installation until substrates have been properly prepared.
- B. If substrate preparation is the responsibility of another installer, notify Architect of unsatisfactory preparation before proceeding.

3.2 PREPARATION

- A. Clean surfaces thoroughly prior to installation.
- B. Prepare surfaces using the methods recommended by the manufacturer for achieving the best result for the substrate under the project conditions.

3.3 INSTALLATION

- A. Install in accordance with manufacturer's instructions.
- B. Except as otherwise indicated, comply with SMACNA recommendations.
- C. Anchor units of work securely in place by methods indicated, providing for thermal expansion of metal units. Conceal fasteners wherever possible, and set units true to line and level. Install work with laps, joints, and seams that will be permanently watertight and weather-restive.
- D. Strictly follow the material manufacturer's printed installation requirements.
- E. Completed work shall be true to line without buckling, creasing, warp or wind in finished surfaces. "Oil-canning" surfaces are not acceptable.
- F. Isolate dissimilar metals, masonry or concrete from metals using bituminous paint, tape or slip-sheet. Use gasketed fasteners where required to prevent corrosive actions.
- G. Allow sufficient clearances for expansion and contraction of linear metal components. Secure metal using continuous cleats, clips and fasteners as required by the system. No exposed face fastening shall be accepted.

3.4 PROTECTION

- A. Protect installed products until completion of project.
- B. Maintain prefinished surfaces in undamaged condition until date of final completion. Repair or replace damaged components, any touch-up to be indistinguishable from undamaged surface/finish.

- C. Upon completion of work, a final inspection by the owner's representative shall be made. Any necessary corrective actions will be noted and the installing contractor shall make corrections within five (5) working days. Upon acceptance of the project, any applicable warranties shall be presented to the owner's representative.

END OF SECTION

SPRAYED INSULATION**PART 1 GENERAL****1.1 SUMMARY**

- A. Section Includes: Medium-density, polyurethane spray foam insulation.
- B. Coordinate mechanical ventilation and fresh air supply with Mechanical sections and ASHRAE Guidelines for optimum indoor air quality.

1.2 REFERENCES

- A. American Society for Testing and Materials International (ASTM).
 1. ASTM C 518: Standard Test Method for Steady-State Thermal Transmission Properties by Means of the Heat Flow Meter Apparatus.
 2. ASTM E 84: Test Method for Surface Burning Characteristics of Building Materials.
 3. ASTM E 96: Standard Test Methods for Water Vapor Transmission of Materials.
 4. ASTM E 283: Standard Test Method for Determining Rate of Air Leakage Through Exterior Windows, Curtain Walls, and Doors Under Specified Pressure Differences Across the Specimen.

1.3 SUBMITTALS

- A. Product Data for each type of insulation product specified.
- B. Product test reports performed by a qualified third-party testing agency evidencing compliance of insulation products with specified requirements including those for thermal resistance, fire-test-response characteristics, water-vapor transmission, and other properties, based on comprehensive testing of current products.
- C. Evaluation Report: Evidence of compliance of foam-plastic insulations with International Building Code (IBC), International Residential Code (IRC), International Energy Conservation Code (IECC).
- D. Manufacturer's certificate certifying insulation provided meets or exceeds specified requirements.
- E. Installer's certificate showing the Icynene installation certification (or equal).
- F. Sample warranty.

1.4 QUALITY ASSURANCE

- A. Manufacturer's Qualifications: Product produced in an ISO 9001 registered factory.
- B. Single Source Responsibility: Single source product from one manufacturer.
- C. Installer Qualifications: Engage an Icynene (or equal) Licensed Dealer (installer) who has been trained and certified by Icynene.
- D. Fire-Test-Response Characteristics: Provide materials specified as determined by testing identical products per test method indicated below by a testing and inspecting agency acceptable to authorities having jurisdiction. Identify materials with appropriate markings of applicable testing and inspecting agency.
 1. Surface-Burning Characteristics: ASTM E 84.
- E. Toxicity/Hazardous Materials.
 1. Provide products that contain no urea-formaldehyde.
 2. Provide products that contain no PBDEs.
 3. Provide products that are "Low-emitting".

1.5 DELIVERY, STORAGE, AND HANDLING

- A. Comply with manufacturers written instructions for handling and protection prior to and during installation.

- B. Store both components in a temperature controlled area between 65 and 85 degrees F. Do not allow product to freeze.
- C. Use only those components that are supplied by the Manufacturer.

1.6 PROJECT CONDITIONS

- A. Do not expose to sunlight, except to extent necessary for period of installation and concealment.

1.7 WARRANTY

- A. Residential projects: Manufacturer's standard limited lifetime warranty.
- B. Refer to www.Icynene.com (or equal) for full warranty terms.

PART 2 - PRODUCTS

2.1 MANUFACTURERS

- A. Polyurethane Spray Foam Insulation: ICYNENE MD-C-200TM (or equal) by Icynene Inc.

2.2 MATERIALS

- A. General: Provide insulating materials that comply with requirements and with referenced standards.
- B. Equal to ICYNENE MD-C-200TM Spray Foam Insulation: Medium-density, closed cell, conforming to the following:
 - 1. Thermal Resistance (for 1 inch of material) (R-Value/inch @75 deg F): ASTM C 518; 6.5 hr.sq ft.degree F/BTU .
 - 2. Air Permeance (for 1 inch of material): ASTM E 283: <0.02 L/s.m2 @75 Pa.
 - 3. Water Vapor Transmission (for 1.5 inches of material): ASTM E 96; 0.9 perms.
 - 4. Flame Spread and Smoke Developed Rating: ASTM E 84.
 - a. Flame Spread: Less than 25.
 - b. Smoke Development: Less than 450.
- C. Product Description:
 - 1. Collaborative for High-Performance Schools (CHPS) "Low-emitting material" per CA 01350 Criteria.

2.3 SOURCE QUALITY CONTROL

- A. Product produced in an ISO 9001 registered factory.

PART 3 – EXECUTION

3.1 EXAMINATION

- A. Examine substrates and conditions, under which work is to be performed. Do not proceed until unsatisfactory conditions have been corrected.

END OF SECTION

08111

STANDARD STEEL DOORS

PART 1 GENERAL

1.1 REFERENCES

- A. ANSI A117.1 - Specifications for Making Buildings and Facilities Accessible to and Usable by Physically Handicapped People.
- B. ASTM A525 - Steel Sheet, Zinc-Coated (Galvanized) by the Hot-Dip Process.
- C. ASTM E152 - Methods of Fire Tests of Door Assemblies.
- D. NFPA 80 - Fire Doors and Windows.
- E. NFPA 252 - Fire Tests for Door Assemblies.
- F. SDI-100 - Standard Steel Doors and Frames.
- G. UL 10B - Fire Tests of Door Assemblies.

1.2 SUBMITTALS FOR REVIEW

- A. Section 01300 - Submittals: Procedures for submittals.
- B. Shop Drawings: Indicate door elevations, internal reinforcement, closure method and cutouts for glazing and louvers.

1.3 SUBMITTALS FOR INFORMATION

- A. Section 01300 - Submittals: Procedures for submittals.
- B. Manufacturer's Certificate: Certify that Products meet or exceed specified requirements.

1.4 QUALITY ASSURANCE

- A. Manufacturer: Specializing in manufacturing products specified in this section with three years experience.

1.5 REGULATORY REQUIREMENTS

- A. Installed Door and Panel Assembly: Conform to NFPA 80 for fire rated class as scheduled.

1.6 DELIVERY, STORAGE AND PROTECTION

- A. Section 01600 - Material and Equipment: Transport, handle, store and protect products.
- B. Accept doors on site in manufacturer's packaging. Inspect for damage.
- C. Break seal on site to permit ventilation.

1.7 PROJECT CONDITIONS

- A. Coordinate frame installation with size, location, and installation of service utilities.
- B. Coordinate the work with door opening construction, doorframes and door hardware installation.
- C. Sequence installation to ensure wire connections are achieved in an orderly and expeditious manner.

PART 2 PRODUCTS

2.1 ACCEPTABLE PRODUCTS:

- A. Allied Steel Products, Inc.

- B. Amweld/Div. American Welding & Mfg. Co.
- C. Ceco Corp.
- D. Curries Mfg., Inc.
- E. Mesker Door, Inc.
- F. Steelcraft/Div. American Standard Co.
- G. Republic Builders Products Corp./Subs. Republic Steel.

2.2 DOORS AND PANELS

- A. Astragals for Double Doors: Steel T shaped, specifically for double doors (As required).
- B. Fabricate doors with hardware reinforcement welded in place.
- C. Attach fire rated label to each fire rated door unit.
- D. Configure exterior doors with special profile to receive recessed weather stripping.
- E. Type and Design:
 - 1. Tightly hemmed vertical seam on lock and hinge edges, with top flush channel and beveled lock edge, in the dimensions and types shown on the drawings, reinforced for the finish hardware being provided under Section 08710 of these Specifications, and in the following gauges:
 - a. Interior Doors: 18 gauge honeycomb core. Labeled and/or Non-labeled.
 - b. Exterior Doors: 16 gauge insulated core. Labeled and/or Non-labeled.

2.3 FINISH

- A. Steel Sheet: Exterior doors to be galvanized to ASTM A525.
- B. Primer: Air-dried.
- C. Paint per Specification Section 09900: color as selected.

PART 3 EXECUTION

3.1 EXAMINATION

- A. Verify that opening sizes and tolerances are acceptable.

3.2 INSTALLATION

- A. Install doors in accordance with SDI-100 and DHI.
- B. Coordinate installation of glass and glazing.
- C. Install door louvers, plumb and level.
- D. Coordinate installation of doors with installation of frames and hardware specified in Section 08710.
- E. Touch-up finished doors.

3.3 ERECTION TOLERANCES

- A. Maximum Diagonal Distortion: 1/16 inch measured with straight edge, corner to corner.

3.4 ADJUSTING

- A. Section 01650 - Starting of Systems: Adjusting installed work.
- B. Adjust door for smooth and balanced door movement.

3.5 SCHEDULE

- A. Refer to Door and Frame Schedule on architectural drawings.

END OF SECTION

08112

STANDARD STEEL FRAMES

PART 1 GENERAL

1.1 REFERENCES

- A. ANSI A117.1 - Specifications for Making Buildings and Facilities Accessible to and Usable by Physically Handicapped People.
- B. ASTM A525 - Steel Sheet, Zinc-Coated (Galvanized) by the Hot-Dip Process.
- C. ASTM E152 - Methods of Fire Tests of Door Assemblies.
- D. DHI - Door Hardware Institute: The Installation of Commercial Steel Doors and Steel Frames, Insulated Steel Doors in Wood Frames and Builder's Hardware.
- E. NFPA 80 - Fire Doors and Windows.
- F. NFPA 252 - Fire Tests for Door Assemblies.
- G. SDI-100 - Standard Steel Doors and Frames.
- H. UL 10B - Fire Tests of Door Assemblies.

1.2 SUBMITTALS FOR REVIEW

- A. Section 01300 - Submittals: Procedures for submittals.
- B. Shop Drawings: Indicate frame elevations, reinforcement, anchor types and spacing, location of cutouts for hardware and finish.

1.3 QUALITY ASSURANCE

- A. Manufacturer: Company specializing in manufacturing the Products specified in this section with minimum three years documented experience.

1.4 REGULATORY REQUIREMENTS

- A. Fire Rated Frame Construction: Conform to NFPA 252 or UL 10B.
- B. Installed Frame Assembly: Conform to NFPA 80 for fire rated class same as fire door.

1.5 DELIVERY, STORAGE AND PROTECTION

- A. Section 01600 - Material and Equipment: Transport, handle, store and protect products.
- B. Accept frames on site in manufacturer's packaging. Inspect for damage.

1.6 PROJECT CONDITIONS

- A. Coordinate the work with frame opening construction, door and hardware installation.
- B. Sequence installation to ensure wire connections are achieved in an orderly and expeditious manner.

1.7 FRAMES

- A. Frames: To suit SDI-100 Grade and Model of door specified in Section 08111.

PART 2 PRODUCTS

2.1 FRAMES

- A. 16 gauge. To suit SDI-100 Grade.

1. Provide drywall wrap around frames for interior and exterior doors.

2.2 ACCESSORIES

- A. Removable Stops: Rolled steel channel shape, butted corners; prepared for countersink style tamper proof screws.
- B. Bituminous Coating: Fibered asphalt emulsion.
- C. Primer: Zinc chromate type.
- D. Silencers: Install where weatherstripping is not used in Hardware Schedule.
- E. Weatherstripping: Specified in Section 08710.

2.3 FABRICATION

- A. Fabricate frames as welded unit.
- B. Mullions for Double Doors: Fixed type, of same profiles as jambs.
- C. Transom Bars for Glazed Lights: Fixed type, of same profiles as jamb and head.
- D. Fabricate frames with hardware reinforcement plates welded in place. Provide mortar guard boxes.
- E. Reinforce frames wider than 4" with roll formed steel channels fitted tightly into frame head, flush with top.
- F. Configure exterior frames with special profile to receive recessed weather stripping.
- G. Attach fire rated label to each fire rated door unit.

2.4 FINISH

- A. Steel Sheet: Galvanized.
- B. Primer: Air-dried.
- C. Paint per Specification Section 09900: color as selected.
- D. Coat inside of frame profile with bituminous coating.

PART 3 EXECUTION

3.1 EXAMINATION

- A. Verify that opening sizes and tolerances are acceptable.

3.2 INSTALLATION

- A. Install frames in accordance with SDI-100 and DHI.
- B. Coordinate with masonry, gypsum board or concrete wall construction for anchor placement.
- C. Coordinate installation of glass and glazing.
- D. Coordinate installation of frames with installation of hardware specified in Section 08710 and doors in Section 08111.
- E. Install roll formed steel reinforcement channels between two abutting frames. Anchor to structure and floor.

3.3 ERECTION TOLERANCES

- A. Maximum Diagonal Distortion: 1/8" measured with straight edges, crossed corner to corner.

3.4 SCHEDULE

- A. Refer to Door Schedule on drawings.

END OF SECTION

OVERHEAD COILING DOORS

PART 1 GENERAL

1.1 SUMMARY

- A. Provide overhead coiling doors where shown on the Drawings, as specified herein and as needed for a complete and proper installation.
- B. Related work:
 - 1. Documents affecting work of this Section include but are not necessarily limited to, General Conditions, Supplementary Conditions and Sections in Division 1 of these Specifications.

1.2 SUBMITTALS

- A. Comply with pertinent provisions of Section 01300.
- B. Product data: Within 45 calendar days after the Contractor has received the Owner's Notice to Proceed, submit:
 - 1. Materials list of items proposed to be provided under this section.
 - 2. Manufacturer's specifications and other data needed to prove compliance with the specified requirements;
 - 3. Shop Drawings in sufficient detail show fabrication, installation, anchorage and interface of the work of this Section with the work of adjacent trades.
 - 4. Manufacturer's recommended installation procedures which, when approved or rejecting actual installation procedures used on the Work.

1.3 QUALITY ASSURANCE

- A. Use adequate numbers of skilled workman who are thoroughly trained and experienced in the necessary crafts and who are completely familiar with the specified requirements and the methods needed for the proper performance of the work of this Section.

1.4 DELIVERY, STORAGE AND HANDLING

- A. Comply with the pertinent provisions of Section 01600.

PART 2 PRODUCTS

2.1 OVERHEAD COILING DOORS

- A. Provide standard rollup service doors of the dimensions and arrangements shown on the Drawings and with the following attributes:
 - 1. Design wind load: 20PSF.
 - 2. Curtain: Interlocking, rolling formed, fully foamed-in-place, insulated, flat profile. The front slat shall be fabricated from minimum 22 gauge-galvanized steel, with the back slat to be fabricated from minimum 24 gauge.
 - 3. Bottom Bar: Extruded aluminum member, to reinforce the curtain in the guides and will have a vinyl weather seal attached.
 - 4. Guides: Hot-dipped galvanized structural steel shapes attached to continuous steel wall angle for door(s). Three structural steel angles with a minimum thickness of 3/16" for door(s). Guides will be weather stripped with a vinyl weather seal at each jamb on the interior and exterior curtain side.
 - 5. Brackets: Galvanized steel plate to support the counterbalance curtain and hood.
 - 6. Counterbalance: Helical torsion springs housed in a galvanized steel tube.

7. Weatherseals: Vinyl bottom seal, exterior guide and internal hood seals. Include header brush or broom seal with aluminum extrusion.
 8. Hood: Aluminum.
 9. Operation: Motor and chain.
 10. Finish: Curtain slats shall be galvanizes per ASTM A-525 and shall receive a rust-inhibitive, roll coating process, including bonderizing, baked on prime paint to be .2 mils thick and a baked on polyester top coat to be .6 mils thick. All non-galvanized exposed ferrous surfaces will receive one coat of rust-inhibitive primer. All aluminum will be furnished in a clear mill finish. Door(s) to have factory white paint on both sides.
 11. Electric Sensing Edge: Provide for each door. Provide safety edges by Air Wave, Miller Edge, Model number MTAW21YB-U-door width minus 2" with coil cord or equal, extend full width of the door. Provide AW12 Air Wave waterproof switch. Upon contact with an obstruction the downward travel of the door shall be stopped or reversed.
- B. Provide electric motor operator with three position pushbutton operation, in capacity recommended by the manufacturer. See specification Section 08720.
- C. Acceptable products:
1. Model 625 Series face mounted rolling service door manufactured by Overhead Door Corporation P.O. Box 809046, Dallas, Texas 75380. 1-800-887-3667.
 2. Equal products of other manufacturers when approved in advance by the Architect.

2.2 OTHER MATERIALS

- A. Provide other materials, not specifically described but required for a complete and proper installation, as selected by the Contractor to the approval of the Architect.

PART 3 EXECUTION

3.1 SURFACE CONDITIONS

- A. Examine the area and conditions under which work of this Section will be performed. Correct conditions detrimental to the timely and proper completion of the Work. Do not proceed until unsatisfactory conditions are corrected.

3.2 INSTALLATION

- A. Coordinate as required with other trades to assure proper and adequate provision in the work of those trades for interface with the work of this Section.
- B. Install the work of this Section in strict accordance with the original design, the approved Shop Drawings per requirements of government agencies having jurisdiction, and the manufacturer's recommended installation procedures as approve by the Architect, anchoring all components firmly into position for long life under hard use.
- C. Upon completion of the installation, put all items through at least ten operating cycles. Make required adjustments and assure that components are in optimum operating condition.

END OF SECTION

DOOR HARDWARE

PART 1 GENERAL

1.1 SUMMARY

- A. Provide hardware for wood, hollow steel and aluminum doors.
- B. Provide thresholds.
- C. Provide weatherstripping, seals and door gaskets.
- D. Provide silencers where weatherstripping is not used in Hardware Schedule.

1.2 REFERENCES

- A. NFPA 80 - Fire Doors and Windows.
- B. NFPA 101 - Life Safety Code.
- C. NFPA 252 - Fire Tests of Door Assemblies.
- D. UL 10B - Safety Fire Tests of Door Assemblies.

1.3 SUBMITTALS FOR REVIEW

- A. Section 01300 - Submittals: Procedures for submittals.
- B. Shop Drawings:
 - 1. Indicate locations and mounting heights of each type of hardware, schedules and catalog cuts.
 - 2. Submit manufacturer's parts lists and templates.
- C. Samples:
 - 1. Submit 1 sample of hinge, latchset, lockset and closer, illustrating style, color and finish.
 - 2. Samples will be incorporated into the Work.

1.4 SUBMITTALS AT PROJECT CLOSEOUT

- A. Section 01700 - Operation and Maintenance Data.
- B. Section 01300 - Procedures for submittals.
- C. Maintenance Data: Include data on operating hardware, lubrication requirements and inspection procedures related to preventative maintenance.
- D. Keys: Deliver with identifying tags to Owner by security shipment direct from hardware supplier.

1.5 REGULATORY REQUIREMENTS

- A. Products Requiring Electrical Connection: Listed and classified by Underwriters' Laboratories, Inc., as suitable for the purpose specified and indicated.

1.6 DELIVERY, STORAGE AND PROTECTION

- A. Section 01600 - Material and Equipment: Transport, handle, store, and protect products.
- B. Package hardware items individually, label and identify each package with door opening code to match hardware schedule.

1.7 PROJECT CONDITIONS

- A. Coordinate the work with other directly affected sections involving manufacture or fabrication of internal reinforcement for door hardware and recessed items.
- B. Sequence installation to ensure utility connections are achieved in an orderly and expeditious

- manner.
- C. Coordinate Owner's keying requirements during the course of the Work.

1.8 WARRANTY

- A. Provide five-year manufacturer warranty for door closers.

1.9 MAINTENANCE PRODUCTS

- A. Section 01700 - Operation and Maintenance Data.
- B. Provide special wrenches and tools applicable to each different or special hardware component.
- C. Provide maintenance tools and accessories supplied by hardware component manufacturer.

1.10 EXTRA MATERIALS

- A. Section 01700 - Operation and Maintenance Data.

PART 2 PRODUCTS

2.1 KEYING

- A. Door Locks: Keyed in like-groups. Master keyed.
- B. Include construction keying, and control keying with removable core cylinders. Key to the existing keying system where requested.
- C. Supply keys in the following quantities:
 - 1. Two master keys.
 - 2. Four construction keys.
 - 3. Three change keys for each lock.

2.2 KEY CABINET

- A. Cabinet Construction: Sheet steel construction, piano hinged door with lockmaster keyed to building system.
- B. Cabinet Size: Size for project keys plus 10 percent growth.
- C. Hooks for all keys.
- D. Horizontal plastic strips for key hook labeling with clear plastic strip cover over labels.
- E. Finish: Baked enamel, finish, colors as selected.

PART 3 EXECUTION

3.1 EXAMINATION

- A. Verify that doors and frames are ready to receive work and dimensions are as indicated on shop drawings.
- B. Verify that electric power is available to power operated devices and is of the correct characteristics.

3.2 INSTALLATION

- A. Install hardware in accordance with manufacturer's instructions.
- B. Use templates provided by hardware item manufacturer.

3.3 FIELD QUALITY CONTROL

- A. Section 01400 - Quality Control 01650 - Starting of Systems: Field inspection, testing, and

- adjusting.
- B. Architectural Hardware Consultant will inspect installation and certify that hardware and installation has been furnished and installed in accordance with manufacturer's instructions and as specified.

3.4 ADJUSTING

- A. Section: 01650 - Starting of Systems: Adjusting installed work.
- B. Adjust hardware for smooth operation.

3.5 SCHEDULE

- A. Furnish the door the following hardware group.

| | | | |
|----|------------------------------|--------------------------------|---------------|
| 1. | Hardware group 1: | Doors: 1 & 2 | |
| | 1-1/2 Pr. Butts | FBB179-4-1/2 x 4-1/2 US26D NRP | Stanley |
| | 1 Entrance | RE-12-S-626 | Marshall Best |
| | 1 Closer | 8616DS | Dorma |
| | 1 Threshold | 2005A 36" x AL | Pemko |
| | 1 Sweep | 18062 36" x AL | Pemko |
| | 1 Gasket Set | 305CN | Pemko |
| | 1 Kick Down Stop | 1153M | Glynn Johnson |
| | 1 Kick Plate | 8" x DW-2" | Rockwood |
| | 1 Top Filler Plate | | |
| | 1 Closure Door Reinforcement | | |

END OF SECTION

ELECTRIC DOOR OPERATORS

PART 1 GENERAL

1.1 SUMMARY

- A. Provide electric trolley type sectional overhead door operator and electric rolling door operator, where shown on the Drawings, as specified herein and as needed for a complete and proper installation.
- B. Related work:
 - 1. Documents affecting work of this Section include but are not necessarily limited to, General Conditions, Supplementary Conditions and Sections in Division 1 of these Specifications.

1.2 SUBMITTALS

- A. Product data: Within 30 calendar days after the Contractor has received the Owner's Notice to Proceed, submit:
 - 1. Materials list of items proposed to be provided under this Section;
 - 2. Manufacturers' specifications and other data needed to prove compliance with the specified requirements;
 - 3. Shop drawings showing general layout, installation, materials, construction and assembly wiring.
 - 4. Manufacturers' recommended installation procedures which, when approved by the Architect, will become the basis for accepting or rejecting actual installation procedures used on the Work.
- B. Upon completion of this portion of the work and as a condition of its acceptance, deliver to the owner three copies of the operation and maintenance manual.

1.3 QUALITY ASSURANCE

- A. Use adequate numbers of skilled workmen who are thoroughly trained and experienced in the necessary crafts and who are completely familiar with the specified requirements and the methods needed for proper performance of the work of this Section.
- B. Comply with all governmental agencies having jurisdiction in this work.
- C. Each operator shall have a minimum one (1) year manufacturer's warranty.

1.4 DELIVERY, STORAGE, AND HANDLING

- A. Comply with pertinent provisions of Section 01600.

PART 2 PRODUCTS AND MATERIAL

2.1 REQUIRED ATTRIBUTES

- A. Front of Hood Mount Type: (with car wash modification)
 - 1. Motor - 115/230V single phase, 1 hp Model "RHX" with hand chain hoist & 24V three button open-close-stop control, NEMA 4, from Overhead Door Corp. or equal.
 - 2. Reversing Contactor - Heavy Duty, electrically and mechanically interlocked.
 - 3. Provisions for the connection of a 2-wire monitored photo electric eye cell system.

2.2 OTHER MATERIALS

- A. Provide other materials, not specifically described but required for a complete and proper installation, as

selected by the Contractor subject to the approval of the Architect.

- B. Provide a one-button remote for each garage door opener.

PART 3 EXECUTION

3.1 SURFACE CONDITIONS

- A. Examine the areas and conditions under which work of this Section will be performed. Correct conditions detrimental to timely and proper completion of the Work. Do not proceed until unsatisfactory conditions are corrected.

3.2 INSTALLATION

- A. Install the work of this section in strict accordance with the manufacturer's recommendations and shop drawings and in accordance with pertinent requirements of governmental agencies having jurisdiction.
- B. Electrical contractor will run electricity to the electric door operator. Final connection to the door operator shall be the responsibility of the electric door operator installer.

3.3 ADJUSTMENTS AND INSTRUCTIONS

- A. Upon completion of the installation, carefully inspect each component and verify that all items have been installed in the proper location, adequately anchored and adjusted to achieve optimum operation.
- B. Demonstrate to the owner, operation and maintenance procedures.

END OF SECTION

08800

GLAZING

PART 1 GENERAL

1.1 SUMMARY

- A. Provide glass and glazing for hollow metal work, windows, glazed walls and doors.
- B. Provide glass for cabinet doors and view panels.

1.2 REFERENCES

- A. ANSI Z97.1 - Safety Performance Specifications and Methods of Test for Safety Glazing Used in Buildings.
- B. ASTM C669 - Glazing Compounds for Back Bedding and Face Glazing of Metal Sash.
- C. ASTM C804 - Use of Solvent-Release Type Sealants.
- D. ASTM C1036 - Flat Glass.
- E. ASTM C1048 - Heat-Treated Flat Glass - Kind HS, Kind FT Coated and Uncoated Glass.
- F. ASTM C1172 - Laminated Architectural Safety Glass.
- G. ASTM E84 - Surface Burning Characteristics of Building Materials.

1.3 QUALITY ASSURANCE

- A. Installer Qualifications: Company specializing in performing the work of this section with minimum three years experience.

1.4 ENVIRONMENTAL REQUIREMENTS

- A. Section 01600 - Material and Equipment: Environmental conditions affecting products on site.
- B. Do not install glazing when ambient temperature is less than 50 degrees F.
- C. Maintain minimum ambient temperature before, during and 24 hours after installation of glazing compounds.

1.5 WARRANTY

- A. 01700 - Warranties and Bonds.
- B. Provide a five (5) year warranty to include coverage for sealed glass units from seal failure, interpane dusting or misting and replacement of it.
- C. Provide a five (5) year warranty to include coverage for delamination of laminated glass and replacement of it.

PART 2 PRODUCTS

2.1 FLAT GLASS MATERIALS

- A. Float Glass (Type FG-A): Clear.

PART 3 EXECUTION

3.1 EXAMINATION

- A. Verify that openings for glazing are correctly sized and within tolerance.
- B. Verify that surfaces of glazing channels or recesses are clean, free of obstructions that may impede moisture movement; weeps are clear and ready to receive glazing.

3.2 PREPARATION

- A. Clean contact surfaces with solvent and wipe dry.
- B. Seal porous glazing channels or recesses with substrate compatible primer or sealer.
- C. Prime surfaces scheduled to receive sealant.
- D. Perform installation in accordance with ASTM C804 for solvent release sealants.

3.3 INSTALLATION - INTERIOR WET/DRY METHOD (TAPE AND SEALANT)

- A. Cut glazing tape to length and install against permanent stops, projecting 1/16 inch above sight line.
- B. Place setting blocks at 1/4 points with edge block no more than 6 inches from corners.
- C. Rest glazing on setting blocks and push against tape to ensure full contact at perimeter of pane or unit.
- D. Install removable stops, spacer shims inserted between glazing and applied stops at 24 inch intervals, 1/4 inch below sight line.
- E. Trim protruding tape edge.

3.4 CLEANING

- A. Remove glazing materials from finish surfaces.
- B. Remove labels after Work is complete.
- C. Clean glass and adjacent surfaces.

3.5 PROTECTION OF FINISHED WORK

- A. After installation, mark pane with an 'X' by using removable plastic tape or paste. Do not mark heat absorbing or reflective glass units.

END OF SECTION

09900

PAINTING

PART 1 GENERAL

1.1 SUMMARY

- A. Provide surface preparation.
- B. Provide field application of paints, stains, varnishes and other coatings.

1.2 REFERENCES

- A. ASTM D16 - Standard Terminology Relating to Paint, Varnish, Lacquer and Related Products.
- B. ASTM D4442 - Standard Test Methods for Direct Moisture Content Measurement of Wood and Wood-Base Materials.
- C. NACE (National Association of Corrosion Engineers) - Industrial Maintenance Painting.
- D. NPCA - Guide to U.S. Government Paint Specifications; National Paint and Coatings Association.
- E. PDCA - Architectural Specifications Manual; Painting and Decorating Contractors of America.
- F. SSPC - Steel Structures Painting Manual; Steel Structures Painting Council.

1.3 DEFINITIONS

- A. Conform to ASTM D16 for interpretation of terms used in this section.

1.4 SUBMITTALS FOR REVIEW

- A. Section 01300 - Submittals: Procedures for submittals.
- B. Samples:
 - 1. Submit two paper chip samples, 2 x 4 inches in size illustrating range of colors and textures available for each surface finishing product scheduled.

1.5 QUALITY ASSURANCE

- A. Manufacturer Qualifications: Company specializing in manufacturing the Products specified in this section with minimum three years documented experience.
- B. Applicator Qualifications: Company specializing in performing the work of this section with minimum three years experience.

1.6 DELIVERY, STORAGE AND PROTECTION

- A. Section 01600 - Material and Equipment: Transport, handle, store and protect products.
- B. Deliver products to site in sealed and labeled containers; inspect to verify acceptability.
- C. Container Label: Include manufacturer's name, type of paint, brand name, lot number, brand code, coverage, surface preparation, drying time, cleanup requirements, color designation and instructions for mixing and reducing.
- D. Paint Materials: Store at minimum ambient temperature of 45 degrees F and a maximum of 90 degrees F, in ventilated area, and as required by manufacturer's instructions.

1.7 ENVIRONMENTAL REQUIREMENTS

- A. Section 01600 - Material and Equipment: Environmental conditions affecting products on site.
- B. Do not apply materials when surface and ambient temperatures are outside the temperature ranges required by the paint product manufacturer.
- C. Do not apply exterior coatings during rain or snow or when relative humidity is outside the

- humidity ranges required by the paint product manufacturer.
- D. Minimum Application Temperatures for Latex Paints: 45 degrees F for interiors; 50 degrees F for exterior, unless required otherwise by manufacturer's instructions.
- E. Minimum Application Temperature for Varnish Finishes: 65 degrees F for interior or exterior, unless required otherwise by manufacturer's instructions.
- F. Provide lighting level of 80 ft candles measured mid-height at substrate surface.

1.8 PROJECT CONDITIONS

- A. Section 01039 - Coordination and Meetings.
- B. Sequence application to the following:
 - 1. Do not apply finish coats until paintable sealant is applied.
 - 2. Back prime wood trim before installation of trim.

1.9 EXTRA MATERIALS

- A. Section 01700 - Operation and Maintenance Data.
- B. Supply 1 gallons of each color, type and surface texture; store where directed.
- C. Label each container with color, type, texture and room locations in addition to the manufacturer's label.

PART 2 PRODUCTS

2.1 MATERIALS

- A. Coatings: Ready mixed, except field-catalyzed coatings. Prepare pigments:
 - 1. To a soft paste consistency, capable of being readily and uniformly dispersed to a homogeneous coating.
 - 2. For good flow and brushing properties.
 - 3. Capable of drying or curing free of streaks or sags.
- B. Accessory Materials: Linseed oil, shellac, turpentine, paint thinners and other materials not specifically indicated but required to achieve the finishes specified; commercial quality.
- C. Patching Materials: Latex filler.
- D. Fastener Head Cover Materials: Latex filler.

2.2 FINISHES

- A. Refer to finish schedule on drawings for surface finish.

2.3 BRAND OF PAINT

- A. Sherwin-Williams or equal.

PART 3 EXECUTION

3.1 EXAMINATION

- A. Section 01039 - Coordination and Meetings: Verification of existing conditions before starting Work.
- B. Verify that surfaces and substrate conditions are ready to receive Work as instructed by the product manufacturer.
- C. Examine surfaces scheduled to be finished prior to commencement of work. Report any condition that may potentially affect proper application.
- D. Test shop applied primer for compatibility with subsequent cover materials.
- E. Measure moisture content of surfaces using an electronic moisture meter. Do not apply finishes

unless moisture content of surfaces is below the following maximums:

1. Plaster and Gypsum Wallboard: 12 percent.
2. Masonry, Concrete and Concrete Unit Masonry: 12%.
3. Interior Wood: 15 percent, measured in accordance with ASTM D4442.
4. Exterior Wood: 15 percent, measured in accordance with ASTM D4442.
5. Concrete Floors: 8 percent.

3.2 PREPARATION

- A. Surface Appurtenances: Remove or mask electrical plates, hardware, light fixture trim, escutcheons and fittings prior to preparing surfaces or finishing.
- B. Surfaces: Correct defects and clean surfaces that affect work of this section.
- C. Marks: Seal with shellac those that may bleed through surface finishes.
- D. Galvanized Surfaces: Remove surface contamination and oils and wash with solvent. Apply coat of etching primer.
- E. Uncoated Steel and Iron Surfaces: Remove grease, mill scale, weld splatter, dirt and rust. Where heavy coatings of scale are evident, remove by [hand] [power tool] wire brushing or sandblasting; clean by washing with solvent. Apply a treatment of phosphoric acid solution, ensuring weld joints, bolts and nuts are similarly cleaned. Spot prime paint after repairs.
- F. Shop Primed Steel Surfaces: Sand and scrape to remove loose primer and rust. Feather edges to make touch-up patches inconspicuous. Clean surfaces with a solvent. Prime paint bare steel surfaces.
- G. Metal Doors Scheduled for Painting: Prime metal door top and bottom edge surfaces.

3.3 APPLICATION

- A. Apply products in accordance with manufacturer's instructions.
- B. Do not apply finishes to surfaces that are not dry. Allow applied coats to dry before next coat is applied.
- C. Apply each coat to uniform appearance. Apply each coat of paint slightly darker than preceding coat unless otherwise approved.
- D. Sand wood surfaces lightly between coats to achieve required finish.
- E. Vacuum clean surfaces of loose particles. Use tack cloth to remove dust and particles just prior to applying next coat.
- F. Where clear finishes are required, tint fillers to match wood. Work fillers into the grain before set. Wipe excess from surface.
- G. Prime concealed surfaces of interior woodwork with primer paint.
- H. Prime concealed surfaces of interior wood surfaces scheduled to receive stain or varnish finish with gloss varnish reduced 25 percent with thinner.

3.4 CLEANING

- A. Collect waste material that may constitute a fire hazard, place in closed metal containers and remove daily from site.

3.5 SCHEDULE - EXTERIOR SURFACES

- A. Steel - Unprimed:
 1. One coat of alkyd primer.
 2. Two coats of alkyd enamel, gloss.
- B. Steel - Shop Primed:
 1. Touch-up with zinc chromate primer.
 2. Two coats of alkyd enamel, gloss.
- C. Steel - Galvanized:
 1. One coat galvanize primer.
 2. Two coats of alkyd enamel, gloss.

END OF SECTION

15400

PLUMBING SYSTEMS

PART 1 GENERAL

1.1 DISCRIPTION

- A. Provide:
 - 1. Water piping.
 - 2. Sanitary drainage.
 - 3. Condensate piping.
 - 4. Testing.
- B. Comply with other Division 15 Sections, as applicable. Refer to other Divisions for coordination of work.

1.2 SUBMITTALS

- A. Make submittals for all products specified in the specification.

PART 2 PRODUCTS

2.1 MATERIALS

- A. Water Piping Above Grade, Type "L" hard drawn, seamless copper water tube, ASTM B88 and Federal Specification WW-T-799. Joined with wrought copper pressure fittings, ANSI B16.22. Make joints using "lead free" solder and a non-corrosive paste-type flux. Core solder is not allowed. Solder will be solid string or wire type. Where soldered copper piping is connected to threaded brass piping, use a cast brass adaptor.
- B. Water Piping Below Grade, Type "K" hard drawn, seamless copper water tube, ASTM B88 and Federal Specification WW-T-799. Joined with wrought copper pressure fittings, ANSI B16.22. Make joints using "lead free" solder and a non-corrosive paste-type flux. Core solder is not allowed. Solder will be solid string or wire type. Where soldered copper piping is connected to threaded brass piping, use a cast brass adaptor.
- C. Make piping connections to fixtures and equipment with chrome-plated seamless brass tube, ASTM B-125 and Federal Specification WW-T0791. No ferrous piping or materials are allowed in water piping smaller than 4 inches.

2.2 SANITARY DRAINAGE

- A. Sanitary Drainage lines (Soil, Waste and Vent): Cast iron soil pipe and fittings, coating inside and outside, ASTM A74 and Federal Specification WW-P-401. Label with Cast Iron Soil Pipe Institutes' "Mark of Quality and Permanence". Weights of pipe are required by code for location and duty. Joints shall be fabricated by use of "Push-On" type gasketed joints (above or below ground) or "No-Hub" mechanical joints (above ground only). Where permitted by local codes, PVC-DWV Plastic Schedule 40, NSF Seal CS-272 may be used for sanitary drainage pipes (soil, waste, and vent), with solvent-welded joints.

2.3 VALVES

- A. Valves for Domestic Water Piping Systems: Nibco S580 or equal.

2.4 PRESSURE REDUCING VALVE

- A. When the water system static pressure is greater than 75 PSI, furnish and install a pressure-reducing valve ahead of all fixtures and located in an accessible place. Set pressure at 50 PSI downstream of

backflow preventer. Contractor to verify supply pressure.

2.5 COMMERCIAL TYPE WATER HAMMER ARRESTERS

- A. Provide commercial type water hammer arresters on hot and cold water supplies at each; water heater, lavatory, break room sink and service sink(s).
- B. Water hammer arresters shall be equal to PDI-15M2 as furnished by Watts or equal product by Josam or Sioux Chief.
- C. Vertical capped pipe columns will not be permitted.
- D. Water hammer arresters, where concealed, shall be accessible by means of access doors or removable panels. Coordinate with Districts on location(s).

2.6 BACKFLOW PREVENTER

- A. Provide a Watts #909 reduced pressure backflow preventer for the domestic water service.

2.7 PLUMBING FIXTURES

- A. Provide and install fixtures as shown on plans.

PART 3 EXECUTION

3.1 PIPING INSTALLATION

- A. Install piping neatly and parallel with or perpendicular to lines of the structure. Install pipe hangers to maintain accurately aligned piping systems, adequately supported both laterally and vertically. Install horizontal soil, waste, and vent pipe with a grade of 1/4" per foot where possible and not less than 1/8" per foot. Where practicable, connect two or more vents together and extend as one vent through roof. Make vent connections to stacks by appropriate use of 45 wyes, long sweep quarter bends, sixth, eighth or sixteenth bends, except that sanitary tees may be used on the vertical stacks.
- B. Extend condensate drain piping from units with condensate discharge.
- C. Install drains at all low points and vents at high points in water distribution system.

3.2 PIPING

- A. Refer to Section 15700 for insulation requirements.

3.3 PIPE TESTS

- A. Test water piping before installing equipment and before insulation is applied, using specified methods and conditions. Subject piping to test for not less than 24 hours under inspection by the Engineer. Make necessary replacements and repairs and repeat tests until entire system is accepted as satisfactory. Work includes testing equipment. After installation of equipment, operate systems; clean out scale, dirt, oil, waste and foreign matter, and correct additional leaks. Test underground piping prior to backfilling.
- B. Test plumbing drainage systems under 10 foot static head. Test water systems under 150 PSIG hydrostatic pressure.
- C. Flush system thoroughly of dirt and foreign matter, then fill with water treated with 50 ppm of chlorine. During filling process, open valves and faucets several times to assure treatment of entire system. Leave treated water in system for 24 hours after which time system may be flushed; if residual chlorine is not less than 10 ppm, repeat flushing. After sterilization, receive approval by regulatory agency on samples of water in system.

END OF SECTION

15500

HEATING, VENTILATING AND AIR CONDITIONING

PART 1 GENERAL

1.1 SUMMARY

- A. Provide heating, ventilating, and air conditioning systems where shown on the Drawings, as specified herein and as needed for a complete and proper installation including but not necessarily limited to:
 - 1. Heating and Central Air Condenser Unit.
 - 2. Air conditioning supply and return ductwork system with grilles and diffusers.
 - 3. Gas-fired, ceiling-hung Unit Heaters.
 - 4. Temperature control system including low-voltage wiring.
 - 5. Acoustical and thermal insulation of ducts.
 - 6. Engineering and design, refer to drawings.

- B. Related work:
 - 1. Documents affecting work of this Section include, but are not necessarily limited to, General Conditions, Supplementary Conditions and Sections in Division 1 of these Specifications.

1.2 SUBMITTALS

- A. Comply with pertinent provisions of Section 01300.

- B. Product data: Within 30 calendar days after the Contractor has received the Owner's Notice to Proceed, submit:
 - 1. Manufacturers catalogs, samples and other items needed to fully demonstrate the quality of the proposed materials and equipment.

- C. Record drawings:
 - 1. Comply with pertinent provisions of Section 01700.
 - 2. Include a copy of the Record Drawings in each copy of the operation and maintenance manual described below.

- D. Upon completion of this portion of the Work, and as a condition of its acceptance, deliver to the Architect two copies of an operation and maintenance manual compiled in accordance with the provisions of Section 01700 of these Specifications.

1.3 QUALITY ASSURANCE

- A. Use adequate numbers of skilled workmen who are thoroughly trained and experienced in the necessary crafts and who are completely familiar with the specified requirements and the methods needed for proper performance of the work of this Section.

- B. Without additional cost to the Owner, provide such other labor and materials as are required to complete the work of this Section in accordance with the requirements of governmental agencies having jurisdiction, regardless of whether such materials and associated labor are called for elsewhere in these Contract Documents.

- C. Provide minimum 1-year manufacturer's warranty on all units.

1.4 DELIVERY, STORAGE AND HANDLING

- A. Comply with pertinent provisions of Section 01600.

PART 2 PRODUCTS

2.1 DUCTWORK

- A. For exhaust systems and for the heating, ventilating, and air conditioning systems, provide galvanized sheet metal ducts fabricated and installed to pertinent ASHRAE and SMACNA standards or to the requirements of governmental agencies having jurisdiction, whichever requirement is more stringent.
- B. Size the ducts for pressure drop of 0.1" H₂O per 100 feet.
- C. Seal all duct seams, transverse and longitudinal, air tight with 6 oz canvas secured in place with "WC800" or equal duct sealing compound, an approved lagging adhesive or duct tape.

2.2 FLEXIBLE DUCT

- A. Provide factory fabricated insulated low-pressure flexible duct with the following attributes:
 - 1. Zinc-coated spring steel helix, with 1" thick fiberglass insulation, sheathed in a seamless vapor barrier jacket.
 - 2. Interior fire-resistive coated to prevent fiber erosion;
 - 3. Straight run sound absorption of 3 db per ft, and 5 db per ft sound absorption at 45 degree bends;
 - 4. Composite assembly, including insulation and vapor barrier, meeting Class 1 requirements of flame spread of 25 or less and smoke developed of 50 or less as set forth in NFPA Bulletin 90-A and bearing UL label as an air duct.
- B. Provide flexible duct in fully extended condition, free from sags and kinks.
 - 1. Use only the minimum length required to make the connection.
 - 2. Do not exceed 8'-0" in length.
 - 3. Where horizontal support is required, provide at least 3/4" wide banding material hangers at not more than 36" centers.
 - 4. Make joints and connections with 1/2" wide positive locking steel straps.
- C. Acceptable products:
 - 1. Insulated low pressure flexible duct "Type S-181" manufactured by Glass Insulation Co., Los Angeles.
 - 2. For toilet exhaust or return air connectors and runouts, aluminum flexible ducts such as "Flexmaster" or "Van-guard" may be used if acceptable to the governmental agencies having jurisdiction.

2.3 INSULATION

- A. General:
 - 1. Provide materials complying with NFPA Bulletin 90-A, as determined by UL method NFPA 225-ASTM E84, and complying with the governing code, with flame spread rating under 25 and smoke developed rating under 50.
 - 2. Where vapor barriers are used, provide intact and continuous throughout.
 - 3. Acceptable manufacturers:
 - a. Owens/Corning Fiberglass;
 - b. Manville.
 - c. Certainteed.
- B. All supply ducts:
 - 1. Insulate supply ducts with 1-1/2" thick fiberglass blanket such as All-Service Duct Wrap, Type 100 or equal approved in advance by the Architect.
 - 2. Insulate return ducts with 1-1/2" thick fiberglass blanket such as All-Service Duct Wrap, Type 100 or equal approved in advance by the Architect.

2.4 AIR OUTLETS

- A. Ceiling diffusers:
 - 1. Provide Hart & Cooley or Approved Equal, in size, capacity and pattern noted on the Drawings.
 - 2. Provide insulated adaptor boxes above each diffuser neck to permit connection of flexible duct.
- B. Grilles: Provide Hart & Cooley or Approved Equal in size, capacity and pattern noted on drawings.
- C. Provide factory-applied or site-applied black coating on the inside of all air outlets and connecting plenums.
- D. Provide sponge rubber under all flanges.

2.5 VIBRATION ISOLATION AND FLEXIBLE CONNECTIONS

- A. At ducts to equipment, provide vent-fabric flexible connections with a minimum of 6" full length and approved by the governmental agencies having jurisdiction.
- B. Provide additional sound isolation as required to limit the noise level in conditioned space to a maximum of NC-40.

2.6 HEATING AND CENTRAL AIR UNIT

- A. Install High Efficiency, Direct Vent, Condensing Upflow Gas Furnaces with necessary appurtenances, per HVAC Schedule. See Construction Documents, equal to Carrier.
- B. Install High Efficiency Air Conditioners with necessary appurtenances, per Split Systems HVAC Units Schedule sheet 26 of 29, equal to Carrier.
- C. Install Carrier Model TSTATCCPAC01-B 7 day programmable thermostats, or approved equals, per manufacturer's instructions and specifications.
- D. Location of units per drawings.
- E. Vent furnace unit per Manufacturer's instructions and specifications and as per drawings.

2.7 UNIT HEATERS

- A. Unit Heater. Furnish gas fired, propeller fan and unit heaters as manufactured by one of the following companies: Crane, Reznor, National, Pearless, Carrier, Tran Bryant, or equal in the capacity shown on the plans. Units shall be A.G.A. certified, completely assembled and be operationally tested before shipment from factory.
- B. Unit Heater Exchanger. Shall be stainless steel seam or arc welded with tubes and headers not lighter than 20 gauge thickness. Draft diverters shall be aluminized steel or equal. Electrical characteristics as required.
- C. Burners. The burners shall be of cast iron or stainless steel construction that will give quiet, smooth ignition throughout the length of the burner. They shall be equipped with adjustable air shutters to regulate flame characteristics for maximum efficiency. All burners shall be individually removable.
- D. Pilot. Shall be of the intermittent pilot systems type using gas only when the system calls for heat, is lit by high voltage capacitive discharge spark, turns off automatically when demand for heat is satisfied or flame is lost. If flame is lost, unit shuts off main valve, re-starts ignition sequence.
- E. Wiring. Units shall be factory wired for high limit and fan control. Fan motor shall be 115 volt, single phase, 60 cycle totally enclosed with overload protection.
- F. Gas Valve. The gas valve shall be standard type 24-volt single phase, 60 cycle arranged for 100% safety shut off on main and pilot burner. 115/24-volt transformer to be supplied with unit heater and factory wired on low voltage side to gas valve.

2.8 PIPING

- A. For refrigerant piping, provide Type "L" copper, refrigerant grade, with wrought copper fittings, and with joints thoroughly cleaned prior to soldering.

2.9 AUTOMATIC TEMPERATURE CONTROL

- A. Provide a system of temperature control with the attributes listed below.
 - 1. Include thermostats, sensors, temperature controllers, and air piping as requiring for a complete and operable system compatible with approved Heating and Central Air Unit.
 - 2. Provide devices calibrated and adjusted with the actual operating conditions.

2.10 OTHER MATERIALS

- A. Provide other materials, not specifically described but required for a complete and proper installation, as selected by the Contractor subject to the approval of the Architect.

PART 3 EXECUTION

3.1 SURFACE CONDITIONS

- A. Examine the areas and conditions under which work of this Section will be performed. Correct conditions detrimental to timely and proper completion of the Work. Do not proceed until unsatisfactory conditions are corrected.

3.2 COORDINATION

- A. Coordinate as required with other trades to assure proper and adequate provision in the work of those trades for interface with the work of this Section.

3.3 EQUIPMENT INTERFACE

- A. Provide all required shutoff valves, unions and final connections of piping to the work of this Section.
- B. For electrically operated equipment, verify the electrical characteristics actually available for the work of this Section and provide equipment meeting those characteristics.

3.4 PAINTING

- A. Paint inside of all air outlets and connecting plenums with one coat of black paint or provide all such items factory preprinted.

3.5 INSULATION

- A. Wrap insulation firmly around ductwork, covering all surfaces including standing seams and with all joints lapped at least 2".
- B. Securely fasten the insulation in place with 16 gauge soft annealed black or galvanized wire spaced approximately 12" on centers for straight runs and 3" on centers for elbows and fittings.
- C. Take special care to avoid excessive stretching and compressing and to achieve securing at lapped sections where possible.

3.6 INSTRUCTIONS

- A. Upon completion of this portion of the Work, and prior to its acceptance by the Owner, provide a qualified engineer and fully instruct the Owner's maintenance personnel in the proper operation and maintenance of items provided under this Section.
- B. Demonstrate the contents of the approved operation and maintenance manual required under Article 1.2 above.

3.7 TESTING AND ADJUSTING

- A. Test and adjust each piece of equipment and each system as required to assure proper balance and operation.
 - 1. Test and regulate ventilation and air conditioning systems to conform to the air volumes shown on the approved design drawings.
 - 2. Make tests and adjustments in apparatus and ducts for securing the proper volume and face distribution of air for each grille and ceiling outlet.
 - 3. Where required, provide pulleys for fans at no additional cost to the Owner and set to drive the fans at the speed needed to give the indicated volume.
 - 4. For each system, take the following data in tabulated form:
 - a. Air volumes at all supply return and exhaust outlets;
 - b. Total c.f.m. supplied;
 - c. Total c.f.m. returned;
 - d. Total static pressure at each fan and at each system;
 - e. Motor speed, fan speed and input ampere rating for each fan.
- B. Submit two sets of test and balance reports to the Architect for approval.
- C. Eliminate noise and vibration, and assure proper function of all controls, maintenance of temperature and operation in accordance with the approved design.
- D. Secure required approval from governmental agencies having jurisdiction.

END OF SECTION

TESTING AND BALANCING**PART 1 GENERAL**

1.1 SUMMARY

- A. This section specifies the requirements and procedures for total mechanical systems testing, adjusting and balancing. Requirements include measurement and establishment of the fluid quantities of the mechanical system as required to meet design specifications, recording and reporting the results and operation of all systems to demonstrate satisfactory performance to the Owner.
- B. Test, adjust and balance the following mechanical systems:
 - 1. Supply, return and exhaust air systems.
 - 2. Hydronic heating and cooling systems.
 - 3. Verify temperature control system operation.
- C. This Section does not include:
 - 1. Specifications for materials for patching mechanical systems.
 - 2. Specifications for materials and installation of adjusting and balancing devices. If devices must be added to achieve proper adjusting and balancing, refer to the respective system sections for materials and installation requirements.
 - 3. Requirements and procedures for piping and ductwork systems leakage tests.

1.2 DEFINITIONS

- A. Systems testing, adjusting, and balancing is the process of checking and adjusting all the building environmental systems to produce the design objectives. It includes:
 - 1. The balance of air and water distribution.
 - 2. Adjustment of total system to provide design quantities.
 - 3. Electrical measurement.
 - 4. Verification of performance of all equipment and automatic controls.
 - 5. Sound and vibration measurement.
- B. Test: To determine quantitative performance of equipment.
- C. Adjust: To regulate the specified fluid flow rate and air patterns at the terminal equipment (e.g. reduce fan speed, throttling).
- D. Balance: To proportion flows within the distribution system (sub mains, branches and terminals) according to specified design quantities.
- E. Procedure: Standardized approach and execution of sequence of work operations to yield reproducible results.
- F. Report Forms: Test data sheets arranged for collecting test data in logical order for submission and review. These data sheets should also form the permanent record to be used as the basis for required future testing, adjusting and balancing.
- G. Terminal: The point where the controlled fluid enters or leaves the distribution system. There are supply inlets on water terminals, supply outlets on air terminals, return outlets on water terminals, and exhaust or return inlets on air terminal such as registers, grilles, diffusers, louvers and hoods.
- H. Main: Duct or pipe containing the system's major or entire fluid flow.

- I. Submain: Duct or pipe containing part of the system's capacity and serving two or more branch mains.
- J. Branch Main: Duct or pipe serving two or more terminals.
- K. Branch: Duct or pipe serving a single terminal.

1.3 SUBMITTALS

- A. Agency Data:
 - 1. Submit proof that the proposed testing, adjusting, and balancing agency meets the qualifications specified below. The firm or individuals performing the work herein specified may be the installing firm or individuals or may be separate and independent firm or individuals employed by the contractor but in either case the personnel performing the work shall be qualified and certified as specified.
- B. Engineer and Technicians Data:
 - 1. Submit proof that the proposed testing, adjusting, and balancing agency meets the qualifications specified below. The firm or individuals performing the work herein specified may be the installing firm or individuals or may be a separate and independent firm or individuals employed by the Contractor, but in either case the personnel performing the work shall be qualified and certified as specified.
- C. Procedures and Agenda: Submit a synopsis of the testing adjusting and balancing procedures and agenda proposed to be used for this project.
- D. Maintenance Data: Submit maintenance and operating data that includes how to test, adjust and balance the building system. Include this information in maintenance data specified in Division 15 - Basic Mechanical Requirements.
- E. Sample Forms: Submit sample forms, if other than those standard forms prepared by the AABC or NEBB are proposed.
- F. Certified Reports: Submit testing, adjusting, and balancing reports bearing the seal and signature of the Test and Balance Engineer. The reports shall be certified proof that the systems have been tested, adjusted, and balanced in accordance with the referenced standards; are an accurate representation of how the systems have been installed; are a true representation of how the systems are operating at the completion of the testing, adjusting, and balancing procedures; and are an accurate record of all final quantities measured, to establish normal operating values of the systems. Follow the procedures and form as specified below:
- G. Reports: Upon completion of testing, adjusting, and balancing procedures, prepare reports on the approved forms. Reports may be hand written, but must be complete, factual, accurate and legible. Submit 3 complete sets of reports. Only 2 complete sets of draft reports will be returned.
- H. Report Format: Report forms shall be those standard forms prepared by the referenced standard for each respective item and system to be tested, adjusted and balanced. Bind report forms complete with schematic systems diagrams and other data in reinforced, vinyl, three-ring binders. Provide binding edge labels with the project identification and a title descriptive of the contents. Divide the contents of the binder into the below listed divisions, separated by divider tabs.
 - 1. General Information and Summary.
 - 2. Air Systems.
 - 3. Temperature Control Systems.

- I. Report Contents: Provide the following minimum information, forms and data:
1. General Information and Summary: Inside cover sheet to identify testing, adjusting and balancing agency, contractor, Owner, Architect, Engineer and Project. Include addresses, and contact names a telephone numbers. Also include a certification sheet containing the seal and name, address, telephone number and signature of the Certified Test and Balance Engineer. Include in this division a listing of the instrumentation used for the procedures along with the proof of calibration.
 2. The remainder of the report shall contain appropriate forms containing as a minimum, the information indicated on the standard report forms prepared by the AABC and NEBB, for each respective item and system to accompany each respective report form. The report shall contain the following information, and all other data resulting from the testing, adjusting and balancing work:
 3. All nameplate and specification data for all pumps, air handling equipment and motors.
 4. Inlet water and outlet water temperatures of each heating and cooling element.
 5. Water pressure drop through each heating and cooling coil.
 6. Operating suction and discharge pressure and final total discharge head for each pump.
 7. Water flow readings at all pumps and coils.
 8. Actual metered running amperage for each phase of each motor on all pumps and air handling equipment.
 9. Actual metered voltage at each pump and each piece of air handling equipment (phase to phase for all phases).
 10. Static pressure for each piece of air handling equipment and at each location in ductwork system where static pressure controllers are located.
 11. Fan RPM for each piece of air handling equipment.
 12. Total actual DCM being handled by each piece of air handling equipment.
 13. Entering and leaving air temperature of all air handling unit heating coils and cooling coils.
 14. Actual CFM of systems by rooms.

1.4 CERTIFICATION

- A. Agency Qualifications:
1. Employ the services of a certified testing, adjusting and balancing agency meeting the qualifications specified below, to be the single source of responsibility to test, adjust and balance the building mechanical systems, identified above, to produce the design objectives. Services shall include checking installations for conformity to design, measurement and establishment of the fluid quantities of the mechanical systems as required to meet design specifications, recording and reporting the results and operation of all systems to demonstrate satisfactory performance to the Owner.
 2. The testing, adjusting, and balancing agency certified by National Environmental Balancing Bureau (NEBB) or Associated Air Balance Council (AABC) in those testing and balancing disciplines required for this project and having at least one person certified by NEBB or AABC as a Test and Balance Engineer.
- B. Codes and Standards
1. NEBB: "Procedural Standards for Testing, Adjusting, and Balancing of Environmental Systems". Or
 2. AABC: "National Standards for Total System Balance", And
 3. ASHRAE: "ASHRAE Handbook", 1984 Systems Volume, Chapter 37, Testing, Adjusting and Balancing.
- C. Pre-balancing Conference: Prior to beginning of the testing, adjusting, and balancing procedures, schedule and conduct a conference with the Architect/Engineer and representatives of installers of the mechanical system. The objective of the conference is final coordination and verification of system operation and readiness for testing, adjusting and balancing.

1.5 PROJECT CONDITIONS

- A. Systems Operation: System shall be fully operational and clean prior to beginning procedures.

1.6 SEQUENCING AND SCHEDULING

- A. Test, adjust and balance the air systems before Hydronic, steam and refrigerant systems.
- B. Test, adjust, and balance air conditioning systems during summer season and heating systems during winter season, including at least a period of operation at outside conditions within 5 deg. F. Wet bulb temperature of maximum summer design condition and within 10 deg. F. Dry bulb temperature of minimum winter design condition. Take final temperature readings during seasonal operation.

PART 2 PRODUCTS

Not Applicable

PART 3 EXECUTION

3.1 PRELIMINARY PROCEDURE FOR AIR SYSTEM BALANCING

- A. Before operating the system, perform these steps:
 - 1. Walk the system from the system air handling equipment to terminal units to determine variations of installation from design.
 - 2. Check filters for cleanliness and to determine if they are the type specified.
 - 3. Check dampers (both volume and fire) for correct and locked position. Check automatic operating and safety controls and devices to determine that they are properly connected, functioning and at proper operating set point.
 - 4. Check automatic control dampers to determine that they are functioning properly, that they will close tightly and those they will open and close smoothly without binding or backlash.
 - 5. Prepare report test sheets for both fans and outlets. Obtain manufacturer's outlet factors and recommended procedures for testing. Prepare a summation of required outlet volumes to permit a cross check with required fan volumes.
 - 6. Determine best locations in main and branch ductwork for most accurate duct traverses.
 - 7. Place outlet dampers in the full open position.
 - 8. Prepare schematic diagrams of system "as-built" ductwork and piping layouts to facilitate reporting.
 - 9. Lubricate all motors and bearings.
 - 10. Check fan belt tension.
 - 11. Check fan rotation.

3.2 MEASUREMENTS

- A. Provide all required instrumentation to obtain proper measurements, calibrated to the tolerances specified in the referenced standards. Instruments shall be properly maintained and protected against damage.
- B. Provide instruments meeting the specifications of the referenced standards.
- C. Use only those instruments that have the maximum field measuring accuracy and are best suited to the function being measured.
- D. Apply instrument as recommended by the manufacturer.
- E. Use instruments with minimum scale and maximum subdivision and with scale ranges proper for the value being measured.

- F. When averaging values, take a sufficient quantity of readings that will result in a repeatability error of less than 5 percent. When measuring a single point, repeat readings until 2 consecutive identical values are obtained.
- G. Take all readings with the eye at the level of the indicated value to prevent parallax.
- H. Use pulsation dampeners where necessary to eliminate error involved in estimating average of rapidly fluctuating readings.
- I. Take measurements in the system where best suited to the task.

3.3 PERFORMANCE TESTING, ADJUSTING, AND BALANCING

- A. Perform testing and balancing procedures on each system identified, in accordance with the detailed procedures outlined in the referenced standards. Balancing of the air systems and hydronic systems shall be achieved by adjusting the automatic controls, balancing valves, dampers, air terminal devices and the fan/motor drives within each system.
- B. Cut insulation, ductwork and piping for installation of test probes to the minimum extent necessary to allow adequate performance of procedures.
- C. Patch insulation, ductwork and hosing, using materials identical to those removed.
- D. Seal ducts and piping, and test for and repair leaks.
- E. Seal insulation to re-establish integrity of the vapor barrier.
- F. Mark equipment settings, including damper control positions, valve indicators, fan speed control levers and similar controls and devices, to show final settings. Mark with paint or other suitable, permanent identification materials.
- G. Retest, adjust and balance systems subsequent to significant system modifications and resubmit test results.

3.4 RECORD AND REPORT DATA

- A. Record all data obtained during testing, adjusting, and balancing in accordance with, and on the forms recommended by the referenced standards and as approved on the sample report forms.
- B. Prepare report of recommendations for correcting unsatisfactory mechanical performances when system cannot be successfully balanced.

3.5 DEMONSTRATION

- A. Training:
 - 1. Train the Owner's maintenance personnel on trouble shooting procedures and testing, adjusting and balancing procedures. Review with the Owner's personnel, the information contained in the Operating and Maintenance Data specified in Division 15.
 - 2. Schedule training with Owner through Engineer with at least 7 days prior notice.

END OF SECTION

16100

ELECTRICAL WORK

16101 GENERAL

- A. Requirements of the conditions of the contract and Instruction to Bidders, and General Conditions, apply to all work of this Section.
- B. Provide complete electrical service where shown on the drawings, as specified herein, and as needed for a complete and proper installation including, but not necessarily limited to:
 - 1. Panelboards as needed.
 - 2. Branch circuit wiring, in conduit for lighting, receptacles, junction boxes and motors.
 - 3. Hangers, anchors, sleeves, chases, supports, for fixtures and other electrical material and equipment in association therewith.
 - 4. Lighting fixtures and lamps.
 - 5. Wiring system, in conduit, for equipment and control provided under other Sections of these specifications.
 - 6. Other items and services required to complete the system.
- C. Related Work
 - 1. Documents affecting work of this section include, but are not necessarily limited to, General Conditions, Supplementary Conditions and Sections in Division 1 of these specifications.

16102 FIELD CONDITIONS AND MEASUREMENTS

- A. The Electrical Contractor shall visit the site of the work and familiarize himself with all available information concerning the structural, excavations, the location condition bearing on transportation, handling, and storage of materials. The Electrical Contractor shall make his own estimate of the facilities needed, and difficulties of execution of the contract including local conditions, availability of labor, uncertainties of weather, transportation, and other contingencies. Failure of the contractor to acquaint himself with all available information concerning these conditions will not relieve him from responsibility for estimating the difficulties and costs or successfully performing the complete work.

16103 CLEANUP

- A. The Electrical Contractor shall have electrical rubbish and debris removed from the premises as directed. On completion of the electrical contract all associated debris and rubbish shall be removed from the premises.
- B. All electrical equipment and materials furnished by this contractor shall be thoroughly cleaned and ready for use upon completion of the work.

16104 GUARANTEE

- A. Contractor guarantees by his acceptance of the contract, that all work installed shall be free from any defects in workmanship and/or materials and that all apparatus will develop capacities and characteristics specified and that if, during a period of one year or as therefore specified, from completion of work, any such defects in workmanship, materials or performance appear, he will with no cost to owner remedy such defect.

16105 CODES

- A. All electrical work shall be done in strict accordance with the National Electrical Code and all regulations, laws and ordinances which may be applicable.

16106 SUBMITTALS

- A. Product data: Within 35 calendar days after the Contractor has received the Owner's Notice to Proceed, submit:
 - 1. Materials list of items proposed to be provided under this section.
 - 2. Manufacturer's specifications and other data needed to prove compliance with the specified requirements.

3. Manufacturer's recommended installation procedures which, when approved by the owner/architect, will become the basis for accepting or rejecting actual installation procedures used on the work.
- B. Submittals shall include the following:
1. Panelboards.
 2. Lighting fixtures.
 3. Wiring devices.
- C. Samples
1. When so requested by the owner/architect, promptly provide samples of items scheduled to be exposed in the final structure.
 2. When specifically so requested by the Contractor and approved by the Architect, approved samples will be returned to the Contractor for installation on the work.
- D. Manuals: Upon completion of this portion of the work, and as a condition of its acceptance, deliver to the owner/architect two copies of an operation and maintenance manual. Include with each manual.
1. Copy of the approved record documents for this portion of work.
 2. Copies of all circuit directories.
 3. Copies of all warranties and guarantees.

16107 QUALITY ASSURANCE

- A. Use adequate number of skilled workmen who are thoroughly trained and experienced in the crafts and who are completely familiar with the specified requirements and the methods needed for proper performance of the work of this section.
- B. Without additional cost to the owner, provide such other labor and materials as are required to complete the work of this section in accordance with the requirements of governmental agencies having jurisdiction, regardless of whether such materials and associated labor are called for elsewhere in these contract documents.

16108 CONDUIT

- A. All interior wiring above grade shall be installed in electrical metallic tubing with screw coupling fittings.
- B. All interior wiring below slab shall be Galvanized Rigid Steel conduit. Schedule 40 PVC conduits may be used if approved by Owner/Architect. If PVC is used the last two feet to point of emergence shall be Galvanized Rigid Steel conduit with grounding bushing and a grounding conductor sized according to ART. 250-95 of the National Electrical Code shall be installed.
- C. Wiring in office areas shall be concealed, unfinished areas in shop and storage areas shall be surfaced mounted.
- D. All exterior wiring shall be in galvanized Rigid Steel Conduit.
- E. Type MC cable with grounding conductor or type AC cable may be used for maximum 6 foot fixture whips.

16109 WIRE AND CABLE

- A. Building wire and cable with 600 volt insulation shall be 98% conductivity copper unless otherwise noted. The minimum size conductor for lighting and power shall be No. 12 AWG. The minimum size conductor for control shall be No. 14 AWG.
- B. Conductors sized No. 10 and smaller shall be Type "THHN" solid or stranded as required unless otherwise noted, sizes No. 8 and larger shall be type "THHN" stranded unless otherwise noted.

- C. Conductors shall be colored coded as required by governmental agencies having jurisdiction or as required by the National Electrical Code.
- D. Contractor shall provide and install all telephone and data cable and equipment as required by the project and per specifications sections 16930.
- E. Contractor shall provide and install all of the grounding and grounding field as required by this project and per specification section 16931.
- F. Tele/ data cables installed above accessible ceilings may be installed without conduit. Tele/data cables installed above non-accessible ceilings and on surface shall be in conduit. Open cables installed in space used for environmental air shall be rated for plenum use.
- G. Contractor shall install ¾" EMT conduit from data receptacle to 2" above acoustical ceiling tile. Tele/ data cabling by MoDOT.

16110 JUNCTION AND OUTLET BOXES

- A. Outlet Boxes
 - 1. Provide standard one-piece units, galvanized or sherardized steel of shape and size best suited to that particular location, of sufficient size to contain enclosed wires according to ART. 370-16 of the National Electrical Code.
 - 2. Provide outlet boxes 2 1/8" deep for 1" conduits.
 - 3. For lighting outlets, provide standard 4" octagon or square units with 3/8" fixture stud and box hanger where required.
 - 4. For switches and receptacles, provide standard boxes with plaster or dry wall ring with stainless steel cover plate for concealed devices and pressed steel boxed with galvanized or cadmium plated steel cover plates for exposed devices.
- B. Junction or Pull Boxes
 - 1. Interior junction boxes shall be galvanized code-gauge sheet steel units with screw-on covers, of size and shape required to accommodate wires without crowding, and to suit the location.
 - 2. Exterior boxes shall meet NEMA 3R or 4 standards.

16111 LIGHTING FIXTURES

- A. Install lighting fixtures, complete with lamps, as shown on drawings and schedules. Manufacturers shown on schedules are for quality and type only, manufacturers of equal quality will be accepted if approved by owner.
 - 1. Recessed fixtures:
 - a. Provide unit having an attached pull box and with UL label.
 - b. Provide local label in addition if so required by governmental agencies having jurisdiction..
 - 2. Fluorescent fixtures
 - a. Provide ballasts thermally protected against overheating by built-in thermal protectors sensitive to ballast winding temperature and current.
 - b. Provide protector preventing winding temperature from exceeding 120 degrees C, allowing winding temperatures to reach 105 degrees C under normal operating conditions at 40 degrees C ambient and, after opening, not reclosing above 80 degrees C.
 - c. Exterior ballast shall be cold weather type.
 - d. Where fixture substitutes are proposed, submit a sample fixture with materials list required to be submitted under Art. 16106 above.
 - e. Light fixtures in work areas shall be located so as not to interfere with the operation of overhead doors.

16112 WIRING DEVICES

- A. Toggle switches - Mount 48" above finished floor.
 - 1. Single pole Leviton 5521-I.
 - 2. 3-way Leviton 5523-I.

- B. Receptacles - Mount 18" above Finished Floor in office area 48" above Finished Floor in garage and storage areas and above splashboard over counters.
 - 1. Duplex receptacles Leviton 5800-I.
 - 2. Weatherproof duplex receptacles Leviton 6599-I mounted in FS box and 6196-VFS cover.
 - 3. Ground Fault Interrupter duplex receptacles Leviton 6599-I.
 - 4. Isolated ground receptacles Leviton 5262-IG.
- C. Telephone and Computer Outlets shall be 4" x 4" x 1 1/2" outlet box with plaster ring. Install 3/4" EMT from box to just above accessible ceiling as required.
- D. Outlets in finished walls shall be 4" x 4" x 1 1/2" outlet box with plaster ring and a cover plate.
- E. Outlets on surface shall be 4" x 4" x 1 1/2" outlet box and 4" x 4" raised cover plate.
- F. Devices of the following manufacturers will be accepted as equal.
 - 1. Hubbel
 - 2. Arrow-Hart
 - 3. General Electric

16113 PANELBOARDS

- A. Panelboards shall be Sq. 'D' Type with circuit breakers as shown on drawings and schedules, and shall be Service Entrance Rated.
- B. Devices of the following manufactures will be accepted as equal.
 - 1. General Electric
 - 2. Cuttler-Hammer

16114 TRANSFORMERS

- A. Service Entrance Transformer is not part of this contract.

16115 DISCONNECT SWITCHES

- A. Disconnect switches shall be Sq. 'D' Class 3130 General Duty fusible or non-fusible as shown on drawings. Interior switches shall be NEMA 1 and Exterior switches shall be NEMA 3R.

16116 GROUNDING

- A. Install a 5/8" x 10' copperclad ground rod at service entrance with a #6 bare copper conductor between ground rod and grounding bus in Panel board.
- B. All grounding shall comply with ART. 250 of the National Electrical Code.

16117 OTHER MATERIALS

- A. Provide other materials, not specifically described but required for a complete and proper installation as approved by the Architect.

16118 EXECUTION

- A. Surface Conditions
 - 1. Examine the areas and conditions under which work of this section will be performed. Correct conditions detrimental to timely and proper completion of the work. Do not proceed until unsatisfactory conditions are corrected.

16119 PREPARATION

- A. Coordinate
 - 1. Coordinate as necessary with other trades to assure proper and adequate provision in the work of those trades for interface with the work of this section.
 - 2. Coordinate the installation of electrical items with the schedule for work of other trades to prevent unnecessary delays in the total work.

- B. Data indicated on the drawings and in these specifications are as exact as could be secured but there absolute accuracy is not warranted. The exact locations, distances, levels and other conditions will be governed by actual construction and the drawings and specifications should be used only for guidance in such regard.
- C. Verify all measurements at the building. No extra compensation will be allowed because of differences between work shown on the drawings and actual measurements at the site of construction.
- D. Branch circuit wiring and arrangement of home runs have been designed for maximum economy consistent with adequate sizing for voltage drops and other considerations. Install the wiring and circuits arranged exactly as shown on the Drawings, except as otherwise approved in advance by the architect.
- E. The electrical drawings are diagrammatic, but are required to be followed as closely as actual construction and work of other trades will permit. Where deviations are required to conform actual construction and the work of other trades, make such deviations without additional cost to the owner.

16120 TRENCHING AND BACKFILLING

- A. Perform trenching and backfilling associated with the work of this section in strict accordance with the provisions of the appropriate sections of these specifications.

16122 INSTALLATION OF CONDUCTORS

- A. Unless otherwise shown use #12 type THHN conductors for all branch circuits protected by 20 amp circuit breakers. Where so indicated on the drawings, use larger wires to limit voltage drops.
- B. Use identified (white) neutrals and color-coded phase wires for all branch circuit wiring.
 - 1. Make splices electrically and mechanically with pressure-type connectors.
 - a. For wire size #6 AWG and smaller, provide "Scotch-Lock" connectors.
 - 2. Insulate splices with a minimum of two half-lapped layers of Scotch Brand #33 vinyl-plastic electrical tape where insulation is required.
- C. Tape all joints with rubber tape 1 1/2 times the thickness of the conductor insulation, than cover with vinyl-plastic electrical tape specified above.
- D. The drawings do not indicate the home runs. Continue all home runs to the panel as though the routes were shown completely.

16123 INSTALLATION OF PANELS

- A. Install panels as shown on drawings and specifications or as directed by the owner/architect.
- B. Mount a typewritten directory behind glass or plastic on the inside of each panel door and, on the directory, show the number and complete description of all outlets on each circuit.

16124 TESTING AND INSPECTION

- A. Make required tests in the presence of the owners representative and required approvals from the owner/architect and governmental agencies having jurisdiction.
- B. Make written notice to the owner/architect adequately in advance of each of the following stages of construction.
 - 1. In the underground condition prior to placing concrete floor slab, when all associated electrical is in place.
 - 2. When all rough in is complete, but not covered.
 - 3. At completion of the work of this section.
- C. When material and/or workmanship is found to not comply with the specified requirements, within three days after receipt of notice of such non-compliance remove the non-complying items from the

job site and replace them with items complying with the specified requirements, all at no additional cost to the owner.

- D. In the owner/architect's presence:
 - 1. Test all parts of the electrical systems for phase to phase and phase to ground short circuits and prove that all such items provided under this section function electrically in the required manner.
 - 2. Immediately submit to the architect a report of maximum and minimum voltages and a copy of the recording voltmeter chart.
 - 3. Also measure voltages between phase wires and neutral and report these voltages to the Architect.

16125 PROJECT COMPLETION

- A. Upon completion of the work of this section, thoroughly clean all exposed portions of the electrical installation, removing all traces of soil, labels, grease, oil, and other foreign material and using only the type cleaner recommended by the manufacturer of the item being cleaned.
- B. Thoroughly indoctrinate the owner's operation and maintenance personnel in the contents of the operations and maintenance manual required to be submitted under article 16106 of this section of these specifications.

END OF SECTION