

Missouri  
Department  
of Transportation



Daniel Niec, District Engineer

North Central District  
902 North Missouri St.  
P.O. Box 8  
Macon, MO 63552  
(660) 385-8249  
Fax (660) 385-1707  
Toll free 1-888 ASK MoDOT  
<http://www.modot.mo.gov>

# QUOTATION TABULATION

General Services  
(Procurement) Division

Thank you for your response to our Request for Quotation # D210-065-R2. For your information, the following is a tabulation of all responses which were received. This quotation was awarded to: **Skyline Materials**. If you have any questions, please contact me at the address/phone number shown above. Buyer: William D. "Bill" Noyes, CPPO, CPPB, Senior Procurement Agent

Qty	U/M	Description	Skyline Materials	Boone Construction (MBE Vendor)	Leo O'Laughlin	APAC Missouri	Bobby Hoelscher Trucking
365	Ton	Type 2 Rock Blanket *	14.25 5201.25	14.85 5420.25	15.40 5621.00	20.00 7300.00	21.10 7701.50
60	Ton	3" to 10" Rip-Rap *	14.45 867.00	14.85 891.00	14.95 897.00	18.50 1110.00	19.60 1176.00
<b>TOTAL ORDER EXTENSION:</b>			<b>\$6,068.25</b>	\$6,311.25	\$6,518.00	\$8,410.00	\$8,877.50

**\* 365 tons to be delivered to southeast side of the Richland Creek Bridge.**

**TYPE 2 ROCK BLANKET: Section 611.30.2** – The material for rock blanket shall be durable stone or broken concrete containing a combined total of no more than 10 percent of soil, sand, shale or non-durable rock. The material shall contain a large percentage of pieces as large as the thickness of the blanket will permit, with enough smaller pieces of various sizes to fill the larger voids. For Type 2 Rock Blanket, at least 60 percent of the mass shall be of pieces having a volume of one cubic foot or more. Acceptance of quality and size of material will be made by visual inspection at the job site.

**\* 60 tons to be delivered to the Richland Creek Bridge (40 tons to northeast corner & 20 tons to southwest corner).**

**3" to 10" RIP- RAP: Section 609.60.2.2** – Type 2 Rock Ditch Liner shall consist of material with a predominant rock size of 6 inches (150 mm), a maximum rock size of 10 inches (250 mm) and a gradation such that no more than 15 percent will be less than 3 inches (75 mm). The material for rock ditch liner shall consist of a predominantly one-sized, durable stone, shot rock or broken concrete. Acceptance by the engineer may be made by visual inspection.

"No Quote" responses were received from Hinnen Hauling & Construction, Mid-Missouri Limestone, and Norris Aggregate Products.

Notification of the online posting of this RFQ opportunity was also sent to Central/Knox County Stone, Hall Hauling, Hermann Sand & Gravel, Joerling Bros. Trucking, Lomax Trucking Service, M&M Trucking, Marcum Hauling, Mutter Farms, Phil Wilson, Ren Potterfield Trucking, and Wilkerson Brothers Quarry, but no responses were received from these vendors.