


Contract Limits and Location Sketch



Contract Term and Extension

Initial Contract Term: Commencing [April 1, 2011](#) and shall terminate [November 30, 2011](#)
First Extended Term: Commencing [April 1, 2012](#) and shall terminate [November 30, 2012](#)
Second Extended Term: Commencing [April 1, 2013](#) and shall terminate [November 30, 2013](#)

Contract Limits and Exclusions

The following areas shall be included in the contract limits:

Route 40 Project Limits

Begin Point: I-70 Ramps west of Callahan Road

End Point: Missouri River

Note: Includes interchanges and outer roads as described in the details below.

Location Specific Details:

1) Along Eastbound and Westbound Lanes of Route 40:

- **MM 0.4 to MM 12.0** A thirty (30) foot wide strip along the edge of outside shoulders.
- **MM 1.6 to MM 8.6** Entire median of Route 40 from west of Lake St. Louis Blvd. to west of Route K.

2) At the Following Interchanges:

- **Exit 1C. Prospect Road.** The entire area between the ramps and Route 40. A 30 foot strip along the outside of the ramps. Includes areas around the north and south roundabouts.
- **Exit 2. Lake St. Louis Blvd.** A 30-foot wide strip along the ramps and along the shoulders of Lake St. Louis Blvd.
- **Exit 4. Route N.** A 30-foot wide strip along both shoulders of all the ramps. A 30 foot wide strip along both shoulders of Route N from the South Service Road to Henke Road.
- **Exit 6. Route DD / Winghaven Blvd.** No work – maintained by others.
- **Exit 9. Route K.** A 30-foot wide strip along the ramps and along the shoulders of Route K from the South Outer Road to just north of westbound ramps.
- **Exit 10. Route 94.** A 30-foot wide strip along shoulders of all ramps and along Route 94 from the South Outer Road to Weldon Springs Road.
- **Exit 11. Research Park Circle.** A 30-foot wide strip along shoulders of all ramps. Includes areas around the roundabout.
-

3) Along the North Outer Road:

- **West of Callahan Road.** A 15-foot wide strip along both shoulders to end State Maintenance.
- **Callahan to Prospect Road.** A 15-foot wide strip along both shoulders.

- **Prospect to Lake St. Louis Blvd** A 15-foot wide strip along both shoulders. State Maintenance ends west of Lake St. Louis Blvd. at curve to Civic Center Drive.
- **Route N / Henke Road to west of Route DD / Winghaven Blvd.** A 15-foot wide strip along both shoulders. Work ends at curve west of Winghaven Blvd. - maintained by others.
- **Route DD / Winghaven to Route K.** A 15-foot wide strip along both shoulders. Work ends west of Route K – maintained by others.
- **Route K to Route 94.**
- **Route 94 to Research Park Circle.** A 15-foot wide strip along both shoulders.
- **East of Research Park Circle.** A 15-foot wide strip along both shoulders. Maintenance ends at curve to Wolfrum Road.

4) Along the South Outer Road:

- **West of Callahan.** A 15-foot wide strip along both shoulders to end State Maintenance near I-70. State maintenance begins just east of Callahan at curve to Duello Road.
- **Prospect east to Hickory Glen.** A 15-foot wide strip along both shoulders. Maintenance ends at curve to Hickory Glen Court.
- **East of Route N.** A 15-foot wide strip along both shoulders.
- **East of Hawk Ridge Trail (Old Route N).** A 15-foot wide strip along both shoulders.
- **East of Route K to Route 94.** A 30-foot wide strip along both shoulders. Part of segment has concrete barrier with no shoulder.
- **East of Route 94.** A 15-foot wide strip along both shoulders. Includes areas around the commuter parking lot, all grassy areas within the commuter parking lot, all areas between the commuter parking lot and the outer road, and all areas between the commuter parking lot and the eastbound on-ramp from Route 94 to Route 40. Maintenance ends at Weldon Springs Heights Drive.

Exclusions: The following are known areas that shall be excluded from the contract limits unless otherwise directed by the engineer:

<u>ROUTE</u>	<u>DIRECTION</u>	<u>CROSS STREET</u>	<u>DESCRIPTION</u>	<u>ACREAGE</u>
Rte 40	EB	Weldon Spring Heights Dr	Area maintained by Research Park	1.0
Rte 40	EB	Research Park Overpass	Area maintained by Research Park	2.0
Rte 40 North Outer Road	WB	Siedentop Rd to Meadows Pkwy.	Areas maintained by St John's & CitiMortgage	2.0
Rte 40 North Outer Road	WB	West of Rte K	Areas maintained by others	2.0
Rte 40 South Outer Road	-	East of Hawk Ridge Trail	Areas maintained by others	2.0
Rte 40	EB & WB	Rte DD / Winghaven Interchange	Begin ramps west of interchange to end ramps east of interchange - area maintained by others	10.0

TOTAL EXCLUSIONS (APPROXIMATE):

19 ACRES

Mowing Cycles, Litter Removal Cycles, and Preliminary Schedule**April 1 through June 30: 2 mowing cycles****July 1 through November 30: 2 mowing cycles****TOTAL MOWING & LITTER REMOVAL CYCLES: 4****Mowing Quantities**

The quantities shown are the total estimated acres to be mowed during one contract term if all areas are mowed and all mowing cycles are authorized. The total area included in the contract limits has been reduced for excluded areas and/or areas mowed and maintained by others.

The quantities are calculated as follows:

TOTAL AREA PER MOWING CYCLE (APPROXIMATE): 185 ACRES

Total Area in Contract Limits (Acres)	X	Number of Mowing Cycles During Contract Term	=	Total Mowing Quantity During Contract Term (Acres)
185	X	4	=	740

TOTAL CONTRACT QUANTITY – MOWING: 740 ACRES

Litter Removal Quantities

In accordance with the contract specifications the litter removal area is presumed to be equal to the mowing area.

Total Area in Contract Limits (Acres)	X	Number of Litter Removal Cycles During Contract Term	=	Total Litter Removal Quantity During Contract Term (Acres)
185	X	4	=	740

TOTAL CONTRACT QUANTITY – LITTER REMOVAL: 740 ACRES

Contract Time for Completion of Work


The contractor shall complete all work required through the entire contract limits within the working days specified below after the notice to proceed date.

Mowing Cycle with Litter Removal Cycle: 9 Working Days

Mowing Height & Special Equipment

- 1) Mowing equipment shall have a minimum adjustable height of 3 to 8 inches.
- 2) No special equipment or equipment restrictions are required for this contract.
- 3) All grass and vegetation shall be cut and trimmed to a height of five (5) inches unless otherwise directed by the engineer.

Special Sign Detail



W021-3-8 48" x 48"
In accordance with
Sec 616

COLOR

Legend & Border – Black
Background – Orange

SHEETING

MoDOT Florescent Orange