


### Contract Limits and Location Sketch



### **Contract Term and Extension**

Initial Contract Term: Commencing [April 1, 2011](#) and shall terminate [November 30, 2011](#)  
First Extended Term: Commencing [April 1, 2012](#) and shall terminate [November 30, 2012](#)  
Second Extended Term: Commencing [April 1, 2013](#) and shall terminate [November 30, 2013](#)

### **Contract Limits and Exclusions**

**The following areas shall be included in the contract limits:**

#### **I-170**

Begin Point: Galleria Parkway underpass (1/4 mile north of I-64)

End Point: Nyflot Road underpass (1/4 mile south of I-270)

#### **I-170 / I-70 Interchange**

Begin Point: McDonnell Blvd. overpass (west of I-170)

End Point: Springdale Avenue underpass (east of I-170)

#### **Notes:**

1) Includes all areas between and adjacent to ramps at interchanges.

#### **I-64 to Route D (Page Ave) Location Specific Details:**

I-170 MM: 0.0-0.6

Full Mow Out: 3.16 Acres

Acres Per Edge Cut: 3.16

I-170 MM: 0.6-1.0

Full Mow Out: 1.42 Acres

Acres Per Edge Cut: 1.42

I-170MM: 1.0-1.08

Full Mow Out: 7.85 Acres

Acres Per Edge Cut: 3.6 Acres

I-170 MM: 1.8-2.2

Full Mow Out: 8.89 Acres

Acres Per Edge Cut: 3.94 Acres

I-170 MM: 2.2-2.8

Full Mow Out: 1.83 Acres

Acres Per Edge Cut: 1.83 Acres

I-170 MM: 2.8-3.2

Full Mow Out: .000 Acres

Acres Per Edge Cut: 0.00 Acres

I-170 MM: 3.2-3.8  
Full Mow Out: 20.84 Acres  
Acres Per Edge Cut: 7.92 Acres

I-170 MM: 3.8-4.2  
Full Mow Out: 9.27 Acres  
Acres Per Edge Cut: 1.39 Acres

I-170 MM 4.0 Page Interchange  
Full Mow Out: 6.28 Acres  
Acres Per Edge Cut: 4.63 Acres

**Route D (Page Ave) to I-270 Location Specific Details:**

15ft cut on all of the mainline 3 times per year one before Memorial Day, one before July 4th, and one before Labor Day. One 30ft cut or final mow will be done before Nov.15th. Trim around all guardrail, guard cable, and signs every cycle. More details about ramps below.

Exit 4 Page 15ft both sides of off and on ramps for 15ft cycles, 30ft right side of off and on ramps and entire area between left side of ramp and interstate for 30ft cycle

Exit 5 St. Charles Rock Rd. 15ft both sides of off and on ramps for 15ft cycles, 30ft right side of off and on ramps and entire area between left side of ramp and interstate for 30ft cycle

Mow entire median from 270 to mile marker 8.3 this includes the area around exit 9C Boeing all other medians between Natural Bridge and St. Charles Rock Rd. only get a 15ft cut for the 15ft cycles and a full mow when we are doing the 30ft cut.

Exit 6 Natural Bridge 15ft both sides of off and on ramps for 15ft cycles, 30ft right side of off and on ramps and entire area between left side of ramp and interstate for 30ft cycle

Exit 7C ramp to Airport 15ft on both sides of ramp for 15ft cycles except where elevated, 30ft on both sides of ramps for 30ft cycle except where elevated

Exit 7B ramps to 70 west 15ft on both sides of ramp for 15ft cycles except where elevated, 30ft on both sides of ramps for 30ft cycle except where elevated

Exit 7A ramps to 70 east 15ft on both sides of ramp for 15ft cycles except where elevated, 30ft on both sides of ramps for 30ft cycle except where elevated

Exit 8 Scudder 15ft both sides of off and on ramps for 15ft cycles, 30ft right side of off and on ramps and entire area between left side of ramp and interstate for 30ft cycle

Exit 9 C Hanley 15ft both sides of off and on ramps for 15ft cycles, 30ft right side of off and on ramps and entire area between left side of ramp and interstate for 30ft cycle

Exit 9 B Boeing details in median section

Exit 9 A Airport Rd. 15ft both sides of off and on ramps for 15ft cycles, 30ft right side of off and on ramps and entire area between left side of ramp and interstate for 30ft cycle

**Exclusions:** The following are known areas that shall be excluded from the contract limits unless otherwise directed by the engineer:

| <u>ROUTE</u> | <u>DIRECTION</u> | <u>CROSS STREET</u>   | <u>DESCRIPTION</u>                                   | <u>ACREAGE</u> |
|--------------|------------------|-----------------------|--|----------------|
| I-170        |                  | St. Charles Rock Road | Mow only around 2 berms in the median                | 2.0            |
| I-170        | NB               | St. Charles Rock Road | From mile marker 6 to 6-1/3 by Unisource and Greybar | 5.0            |
| I-170        |                  | Varies                | Miscellaneous areas moved by others                  | 5.0            |

**TOTAL EXCLUSIONS (APPROXIMATE):**

**12 ACRES**

### **Mowing Cycles, Litter Removal Cycles, and Preliminary Schedule**

**April 1 through June 30: 2 mowing cycles**

**July 1 through November 30: 2 mowing cycles**

**TOTAL MOWING & LITTER REMOVAL CYCLES:**

**4**

**Mowing Quantities**

The quantities shown are the total estimated acres to be mowed during one contract term if all areas are mowed and all mowing cycles are authorized. The total area included in the contract limits has been reduced for excluded areas and/or areas mowed and maintained by others.

The quantities are calculated as follows:

**TOTAL AREA PER 15' MOWING CYCLE (APPROXIMATE): 120 ACRES**  
**TOTAL AREA PER 30' MOWING CYCLE (APPROXIMATE): 225 ACRES**

| Total Area in<br>Contract Limits<br>(Acres) | X | Number of Mowing<br>Cycles During Contract<br>Term | = | Total Mowing Quantity<br>During Contract Term<br>(Acres) |
|---|---|--|---|--|
| 120   | X | 3  | = | 360  |
| 225   | X | 1  | = | 225  |
| <b>TOTAL CONTRACT QUANTITY – MOWING:</b>    |   |  |   | <b>585 ACRES</b>   |

**Litter Removal Quantities**

In accordance with the contract specifications the litter removal area is presumed to be equal to the mowing area.

| Total Area in<br>Contract Limits<br>(Acres)      | X | Number of Litter Removal<br>Cycles During Contract<br>Term | = | Total Litter Removal Quantity<br>During Contract Term<br>(Acres) |
|--|---|--|---|--|
| 120  | X | 3  | = | 360  |
| 225  | X | 1  | = | 225  |
| <b>TOTAL CONTRACT QUANTITY – LITTER REMOVAL:</b> |   |  |   | <b>585 ACRES</b>   |

### **Contract Time for Completion of Work**

The contractor shall complete all work required through the entire contract limits within the working days specified below after the notice to proceed date.

#### **Mowing Cycle with Litter Removal Cycle:**


**120 Acre Cycle: 8 Working Days**

**225 Acre Cycle: 13 Working Days**

### **Mowing Height & Special Equipment**

- 1) Mowing equipment shall have a minimum adjustable height of 3 to 8 inches.
- 2) No special equipment or equipment restrictions are required for this contract.
- 3) All grass and vegetation shall be cut and trimmed to a height of five (5) inches unless otherwise directed by the engineer.

Special Sign Detail



W021-3-8 48" x 48"  
In accordance with  
Sec 616

COLOR

Legend & Border – Black  
Background – Orange

SHEETING

MoDOT Florescent Orange