

Miscellaneous Contract Requirements and Specifications

A. Work Location

I-55, Northbound Onramp
Jefferson County
At Richardson Road
From Near Mile Marker 190.6 to 190.2
Work Location is shown in Exhibit A

B. Summary of Work Required

Furnish and install traffic control as shown in Exhibit A.
Layout guard cable and anchors as shown in Exhibit A and Exhibit D.
Locate utilities to determine any conflicts.
Furnish and install guard cable.
Final cleanup of work site.

C. Tabulation of Quantities

1 Lump Sum	Traffic control as shown in Exhibit A - Plans
1390 Linear Feet	3-Strand Roadside Guard Cable with 16 Foot Post Spacing
2 Each	Guard Cable Anchor Assembly
No direct payment for Mobilization	

D. 3-Strand Guard Cable – Non-Proprietary Low Tension System

Guard cable used for this contract shall be a non-proprietary low tension guard cable system in accordance with applicable portions of Section 606 of the Missouri Standard Specifications for Highway Construction. All materials shall be in accordance with Section 1040 of the Standard Specs. Standard Specifications are shown in Exhibit C of the bid documents. All work shall be in accordance with Exhibit A – Plans and Exhibit D – Standard Plans. All three cables shall be installed on the roadway side of posts.

E. Traffic Control

All traffic control shall be provided by the contractor as shown in Exhibit A - Traffic Control Plans. Standard MUTCD compliant signs, channelizers, flashing arrow panels, etc shall be used. All work shall be in accordance with Section 616 of the Standard Specs. Payment includes moving traffic control devices as required for daily work activities.

F. Working Hours

Monday through Friday days allowed, 8:00 AM to 2:30 PM.
Weekend and holiday work hours require prior approval by the engineer and may not be allowed.

All equipment and materials shall be removed, pavement cleaned, all traffic control devices removed or set aside, and all lanes open by 2:30 PM. NO EXCEPTIONS ALLOWED.