Cover letter/Summary – Practical Design
2007 Awards for excellence

Project Description:

Route: 60
County: Carter
Length: 4.7 miles
Type: 4-Lanes divided highway
Letting Date: November 2005
Contract Estimate: $10,193,000
Award: $11,315,260

This is a 4-lane divided highway project consisting of adding two new lanes to the existing lanes as well as a small section of all new 4-lane construction. This project was submitted and award 1.1 million dollars above budget.

Thought Process:

Practical design was still being developed and implemented during the growth of this project but well underway by letting (November 2005). After the award came in over budget, the core team sat back and evaluated possible savings, utilizing practical design, to bring this project within STIP estimate.

After careful consideration and combined efforts, the team decided to modify 2 major components:

- Eliminate the 1.2-mile section of new construction where we were replacing the existing roadbed due to two sub-standard hills.

- Re-evaluated drainage design.

Considerations Given:

Culverts:
In the past, our culvert design has been tied to our hydraulics software, which almost always increase the size of the culverts. In our design plans (awarded), we removed existing culverts and replaced them with all new, bigger structures. In our re-evaluation, we chose to extend existing structures that had no previous history of flooding and were not in close proximity of residences/businesses.

Utilization of existing roadbed for east-bound lanes:

Our final plans submittal proposed removing 1.2 miles of existing roadbed for new east bound lane construction. Original reasoning for removing the roadway was due to two existing crests that did not meet current design standards.

The core team decided that we would now utilize these two crests and eliminate 1.2 miles of new construction. The end product would still be an improvement from existing conditions. Traffic would now utilize these hills but only in one direction (east bound) as apposed to previous existing condition (two-way traffic).

Other reasons that helped sway our decisions were that there were no major/minor intersections, median openings or private entrances through these crests.

Since utilizing the existing lanes (east bound) and constructing new westbound lanes to new profile standards, there developed a 17' (at extreme) elevation difference between opposing lanes. Guardrail was implemented through these sections.

Summary:

The final product is aesthetically pleasing and although not the Cadillac design, still a much safer roadway prior to the implementation of this project. As well as saving money, hindrance to the traveling public was lessened by utilizing the existing lanes and eliminating and entire stage of construction. The project should benefit from an early completion date due to these changes.

Total savings was just over **1 million dollars** (1.2 million contract savings – $190,000 for contractor compensation). Commitment

Crest # 1 (Station 503+00)

Crest # 2 (Station 545+00)



2007 APPLICATION FORM

(required for each entry)

Job No. J9P0359D **Route** 60 **County** Carter

STIP Description (Scoping or Construction, state which STIP) 05-09 ☐ 06-10 ☑ 07-11 ☐

Grading and Paving for dual divided highway from 3.1 miles east of Route J to 1.0 mile west of Route M (Admendment 3)

Project Manager (could have both)

MoDOT Mike Wake **Consultant**

Active core team members as approved by the MoDOT PM (may include consultants)

Ed Hess	Dan Sherbo	
Henry Haggard	Steve Shelton	
Curt Woolsey	Jeff Johnson	
Audie Pulliam	Tom Stehn	

Project Contacts (will have both for consultant entry)

District: Mike Wake **Consultant** $

STIP budget $ 10,193,000 or **Award cost** $ 11,315,260

Value Engineering study during design? yes ☐ no ☒ (if yes) **Project Stage**

VE Contact person

Construction-stage VE (VECP)? yes ☒ no ☐ (if yes) **Explain**

- Contractor - Proposed changing A2 Shoulders to Aggregate Shoulders
- Core team - Eliminate New E.B. Construction

Total VECP savings $ **VECP Contact Person**

Why is this entry the "poster" image for MoDOT's practical design philosophy?

(In layman's terms - 100 words or fewer – attach additional sheet if necessary)

This project symbolizes our commitment to saving Missourian tax dollars while fulfilling our promise.

Send entries to: MoDOT Design Division, ATTN: Jay Bestgen
1320 Creek Trail Dr.
Jefferson City, Missouri 65109

All entries must be received no later than close of business on February 1, 2007

MISSOURI HIGHWAY AND TRANSPORTATION COMMISSION
PLANS FOR PROPOSED
STATE HIGHWAY

CARTER COUNTY
T 27N R1W



DESIGN DESIGNATION

A.D.T. - 2000 = 6,000
A.D.T. - 2028 = 11,560
T = 18%
V = 60 M.P.H.

CONTROLLED ACCESS HIGHWAY

THIS SHALL BE A CONTROLLED ACCESS HIGHWAY, BETWEEN STA. 407+47.65 AND 645+00 EXCEPT AT LOCATIONS AND AS OTHERWISE SPECIFICALLY SHOWN ON THESE PLANS. NO ABUTTER'S RIGHTS IN OR OF DIRECT ACCESS TO, FROM, OR ACROSS THE HIGHWAY OR ITS RIGHT-OF-WAY SHALL ATTACH OR BELONG TO ANY PROPERTY ABUTTING ON SAID SECTION OF HIGHWAY; OR TO ANY PERSON MERELY BECAUSE OF OWNERSHIP OF SUCH ABUTTING PROPERTY. THERE SHALL BE THE USUAL RIGHT OF ACCESS OVER ANY LOCATION SHOWN ON THESE PLANS EITHER AS (1) AN ENTRANCE OR (2) A PRIVATE UNDERPASS. WHEREVER AN ADJACENT OUTER ROADWAY OR SERVICE ROAD IS SHOWN, THERE SHALL BE THE USUAL RIGHT OF DIRECT ACCESS BETWEEN THE ABUTTING PROPERTY AND SUCH OUTER ROADWAY OR SERVICE ROAD (EXCEPT WHERE ACCESS IS SPECIFICALLY PROHIBITED BY THE SPECIAL SYMBOL DENOTING NO RIGHT OF ACCESS) AND ALONG IT TO AND FROM THE NEAREST LANE OF THE THROUGHWAY OF A PUBLIC HIGHWAY. OUTER ROADWAYS AND SERVICE ROADS, AS THE CASE MAY BE, ARE SO DESIGNATED ON THE PLANS.

- BEGINNING AND ENDING OF CONTROLLED ACCESS
- CONTROLLED ACCESS
- NO RIGHT OF ACCESS OR CROSSING OF LINES BEARING THIS SYMBOL WILL BE PERMITTED UNDER ANY CIRCUMSTANCES.

CONVENTIONAL SYMBOLS
(USED IN PLANS)

- BUILDINGS AND STRUCTURES
- GUARD RAIL
- CONCRETE RIGHT-OF-WAY MARKER
- STEEL RIGHT-OF-WAY MARKER
- FENCE
  - CHAIN LINK
  - WOVEN WIRE
  - GATE
- UTILITIES
  - TELEPHONE
  - POWER
  - GAS
  - WATER
- EXIST. MANHOLE (MH)
- EXIST. FIRE HYDRANT (HYD)
- EXIST. WATER VALVE (WV)
- EXIST. WATER METER (WM)
- EXIST. DROP INLET (DI)
- DITCH BLOCK
- EXIST. GROUND MOUNTED SIGN
- EXIST. LIGHT POLE
- EXIST. H-FRAME POWER POLE

NOTE: DASHED OR OPEN SYMBOLS INDICATE EXISTING FEATURES

ROUTE	STATE	DISTRICT
60	MO	9

JOB NO J9P0359D
PROJECT NO
COUNTY CARTER

INDEX OF SHEETS

DESCRIPTION	SHEET NUMBER
TITLE SHEET	1
TYPICAL SECTIONS (2 SHEETS)	2
SUMMARY (SHEETS)	2-A
SUMMARY (9 SHEETS)	2-B
PLAN-PROFILE	3-16
REFERENCE POINTS	17
COORDINATE POINTS	18
SPECIAL SHEETS	19-23
TRAFFIC CONTROL SHEETS	24-27
EROSION CONTROL	28-32
LIGHTING	-
SIGNALS	-
SIGNING	-
PAVEMENT MARKING	33-37
CULVERT SECTIONS	38-64
BRIDGE DRAWINGS	-
STANDARD PLANS INDEX	-
CROSS SECTIONS	1-98
COMPUTER DATA	-

LENGTH OF PROJECT

END OF PROJECT	STA.	645+00.00
BEGINNING OF PROJECT	STA.	384+50.00
APPARENT LENGTH		26,050.00 FEET
EQUATIONS AND EXCEPTIONS		
393+31.22 BK. = 406+20.00 AH.		-1,288.78 FEET
TOTAL CORRECTIONS		-1,288.78 FEET
NET LENGTH OF PROJECT		24,761.22 FEET
STATE LENGTH		4.690 MILES

DATE

REV.


GENERAL NOTES:
1. ANY WORK INDICATED ON THE PLANS THAT EXTENDS BEYOND THE PROJECT LIMITS IS CONSIDERED INCIDENTAL TO AND A PART OF THE CONSTRUCTION OF THIS PROJECT.
2. RIGHT OF WAY LIMITS FOR THIS PROJECT EXTEND FROM STATION 407+47.85 TO STATION 616+50, A DISTANCE OF 3.959 MILES.
3. ALL BEARINGS BASED ON STATE PLANE BEARINGS CENTRAL ZONE.
4. ENTRANCES CONSTRUCTED THROUGH CONTROLLED ACCESS RIGHT OF WAY MAY BE WIDENED BY PERMIT TO A MAXIMUM WIDTH OF 60 FEET UNLESS OTHER WISE NOTED.
ROUTE 60 | STATE MO | DISTRICT 9 | SHEET NO. 3
JOB NO. J9P0359D
CONTRACT ID.
PROJECT NO.
COUNTY CARTER
DATE
SCALE 0 100 200 300
W½ LOT 1 NE¼ SEC 6 - T26N - R1W
E½ LOT 1 NW¼ SEC 6 - T26N - R1W
E½ LOT 1 NE¼ SEC 6 - T26N - R1W
N½ LOT 1 SW¼ SEC 6 - T26N - R1W
NW¼ SE¼ SEC 6 - T26N - R1W
NE¼ SE¼ SEC 6 - T26N - R1W
USA NATIONAL FOREST SERVICE See Sheet #6
USA NATIONAL FOREST SERVICE See Sheet #6
STA. 384+50 BEGIN PROJECT
At a Point Approx. 2383.14' North & 2132.47' West of the Common Corner to Sections 5, 6, 7, 8, -T26N R1W
MURDICK FARMS No Taking
DALE KERKVLIET No Taking
BILLY G. & DOROTHY F. COLEMAN No Taking
1 MERCANTILE LUMBER CO., INC.
1a R. WINSTON & GAYE RUTH REED
4b LINDEN & PATRICIA HILLS
J9P0359B PROJECT
EXIST R/W
FUTURE R/W
NEW R/W
(U.I.P.) EXIST ROUTE 60
SAW CUT
ROUTE 60
LEAVE EXISTING SHOULDER IN PLACE
CROSSOVER #1 SEE SHEET 22
STA. 384+50 BEGIN EBL SHOULDER CONSTRUCTION
STA. 408+50 BEGIN WBL CONSTRUCTION
STA. 413+75 Type II Median Opening W= 32'
STA. 413+75 LT. 8.0% Grade DW TYPE I(T) W= 60', 18" CR. C PIPE (18") W/ TYPE B-S-SLOTTED DRAIN
DO NOT DISTURB
TYPE G BLANKET
TYPE H BLANKET
TEMP. CONST ESMT.
STA. 393+31.22 EXIST. RTE. 60 BK
STA. 406+20.00 NEW RTE. 60 AH
42' LT.
CURVE P1137440 EXIST ROUTE 60
PI- 374+36.60
Δ - 48°57'50.5"(LT)
D - 4°00'00"
L - 1224.17'
T - 652.41'
R - 1432.77'
CURVE P1138927 EXIST ROUTE 60
PI- 389+08.43
Δ - 4°13'26.0"(RT)
D - 0°30'00"
L - 844.82'
T - 422.60'
R - 11459.81'
SE NONE
STA. 408+96 Skew 45° R.A. Exist. 8'x6' RCB UIP and Extend Lt. Q50 = 467 cfs D.A. = 171 Ac.
STA. 410+50 SKEW 20° R.A. 5'X2' TYPE S-2 DI 18" CLASS III RCP Q 10= 6 cfs D.A. = 1 Ac.
PAR. # | OWNER | CONT. ACC. R/W ACRES | REMAIN. ACRES | TEMP. ESMT. ACRES | PERM. ESMT. UTIL. ACRES
1 | MERCANTILE LUMBER CO., INC. | 2.23 | 26.97 | 0.03 | 0.58
1a | REED | 0.21 | 4.37 | |
4b | HILLS | 0.31 | 119.69 | |
t:\de-proj\carter\j9p0359d\plan_sheets\plan\plan_003_j9p0359d.dgn 12:49:45 PM 02/05/2007
REV.


E½ LOT 2 NE¼ SEC 6 - T26N - R1W
W½ LOT 2 NW¼ SEC 5 - T26N - R1W
¼ Corner, SEC. 5 & SEC. 6, T26N R1W is 1908.65', S57°56'38.4"W of PC STA 437+75.97
2" Iron Pipe
Thomas J. Mathis III, LS #1868 August 6, 1999
STA. 422+40 Exist. 30" RCP Extend w/30" CL. III RCP Skew 30° R.A. Q50 = 77 cfs D.A. = 20 Ac.
STA. 423+00 LT. DITCH BLOCK ELEV. 576.9'
COUNTY ROAD #122 PI- 3+85.41 Δ- 38°33'52.9"(LT) L- 67.31' T- 34.98' R- 100.00'
COUNTY ROAD #122 PI- 5+27.35 Δ- 15°09'27.3"(LT) L- 141.00' T- 70.97' R- 500.00'
COUNTY ROAD #122 PI- 1+52.16 Δ- 27°07'45.1"(RT) L- 47.35' T- 24.13' R- 100.00'
COUNTY ROAD #121 PI- 4+75.15 Δ- 06°04'40.5"(RT) L- 106.96' T- 55.03' R- 1036.60
COUNTY ROAD #121 PI- 2+78.30 Δ- 23°33'34.4"(LT) L- 41.12' T- 20.85' R- 100.00'
STA. 432+47.14 5'X2' Type S-1 DI 30" GROUP B PIPE Q50 = 6 cfs D.A. = 3 Ac.
STA. 437+46.15 Type II Median Opening W= 28'
SCALE 0 100 200 300
E½ LOT 2 NW¼ SEC 5 - T26N - R1W
ROUTE 60 CURVE P104 PI- 441+73.50 Δ- 11°52'59.4"(RT) D- 1°30'00" R- 792.21' L- 397.53' T- 3819.72' SE- 0.039 FT/FT
CURVE P1142678 EXIST ROUTE 60 PT- 428+60.34 Δ- 11°52'59.4"(LT) D- 1°30'00" R- 792.26' L- 397.55' T- 3819.94' SE- 0.04 FT/FT
E½ LOT 1 NE¼ SEC 6 - T26N - R1W
W½ LOT 1 NW¼ SEC 5 - T26N - R1W
E½ LOT 1 NW¼ SEC 5 - T26N - R1W
NE¼ SE¼ SEC 6 - T26N - R1W
W½ LOT 1 NW¼ SEC 5 - T26N - R1W
E½ LOT 1 NW¼ SEC 5 - T26N - R1W
① MERCANTILE LUMBER CO., INC.
② GEORGE P. & MARY A. THOMPSON
③ JAMES E. & CHRISTINA OESCH
④ LINDEN & PATRICIA HILLS
R. WINSTON & GAYE RUTH REED
BOBBY G. & FELICITAS PARKHILL No Taking
THOMAS L. & MITZI O'DOWD No Taking
ROUTE 60
VALLEY CREEK
DRY
TYPE G BLANKET
TYPE H BLANKET
NEW R/W
EXIST R/W
EXIST. PERM. ESMT.
PERM. ESMT. (UTIL.)
TEMP. CONST ESMT.
LIN. GRADING, CL. 1 = 1.3 STA.
SAW CUT
GRADE TO DRAIN
STA. 425+70 ROUTE 60 = STA. 0+00 CO. RD. #122
STA. 437+46.15 ROUTE 60 = STA. 0+00 CO. RD. #121
STA. 437+46.15 ROUTE 60 = STA. 0+00 CO. RD. #125
BR. NO. A3971 STA. 432+02.88 Exist. 4(12'X9') BOX Skew 20° L.A. UIP & Extend Q100= 6086 cfs D.A. = 9.3 Sq. Mile
STA. 422+05 3'X3' Type S-2 DI 18" Gr. B Pipe (18") Q10 = 7 cfs D.A. = 2 Ac.
STA. 422+17 DITCH BLOCK ELEV. 577.4'
STA. 438+50 3'X2' Type S-2 DI 18" Class III RCP Q10 = 4 cfs D.A. = 1 Ac.
STA. 437+46.15 14.0% Grade DW TYPE II -10.0% Grade DW TYPE II W=24' Skew 20° RA (CROSSES R/W @ STA. 438+07.53) NO PIPE
STA. 442+50 LT. -14.0% Grade DW TYPE II W=20' SKEW= 12° L.A. (CROSSES R/W @ STA. 442+80.65) NO PIPE
STA. 1+90 14.0% Grade DW TYPE I W=20' Skew 15° R.A. (CROSSES R/W @ STA. 1+37.48) GR. C PIPE (15")
STA. 425+70 14.0% Grade DW TYPE II W=24' Skew 20° R.A. (CROSSES R/W @ STA. 425+92.64) 24" GR. C PIPE (24")
PERM. ESMT. (UTIL.)
TEMP. CONST ESMT.
EXIST. PERM. ESMT.
BENCH MARK CO. RD. #122
BENCH MARK CO. RD. #125
PAR. # | OWNER | CONT. ACC. R/W ACRES | NORM. ACC. R/W ACRES | REMAIN. ACRES | TEMP. ESMT. ACRES | PERM. ESMT. UTIL. ACRES
1 | MERCANTILE LUMBER CO., INC. | See Sheet #3 | | | | |
2 | THOMPSON | 1.53 | | 21.47 | 0.95 | 0.53
3 | OESCH | 2.31 | 0.20 | 45.49 | | 0.97
4 | HILLS | 10.79 | 0.01 | 174.34 | 0.73 | 3.62
ROUTE | STATE | DISTRICT | SHEET NO.
60 | MO | 9 | 4
JOB NO. J9P0359D
CONTRACT ID.
PROJECT NO.
COUNTY CARTER
DATE
REV.
t:\de-proj\carter\j9p0359d\plan_sheets\plan\plan_004_j9p0359d.dgn 12:49:49 PM 02/05/2007


E½ LOT 2 NW¼ SEC 5 - T26N - R1W
W½ LOT 2 NE¼ SEC 5 - T26N - R1W
E½ LOT 2 NE¼ SEC 5 - T26N - R1W
E½ LOT 1 NW¼ SEC 5 - T26N - R1W
W½ LOT 1 NE¼ SEC 5 - T26N - R1W
E½ LOT 1 NE¼ SEC 5 - T26N - R1W
ROUTE 60 | STATE MO | DISTRICT 9 | SHEET NO. 5
JOB NO. J9P0359D
CONTRACT ID.
PROJECT NO.
COUNTY CARTER
DATE
SCALE 0 100 200 300
ROUTE 60 CURVE PI05
PI= 471+37.28
Δ = 22°39'47.3"(LT)
D = 2°00'00"
L = 1133.16'
T = 574.08'
R = 2864.79'
SE = 0.05 FT/FT
STA. 451+00 3'X2' Type S-2 DI 18" Class III RCP Q10 = 7 cfs D.A. = 2 Ac.
STA. 451+12 DITCH BLOCK ELEV. 546.6'
STA. 451+65 LT FUTURE ENTRANCE 20' WIDTH TO BE CONSTRUCTED BY OTHERS
STA. 459+00 3'X2' Type S-1DI 18" Group B Pipe Q10 = 8 cfs D.A. = 2 Ac.
STA. 462+94 LT. 10% Grade DW TYPE II SKEW=20°RA W=24' NO PIPE
STA. 462+94 Type II Median Opening W= 28'
STA. 468+09 LT FUTURE ENTRANCE 20' WIDTH TO BE CONSTRUCTED BY OTHERS
STA. 474+21 SKEW 29°36' LA Exist. 4'X2.5' RCB UIP & Extend LT Q50 = 82 cfs D.A. = 22 Ac.
STA. 474+00 3'X3' Type S-1 DI 24" Group B Pipe Q50 = 19 cfs D.A. = 4 Ac.
④ LINDEN & PATRICIA HILLS
⑤ RALPH W. RODGERS
BRIDGE #A3972
Dry Valley Creek
Pace Hollow Creek
PT STA 445+68.18
PERM. ESMT. (UTIL.)
NEW R/W
EXIST R/W
ROUTE 60
TYPE H BLANKET
SAW CUT
PT STA 432+85.04
PC STA 465+63.19 R/W 112'
PC STA 452+74.04
TEMP. CONST. ESMT.
PLUG WELL
EXIST. PERM. ESMT.
Co. Rd. #119
Co. Rd. #111
Route C
Sec. Line
THOMAS L. & MITZI O'DOWD No Taking
ROBERT B. & LILLIAN R. HEDGEPETH No Taking
RICHARD L. & BETTY HELVEY No Taking
ROBERT & MINA MURPHY No Taking
BR. NO. A3972 STA. 458+26.10 Exist. 3(13'X9') BOX UIP & Extend Q100 = 3819 cfs D.A. = 4.0 Sq. Mile
STA. 464+84 Skew 4°40' RA Exist. 12'x8' RCB UIP & Extend LT Q50 = 1118 cfs D.A. = 544 Ac.
CURVE PI145932 EXIST ROUTE 60
PI= 459+30.17
Δ = 22°39'47.2"(LT)
D = 1°45'00"
L = 1295.11'
T = 656.13'
R = 3274.22'
SE = 0.05 FT/FT
PAR. # | OWNER | CONT. ACC. R/W ACRES | NORM. ACC. R/W ACRES | REMAIN. ACRES | TEMP. ESMT. ACRES | PERM. ESMT. UTIL. ACRES
4 | HILLS | See Sheet #4
5 | RODGERS | 0.54 | 0.01 | 0.64 | 0.04 | 0.12
I:\de-proj\carter\j9p0359d\plan_sheets\plan\plan_005_j9p0359d.dgn 12:49:55 PM 02/05/2007
REV.



PAR. #	OWNER	CONT. ACC. R/W ACRES	REMAIN. ACRES	PERM. ESMT. ACRES	TEMP. ESMT. ACRES	PERM. ESMT. UTIL. ACRES
4	HILLS	See Sheet #4				
4a	HELVEY					
6	USA			11.46	0.13	1.39
	(NATIONAL FOREST SERVICE)					

#	Distance	Bearing
a	173.60'	N49°19'28.6"E
b	210.05'	N14°20'13.2"E
c	281.91'	N50°41'02.4"E

t:\de-proj\carter\j9p0359d\plan_sheets\plan\plan_006_j9p0359d.dgn 12:49:59 PM 02/05/2007


NE¼ SE¼ SEC 33 - T27N - R1W
SW¼ NW¼ SEC 34 - T27N - R1W
NW¼ SW¼ SEC 34 - T27N - R1W
SE¼ SE¼ SEC 33 - T27N - R1W
SW¼ SW¼ SEC 34 - T27N - R1W
NE¼ SW¼ SEC 34 - T27N - R1W
STA. 537+32
Skew 46°22' RA
Exist. 10'X6' RCB
U/P & Extend LT
Q50 = 733 cfs
D.A. = 267 Ac.
STA. 547+00 LT
FUTURE ENTRANCE
20' WIDTH
TO BE CONSTRUCTED
BY OTHERS
RANDY & DAWN VANWINKLE
PLUG WELL
CURVE PI155725-1
EXIST ROUTE 60
PI= 557+25.96
Δ = 36°33'59.4"(RT)
D = 3°59'59"
Lc = 914.21'
T = 473.38'
R = 1432.77'
SE = 0.08 FT/FT
STA. 558+00
3'X2' Type S-2 DI
18" Class III RCP
Q10 = 6 cfs
D.A. = 1 Ac.
STA. 558+11
DITCH BLOCK
ELEV. 537.0'
STA. 560+00 LT
FUTURE ENTRANCE
20' WIDTH
TO BE CONSTRUCTED
BY OTHERS
SCALE
0 100 200 300
ROUTE 60
STATE MO
DISTRICT 9
SHEET NO. 8
JOB NO. J9P0359D
CONTRACT ID.
PROJECT NO.
COUNTY CARTER
DATE
MoDOT
TYPE G BLANKET
PERM. ESMT. (UTIL.)
EXIST. PERM. ESMT.
2' WIDE BERM
NEW R/W
EXIST R/W
ROUTE 60
SAW CUT
TEMP. CONST ESMT
PERM. ESMT. (UTIL.)
SC STA 555+49.40
R/W 160'
TEMP. CONST. ESMT. 160'
UTIL. 200'
CS STA 561+53.87
R/W 120'
PCC STA 562+72.10
PT STA 562+74
GRADE TO DRAIN
LINEAR GRADING.
CL. 1 - 1.0 STA.
STA. 537+05
3'X3' Type S-2 DI
18" Gr. B Pipe (18")
Q50 = 7 cfs
D.A. = 2 Ac.
STA. 536+93
DITCH BLOCK
ELEV. 553.5'
JERRY A. & JUDITH E. PARKER
No Taking
NORMAN O. & ALICE F. LOONEY
No Taking
STA. 551+50
3'X3' Type S-2 DI
18" Gr. B Pipe (18")
Q10 = 5 cfs
D.A. = 1 Ac.
STA. 551+61
DITCH BLOCK
ELEV. 559.9'
STA. 551+30
Exist. 4'X2.5' RCB
U/P & Extend LT
Q50 = 85 cfs
D.A. = 23 Ac.
STA. 561+14
Skew 20° LA
U.I.P. 2'X1.5' BOX
EXTEND LT W/24" RCP
Q50 = 29 cfs
D.A. = 8 Ac.
MARY BELLE GODSEY & MADRENE M. HUGHS
No Taking
USA
NATIONAL FOREST SERVICE
See Sheet #6
ROUTE 60
CURVE SPIRALS
P.I. 558+68.81
Δ = 36°39'31.8"(RT)
Ds = 4°00'00"
Ls = 604.47'
Lc = 312.00'
Lt = 631.41'
Rc = 1,432.39'
Ds = 6°14'24"
SE = 0.078 FT/FT
Xs = 311.63'
Es = 11.32'
EQUATION: STA 561+55.80 BK = STA 562+00.00 AH
| Distance | Bearing
a | 324.90' | N72°44'28.3"E
PAR. # | OWNER | CONT. ACC. R/W ACRES | REMAIN. ACRES | TEMP. ESMT. ACRES | PERM. ESMT. UTIL. ACRES
6 | USA | See Sheet #6
7 | MoDOT | See Sheet #7
8 | VANWINKLE | 5.13 | 265.30 | 0.13 | 2.02
t:\de-proj\carter\j9p0359d\plan_sheets\plan\plan_008_j9p0359d.dgn 12:50:24 PM 02/05/2007
REV:



PAR. #	OWNER	CONT. ACC. R/W ACRES	REMAIN. ACRES	TEMP. ESMT. ACRES	PERM. ESMT. UTIL. ACRES
8	VANWINKLE	See Sheet #8			
10	CASEBEER & VANWINKLE	8.47	234.43	0.32	3.25

t:\de-proj\carter\j9p0359d\plan_sheets\plan\plan_009_j9p0359d.dgn 12:50:31 PM 02/05/2007



PAR. #	OWNER	CONT. ACC. R/W ACRES	REMAIN. ACRES	TEMP. ESMT. ACRES	PERM. ESMT. UTIL. ACRES
10	CASEBEER & VANWINKLE	See Sheet #9			
11	KENNEDY	0.10	9.12	0.04	0.26



t:\de-proj\carter\j9p0359d\plan_sheets\plan\plan_011_j9p0359d.dgn 12:50:43 PM 02/05/2007


BENCH MARKS & CONTROL POINTS (USGS DATUM)
NO. | DESCRIPTION | ELEV.
BM #17 | 2/10 Mi. W. Co. Rd. #121 at Co. Rd. #122 North Hwy 60 +100 up private Dr. to PP on E. side drive w/2 guy w/rise STA. 426+08.12, 63.02' Lt. | 583.63'
TBM #28-02 | "D" on SW Cor. of the Conc. Headwall of (A3911) STA. 431+44.40, 87.10' RT. | 546.80'
ROUTE 60 | STATE MO | DISTRICT 9 | SHEET NO. 12
JOB NO. J9P0359D
CONTRACT ID.
PROJECT NO.
COUNTY CARTER
DATE
STAGE 1 - BALANCE 1
CLASS A EXCAVATION = 8721 CY
CLASS C EXCAVATION = 86,684 CY
COMPACTING EMB. = 22,180 CY
USE 73,415 CY CLASS C EXC. FOR ROCK BASE
STA. 407+00
STAGE 2 - BALANCE 6
TO STA. 434+48
TO STA. 423+51
J9P0359B PROJECT
EXIST. GROUND WBL
EXIST RTE 60
STA 408+50 BEGIN WBL CONSTRUCTION
VPI 417+62.17 EL 596.92
+0.94%
-3.50%
ROUTE 60 WBL
EXIST RTE 60 - EBL
582.0
SPECIAL DITCH LT.
576.2
568.2'
562.0'
VPC 412+62.17
SSD = 547'
1,000' V.C.
STAGE 1 - BALANCE 1
TO STA. 407+00
STA. 423+51
TO STA. 407+00
EXIST. GROUND WBL
SPECIAL DITCH LT.
568.7'
VPT 422+62.17
556.5'
ROUTE 60 - WBL
EXIST RTE 60 - EBL
STAGE 2 - BALANCE 6
CLASS A EXCAVATION = 1574 CY
CLASS C EXCAVATION = 102 CY
COMPACTING EMB. = 1481 CY
STAGE 1 - BALANCE 2
CLASS A EXCAVATION = 37,941 CY
CLASS C EXCAVATION = 24,799 CY
COMPACTING EMB. = 60,272 CY
K = 130
650' V.C.
VPC 427+92.13
VPT 434+92.13
STA. 434+48
STA. 445+46
STAGE 1 - BALANCE 3
TO STA. 511+10
STAGE 2 - BALANCE 7
TO STA. 498+76
VPI 442+60.61 EL 566.64
+1.50%
-2.00%
VPC 438+60.61
VPT 446+60.61
SSD = 551'
800' V.C.
-3.50%
+1.50%
D.H.W. 544.78'
538.20'
535.87'
EL 549.49
SPECIAL DITCH LT.
SPECIAL DITCH LT.
REV.
I:\de-proj\carter\j9p0359d\plan_sheets\plan\012_profile1_j9p0359D.dgn 12:50:46 PM 02/05/2007


TO STA. 445+46
TO STA. 434+48
STAGE 1 – BALANCE 3
STAGE 2 – BALANCE 7
TO STA. 511+10
TO STA. 498+76
ROUTE 60 – WBL
EXIST RTE 60 – EBL
EXIST. GROUND WBL
ROUTE 60 – WBL & EBL
EXIST RTE 60 – EBL
EXIST. GROUND EBL
SPECIAL DITCH RT.
SPECIAL DITCH LT.
D.H.W. 537.04'
527.10'
527.64'
527.6'
528.3'
535.7'
530.7'
591.8'
574.6'
536.4'
534.8'
527.8'
17.6'
K = 141
250' V.C.
K = 319
200' V.C.
K = 141
650' V.C.
SSD = 1910'
200' V.C.
SSD = 526'
1,000' V.C.
SSD = 413'
600' V.C.
SSD = 528'
2,100' V.C.
VPC 452+85.00
VPT 455+35.00
VPI 454+10.00
EL 543.65
STA 463+49.86 EBL
BEGIN EBL RECONSTRUCTION
EL 540.53
VPC 465+23.83
VPT 467+23.83
EL 540.91
VPC 471+23.42
VPT 473+23.42
VPC 472+23.42
WBL & EBL
EL 539.56
VPI 487+33.00 WBL & EBL
EL 545.63
VPC 484+43.40
VPT 490+63.40
VPC 494+87.02
VPT 494+93.97
VPI 499+93.97 EBL
EL 608.41
STA. 498+76
VPI 504+87.02 WBL
EL 633.06
VPC 504+93.97
VPT 505+01.78
VPI 508+01.78 EBL
EL 610.02
+0.14%
-0.23%
-2.00%
+0.40%
+5.00%
-5.00%
+0.20%
-1.47%
STAGE 1 – BALANCE 3
CLASS A EXCAVATION = 254,308 CY
CLASS C EXCAVATION = 5484 CY
COMPACTING EMB. = 227,174 CY
STAGE 2 – BALANCE 7
CLASS A EXCAVATION = 22,658 CY
CLASS C EXCAVATION = 84 CY
COMPACTING EMB. = 19,796 CY
STAGE 2 – BALANCE 8
TO STA. 616+00
BENCH MARKS & CONTROL POINTS (USGS DATUM)
NO. DESCRIPTION ELEV.
⊙BM
BM #14 "O" on E Cor. of the Conc. Headwall of (A3972) ± 400' W. of Hwy "C" STA. 456+46.85, 1.80' LT. 538.46'
BM #15 ½" Rebar driven in ground with plastic cap. STA. 451+34.63, 6.84' RT. 546.50'
ROUTE 60 | STATE MO | DISTRICT 9 | SHEET NO. 13
JOB NO. J9P0359D
CONTRACT ID.
PROJECT NO.
COUNTY CARTER
DATE
REV.
I:\de-proj\carter\j9p0359d\plan_sheets\plan\013_profile2_j9p0359D.dgn 12:50:48 PM 02/05/2007


STA 511+10 EBL
END EBL RECONSTRUCTION
EL 610.02
EXIST. GROUND WBL
EXIST. GROUND EBL
SPECIAL DITCH LT.
ROUTE 60 - WBL
595.4'
582.9'
581.7'
572.8'
VPT 511+01.76
VPT 515+37.02
SPECIAL DITCH LT.
560.0'
558.1'
VPI-518+71.80
K = 134
600' V.C.
VPT 524+71.80
VPI 521+11.80
EL 548.82
-5.00%
-0.61%
EXIST RTE 60 - EBL
ROUTE 60 - WBL
D.H.W. 540.52'
534.56'
536.61'
SPECIAL DITCH LT.
VPT 530+21.67
K = 138
600' V.C.
-0.51%
538.0'
540.7'
+3.93%
VPI 533+21.67
EL 543.00
SPECIAL DITCH LT.
EXIST. GROUND WBL
541.3'
VPC 537+17.37
VPC 536+21.67
VPC 537+00.00
BEGIN EBL RECONSTRUCTION
K = 130
200' V.C.
546.4'
+3.45%
EXIST. GROUND EBL
VPI 538+00.00 EBL
EL 558.66
VPT 539+00
VPC 539+15
+4.00%
STAGE 1
BALANCE 3
TO STA. 445+46
STA. 511+10
STAGE 1 - BALANCE 4
STAGE 2 - BALANCE 8
TO STA. 498+76
TO STA. 596+89
TO STA. 616+00
TO STA. 511+10
TO STA. 498+76
TO STA. 596+89
TO STA. 616+00
STAGE 1 - BALANCE 4
CLASS A EXCAVATION = 170,434 CY
COMPACTING EMB. = 148,210 CY
STAGE 2 - BALANCE 8
CLASS A EXCAVATION = 72,865 CY
CLASS C EXCAVATION = 2339 CY
COMPACTING EMB. = 1934 CY
DISPOSE OF APPROX. 73,200 CY
VPI-545+00.00 EBL
EL 593.55
+4.98%
-4.75%
+3.83%
-3.88%
EXIST. GROUND WBL
EXIST. GROUND EBL
EXIST RTE 60
ROUTE 60 - WBL
SPECIAL DITCH LT.
VPC 539+15
VPT 545+17.37 WBL
EL 588.83
SSD = 400'
1,170' V.C.
SSD = 525'
1,600' V.C.
K = 160
200' V.C.
VPT 551+00.00
VPT 550+85.00
543.2'
537.4'
VPI-552+00.00 EBL
EL 560.30
VPT 553+17.37
STA 553+00.00
END EBL RECONSTRUCTION
-4.75%
-3.50%
SPECIAL DITCH RT.
SPECIAL DITCH LT.
K = 140
200' V.C.
VPC 558+60.21
VPT 560+60.21
VPI 559+60.21
EL 532.90
-3.88%
+3.45%
524.4'
515.7'
EXIST. GROUND WBL
ROUTE 60 - WBL
EXIST RTE 60 - EBL
507.3'
509.2'
566
BENCH MARKS & CONTROL POINTS (USGS DATUM)
NO. | DESCRIPTION | ELEV.
BM #10 | ½" Rebar driven in ground with plastic cap. STA. 525+65.73, 9.32' RT. | 541.96'
BM #9 | ½" Rebar driven in ground with plastic cap. STA. 532+44.08, 8.89' RT. | 544.39'
ROUTE 60 | STATE MO | DISTRICT 9 | SHEET NO. 14
JOB NO. J9P0359D
CONTRACT ID.
PROJECT NO.
COUNTY CARTER
DATE
REV.
t:\de-proj\carter\j9p0359d\plan_sheets\plan\014_profile3_j9p0359D.dgn 12:50:50 PM 02/05/2007


ROUTE 60 | STATE MO | DISTRICT 9 | SHEET NO. 15
JOB NO. J9P0359D
CONTRACT ID.
PROJECT NO.
COUNTY CARTER
DATE
TO STA. 511+10
TO STA. 498+76
STAGE 1 - BALANCE 4
STAGE 2 - BALANCE 8
K = 141
250' V.C.
VPC 570+48.92
VPT 572+98.92
-2.45%
-0.67%
493.9'
498.4'
VPI 571+73.92
EL 508.17
ROUTE 60 - WBL
489.9'
495.5'
SPECIAL DITCH LT.
K = 157
150' V.C.
VPC 581+35.90
VPT 582+85.90
-0.67%
+0.28%
VPI 582+10.90
EL 496.72
487.5'
490.9'
485.7'
489.5'
EXIST. GROUND WBL
EXIST RTE 60 - EBL
487.8'
493.8'
STA. 596+89
STAGE 1 - BALANCE 5
TO STA. 632+56.52
TO STA. 616+00
VPI 598+54.83
EL 500.87
+0.28%
-1%
VPC 597+67.33
SSD = 605'
175' V.C.
TO STA. 596+89
STAGE 1 - BALANCE 5
CLASS A EXCAVATION = 15,515 CY
COMPACTING EMB. = 13,490 CY
EMBANKMENT IN PLACE = 37,120 CY
TO STA. 632+56.52
TO STA. 498+76
STAGE 2 - BALANCE 8
K = 141
250' V.C.
VPC 601+63.71
VPT 603+13.71
-1.00%
+0.77%
VPT 599+42.33
VPI 601+68.71
EL 497.53
487.6'
489.5'
EXIST. RTE 60 - EBL
ROUTE 60 - WBL
494.9'
497.3'
SPECIAL DITCH LT.
VPI 614+90.81
EL 507.57
STA. 616+00
+0.77%
-0.33%
VPC 614+20.81
SSD = 674'
140' V.C.
VPT 615+60.81
494.0'
496.5'
ROUTE 60 - WBL
493.9'
498.5'
EXIST. GROUND WBL
490.2'
482.2'
SPECIAL DITCH LT.
REV.
t:\de-proj\carter\j9p0359d\plan_sheets\plan\015_profile4_j9p0359D.dgn 12:50:52 PM 02/05/2007


ROUTE 60 STATE MO DISTRICT 9 SHEET NO. 16
JOB NO. J9P0359D
CONTRACT ID.
PROJECT NO.
COUNTY CARTER
DATE
610
600
590
580
570
560
550
540
530
520
510
500
490
480
470
460
450
440
STAGE 1 - BALANCE 5
TO STA. 596+89
ROUTE 60 - EXISTING
EXIST. GROUND WBL
PT ROUTE 60 - WBL
630+11.00
STA 632+56.07
525.41
END WBL RECONSTRUCTION
629 630 631 632 633 634 635 636 637 638 639 640 641 642 643 644 645 646 647 648 649 650 651 652 653 654 655 656 657 658 659
REV.
I:\de-proj\carter\j9p0359d\plan_sheets\plan\016_profile5_j9p0359D.dgn 12:50:54 PM 03/05/2007