

# Route 141–Ladue to Olive

## Summary of Impacts

	Alternate A (Green)	Alternate B (Red)	Alternate E (Blue)
<b>Displacements</b>			
Residential	64	8	5
Commercial	23	1	—
<b>Cost</b>			
Construction	\$48,430,000	\$59,453,000	\$76,507,000
Right of Way	\$51,168,000	\$15,189,000	\$15,651,000
Total Cost	\$99,598,000	\$74,642,000	\$92,158,000
<b>Wetland Impacts (Acres)</b>			
Emergent	0.3	0.3	0.3
Forested	4.9	12.0	8.1
Scrub-shrub	0.4	0.4	0.4
Total Wetlands	5.6	12.6	8.7
<b>Floodplain Impacts (Acres)</b>			
Floodplain	27.7	57.6	53.6
Floodway	14.9	33.4	27.7
<b>Cultural Resource Impacts</b>			
Right of Way Needed (Acres)	110	130	130
No. of Architectural Resources	3	2	2
No. of Archaeological Resources*	5	7	7
Potential Section 4(f) Properties	1	1	2
<b>Hazardous Waste Sites</b>	2	—	—
<b>Preferred Alternate</b>		✓	

\*Estimated number of sites